

LEARN PYTHON THE RIGHT WAY



HOW TO THINK LIKE A
COMPUTER SCIENTIST



Ritza

Marketing as Education

Learn Python the right way

How to think like a computer scientist

Ritza

© 2021 Ritza

Contents

Copyright Notice	1
Foreword	2
Preface	4
How and why I came to use Python	4
Finding a textbook	5
Introducing programming with Python	6
Building a community	7
Contributor List	8
Second Edition	8
First Edition	9
Chapter 1: The way of the program	11
1.1. The Python programming language	11
1.2. What is a program?	13
1.3. What is debugging?	13
1.4. Syntax errors	14
1.5. Runtime errors	14
1.6. Semantic errors	14
1.7. Experimental debugging	14
1.8. Formal and natural languages	15
1.9. The first program	17
1.10. Comments	18
1.11. Glossary	18
1.12. Exercises	20
Chapter 2: Variables, expressions and statements	23
2.1. Values and data types	23
2.2. Variables	25
2.3. Variable names and keywords	27
2.4. Statements	28
2.5. Evaluating expressions	28
2.6. Operators and operands	29

CONTENTS

2.7. Type converter functions	30
2.8. Order of operations	31
2.9. Operations on strings	32
2.10. Input	33
2.11. Composition	34
2.12. The modulus operator	35
2.13. Glossary	35
2.14. Exercises	38
Chapter 3: Hello, little turtles!	40
3.1. Our first turtle program	40
3.2. Instances — a herd of turtles	43
3.3. The for loop	45
3.4. Flow of Execution of the for loop	46
3.5. The loop simplifies our turtle program	47
3.6. A few more turtle methods and tricks	49
3.7. Glossary	52
3.8. Exercises	53
Chapter 4: Functions	56
4.1. Functions	56
4.2. Functions can call other functions	59
4.3. Flow of execution	60
4.4. Functions that require arguments	63
4.5. Functions that return values	63
4.6. Variables and parameters are local	65
4.7. Turtles Revisited	66
4.8. Glossary	67
4.9. Exercises	69
Chapter 5: Conditionals	73
5.1. Boolean values and expressions	73
5.2. Logical operators	74
5.3. Truth Tables	75
5.4. Simplifying Boolean Expressions	75
5.5. Conditional execution	76
5.6. Omitting the else clause	78
5.7. Chained conditionals	79
5.8. Nested conditionals	81
5.9. The return statement	82
5.10. Logical opposites	82
5.11. Type conversion	84
5.12. A Turtle Bar Chart	85
5.13. Glossary	89

CONTENTS

5.14. Exercises	90
Chapter 6: Fruitful functions	93
6.1. Return values	93
6.2. Program development	95
6.3. Debugging with print	98
6.4. Composition	98
6.5. Boolean functions	99
6.6. Programming with style	100
6.7. Unit testing	101
6.8. Glossary	103
6.9. Exercises	104
Chapter 7: Iteration	109
7.1. Assignment	109
7.2. Updating variables	110
7.3. The for loop revisited	111
7.4. The while statement	111
7.5. The Collatz $3n + 1$ sequence	113
7.6. Tracing a program	115
7.7. Counting digits	116
7.8. Abbreviated assignment	117
7.9. Help and meta-notation	118
7.10. Tables	120
7.11. Two-dimensional tables	121
7.12. Encapsulation and generalization	122
7.13. More encapsulation	123
7.14. Local variables	123
7.15. The break statement	124
7.16. Other flavours of loops	125
7.17. An example	127
7.18. The continue statement	128
7.19. More generalization	129
7.20. Functions	130
7.21. Paired Data	131
7.22. Nested Loops for Nested Data	132
7.23. Newton's method for finding square roots	133
7.24. Algorithms	134
7.25. Glossary	135
7.26. Exercises	137
Chapter 8: Strings	142
8.1. A compound data type	142
8.2. Working with strings as single things	142

CONTENTS

8.3. Working with the parts of a string	144
8.4. Length	145
8.5. Traversal and the for loop	145
8.6. Slices	146
8.7. String comparison	147
8.8. Strings are immutable	148
8.9. The in and not in operators	148
8.10. A find function	149
8.11. Looping and counting	150
8.12. Optional parameters	150
8.13. The built-in find method	152
8.14. The split method	152
8.15. Cleaning up your strings	153
8.16. The string format method	154
8.17. Summary	157
8.18. Glossary	158
8.19. Exercises	159
Chapter 9: Tuples	164
9.1. Tuples are used for grouping data	164
9.2. Tuple assignment	165
9.3. Tuples as return values	166
9.4. Composability of Data Structures	167
9.5. Glossary	167
9.6. Exercises	168
Chapter 10: Event handling	169
10.1. Event-driven programming	169
10.2. Keypress events	169
10.3. Mouse events	170
10.4. Automatic events from a timer	172
10.5. An example: state machines	173
10.6. Glossary	176
10.7. Exercises	176
Chapter 11: Lists	179
11.1. List values	179
11.2. Accessing elements	179
11.3. List length	180
11.4. List membership	181
11.5. List operations	182
11.6. List slices	182
11.7. Lists are mutable	182
11.8. List deletion	184

CONTENTS

11.9. Objects and references	184
11.10. Aliasing	185
11.11. Cloning lists	186
11.12. Lists and for loops	187
11.13. List parameters	188
11.14. List methods	189
11.15. Pure functions and modifiers	190
11.16. Functions that produce lists	191
11.17. Strings and lists	192
11.18. list and range	193
11.19. Nested lists	194
11.20. Matrices	195
11.21. Glossary	195
11.22. Exercises	197
Chapter 12: Modules	201
12.1. Random numbers	201
12.2. The time module	204
12.3. The math module	205
12.4. Creating your own modules	206
12.5. Namespaces	207
12.6. Scope and lookup rules	209
12.7. Attributes and the dot operator	210
12.8. Three import statement variants	211
12.9. Turn your unit tester into a module	212
12.10. Glossary	212
12.11. Exercises	213
Chapter 13: Files	218
13.1. About files	218
13.2. Writing our first file	218
13.3. Reading a file line-at-a-time	219
13.4. Turning a file into a list of lines	220
13.5. Reading the whole file at once	221
13.6. Working with binary files	221
13.7. An example	222
13.8. Directories	223
13.9. What about fetching something from the web?	224
13.10. Glossary	225
13.11. Exercises	226
Chapter 14: List Algorithms	227
14.1. Test-driven development	227
14.2. The linear search algorithm	227

CONTENTS

14.3. A more realistic problem	229
14.4. Binary Search	233
14.5. Removing adjacent duplicates from a list	237
14.6. Merging sorted lists	238
14.7. Alice in Wonderland, again!	240
14.8. Eight Queens puzzle, part 1	242
14.9. Eight Queens puzzle, part 2	246
14.10. Glossary	248
14.11. Exercises	249
Chapter 15: Classes and Objects — the Basics	253
15.1. Object-oriented programming	253
15.2. User-defined compound data types	253
15.3. Attributes	255
15.4. Improving our initializer	256
15.5. Adding other methods to our class	257
15.6. Instances as arguments and parameters	259
15.7. Converting an instance to a string	259
15.8. Instances as return values	260
15.9. A change of perspective	262
15.10. Objects can have state	262
15.11. Glossary	263
15.12. Exercises	264
Chapter 16: Classes and Objects — Digging a little deeper	266
16.1. Rectangles	266
16.2. Objects are mutable	267
16.3. Sameness	268
16.4. Copying	270
16.5. Glossary	271
16.6. Exercises	272
Chapter 17: PyGame	274
17.1. The game loop	274
17.2. Displaying images and text	278
17.3. Drawing a board for the N queens puzzle	281
17.4. Sprites	287
17.5. Events	291
17.6. A wave of animation	294
17.7. Aliens - a case study	299
17.8. Reflections	300
17.9. Glossary	300
17.10. Exercises	301

CONTENTS

Chapter 18: Recursion	302
18.1. Drawing Fractals	302
18.2. Recursive data structures	305
18.3. Processing recursive number lists	306
18.4. Case study: Fibonacci numbers	308
18.5. Example with recursive directories and files	309
18.6. An animated fractal, using PyGame	310
18.7. Glossary	313
18.8. Exercises	314
Chapter 19: Exceptions	318
19.1. Catching exceptions	318
19.2. Raising our own exceptions	320
19.3. Revisiting an earlier example	321
19.4. The <code>finally</code> clause of the <code>try</code> statement	321
19.5. Glossary	322
19.6. Exercises	323
Chapter 20: Dictionaries	324
20.1. Dictionary operations	325
20.2. Dictionary methods	326
20.3. Aliasing and copying	328
20.4. Sparse matrices	329
20.5. Memoization	330
20.6. Counting letters	331
20.7. Glossary	332
20.8. Exercises	333
Chapter 21: A Case Study: Indexing your files	336
21.1. The Crawler	336
21.2. Saving the dictionary to disk	339
21.3. The Query Program	339
21.4. Compressing the serialized dictionary	341
21.5. Glossary	342
Chapter 22: Even more OOP	343
22.1. MyTime	343
22.2. Pure functions	343
22.3. Modifiers	345
22.4. Converting increment to a method	346
22.5. An “Aha!” insight	346
22.6. Generalization	348
22.7. Another example	349
22.8. Operator overloading	350

CONTENTS

22.9. Polymorphism	352
22.10. Glossary	353
22.11. Exercises	354
Chapter 23: Collections of objects	356
23.1. Composition	356
23.2. Card objects	356
23.3. Class attributes and the <code>__str__</code> method	357
23.4. Comparing cards	359
23.5. Decks	361
23.6. Printing the deck	361
23.7. Shuffling the deck	363
23.8. Removing and dealing cards	364
23.9. Glossary	365
23.10. Exercises	365
Chapter 24: Inheritance	366
24.1. Inheritance	366
24.2. A hand of cards	366
24.3. Dealing cards	367
24.4. Printing a Hand	368
24.5. The <code>CardGame</code> class	369
24.6. <code>OldMaidHand</code> class	370
24.7. <code>OldMaidGame</code> class	371
24.8. Glossary	375
24.9. Exercises	376
Chapter 25: Linked lists	377
25.1. Embedded references	377
25.2. The <code>Node</code> class	377
25.3. Lists as collections	378
25.4. Lists and recursion	379
25.5. Infinite lists	380
25.6. The fundamental ambiguity theorem	381
25.7. Modifying lists	382
25.8. Wrappers and helpers	383
25.9. The <code>LinkedList</code> class	383
25.10. Invariants	385
25.11. Glossary	385
25.12. Exercises	386
Chapter 26: Stacks	387
26.1. Abstract data types	387
26.2. The <code>Stack</code> ADT	387

CONTENTS

26.3. Implementing stacks with Python lists	388
26.4. Pushing and popping	389
26.5. Using a stack to evaluate postfix	389
26.6. Parsing	390
26.7. Evaluating postfix	390
26.8. Clients and providers	391
26.9. Glossary	392
26.10. Exercises	393
Chapter 27: Queues	394
27.1. The Queue ADT	394
27.2. Linked Queue	394
27.3. Performance characteristics	396
27.4. Improved Linked Queue	396
27.5. Priority queue	397
27.6. The Golfer class	399
27.7. Glossary	400
27.8. Exercises	401
Chapter 28: Trees	402
28.1. Building trees	403
28.2. Traversing trees	403
28.3. Expression trees	404
28.4. Tree traversal	405
28.5. Building an expression tree	406
28.6. Handling errors	410
28.7. The animal tree	411
28.8. Glossary	413
28.9. Exercises	414
Appendix A: Debugging	415
A.1. Syntax errors	415
A.2. I can't get my program to run no matter what I do.	416
A.3. Runtime errors	416
A.4. My program does absolutely nothing.	417
A.5. My program hangs.	417
A.6. Infinite Loop	417
A.7. Infinite Recursion	418
A.8. Flow of Execution	418
A.9. When I run the program I get an exception.	419
A.10. I added so many print statements I get inundated with output.	420
A.11. Semantic errors	420
A.12. My program doesn't work.	421
A.13. I've got a big hairy expression and it doesn't do what I expect.	422

CONTENTS

A.14. I've got a function or method that doesn't return what I expect.	422
A.15. I'm really, really stuck and I need help.	423
A.16. No, I really need help.	423
Appendix B: An odds-and-ends Workbook	425
B.1. The Five Strands of Proficiency	425
B.2. Sending Email	426
B.3. Write your own Web Server	427
B.4. Using a Database	429
Appendix C: Configuring Ubuntu for Python Development	432
C.1. Vim	432
C.2. \$HOME environment	433
C.3. Making a Python script executable and runnable from anywhere	434
Appendix D: Customizing and Contributing to the Book	435
D.1. Getting the Source	435
D.2. Making the HTML Version	436
Appendix E: Some Tips, Tricks, and Common Errors	437
E.1. Functions	437
E.2. Problems with logic and flow of control	438
E.3. Local variables	440
E.4. Event handler functions	441
E.5. String handling	441
E.6. Looping and lists	443

Copyright Notice

Copyright (C) Peter Wentworth, Jeffrey Elkner, Allen B. Downey and Chris Meyers. Permission is granted to copy, distribute and/or modify this document under the terms of the GNU Free Documentation License, Version 1.3 or any later version published by the Free Software Foundation; with Invariant Sections being Foreword, Preface, and Contributor List, no Front-Cover Texts, and no Back-Cover Texts. A copy of the license is included in the section entitled “GNU Free Documentation License”.

Foreword

By David Beazley

As an educator, researcher, and book author, I am delighted to see the completion of this book. Python is a fun and extremely easy-to-use programming language that has steadily gained in popularity over the last few years. Developed over ten years ago by Guido van Rossum, Python's simple syntax and overall feel is largely derived from ABC, a teaching language that was developed in the 1980's. However, Python was also created to solve real problems and it borrows a wide variety of features from programming languages such as C++, Java, Modula-3, and Scheme. Because of this, one of Python's most remarkable features is its broad appeal to professional software developers, scientists, researchers, artists, and educators.

Despite Python's appeal to many different communities, you may still wonder why Python? or why teach programming with Python? Answering these questions is no simple task—especially when popular opinion is on the side of more masochistic alternatives such as C++ and Java. However, I think the most direct answer is that programming in Python is simply a lot of fun and more productive.

When I teach computer science courses, I want to cover important concepts in addition to making the material interesting and engaging to students. Unfortunately, there is a tendency for introductory programming courses to focus far too much attention on mathematical abstraction and for students to become frustrated with annoying problems related to low-level details of syntax, compilation, and the enforcement of seemingly arcane rules. Although such abstraction and formalism is important to professional software engineers and students who plan to continue their study of computer science, taking such an approach in an introductory course mostly succeeds in making computer science boring. When I teach a course, I don't want to have a room of uninspired students. I would much rather see them trying to solve interesting problems by exploring different ideas, taking unconventional approaches, breaking the rules, and learning from their mistakes. In doing so, I don't want to waste half of the semester trying to sort out obscure syntax problems, unintelligible compiler error messages, or the several hundred ways that a program might generate a general protection fault.

One of the reasons why I like Python is that it provides a really nice balance between the practical and the conceptual. Since Python is interpreted, beginners can pick up the language and start doing neat things almost immediately without getting lost in the problems of compilation and linking. Furthermore, Python comes with a large library of modules that can be used to do all sorts of tasks ranging from web-programming to graphics. Having such a practical focus is a great way to engage students and it allows them to complete significant projects. However, Python can also serve as an excellent foundation for introducing important computer science concepts. Since Python fully supports procedures and classes, students can be gradually introduced to topics such as procedural abstraction, data structures, and object-oriented programming — all of which are applicable to later

courses on Java or C++. Python even borrows a number of features from functional programming languages and can be used to introduce concepts that would be covered in more detail in courses on Scheme and Lisp.

In reading Jeffrey's preface, I am struck by his comments that Python allowed him to see a higher level of success and a lower level of frustration and that he was able to move faster with better results. Although these comments refer to his introductory course, I sometimes use Python for these exact same reasons in advanced graduate level computer science courses at the University of Chicago. In these courses, I am constantly faced with the daunting task of covering a lot of difficult course material in a blistering nine week quarter. Although it is certainly possible for me to inflict a lot of pain and suffering by using a language like C++, I have often found this approach to be counterproductive—especially when the course is about a topic unrelated to just programming. I find that using Python allows me to better focus on the actual topic at hand while allowing students to complete substantial class projects.

Although Python is still a young and evolving language, I believe that it has a bright future in education. This book is an important step in that direction. David Beazley University of Chicago
Author of the Python Essential Reference

Preface

By Jeffrey Elkner

This book owes its existence to the collaboration made possible by the Internet and the free software movement. Its three authors—a college professor, a high school teacher, and a professional programmer—never met face to face to work on it, but we have been able to collaborate closely, aided by many other folks who have taken the time and energy to send us their feedback.

We think this book is a testament to the benefits and future possibilities of this kind of collaboration, the framework for which has been put in place by Richard Stallman and the Free Software Foundation.

How and why I came to use Python

In 1999, the College Board’s Advanced Placement (AP) Computer Science exam was given in C++ for the first time. As in many high schools throughout the country, the decision to change languages had a direct impact on the computer science curriculum at Yorktown High School in Arlington, Virginia, where I teach. Up to this point, Pascal was the language of instruction in both our first-year and AP courses. In keeping with past practice of giving students two years of exposure to the same language, we made the decision to switch to C++ in the first year course for the 1997-98 school year so that we would be in step with the College Board’s change for the AP course the following year.

Two years later, I was convinced that C++ was a poor choice to use for introducing students to computer science. While it is certainly a very powerful programming language, it is also an extremely difficult language to learn and teach. I found myself constantly fighting with C++’s difficult syntax and multiple ways of doing things, and I was losing many students unnecessarily as a result. Convinced there had to be a better language choice for our first-year class, I went looking for an alternative to C++.

I needed a language that would run on the machines in our GNU/Linux lab as well as on the Windows and Macintosh platforms most students have at home. I wanted it to be free software, so that students could use it at home regardless of their income. I wanted a language that was used by professional programmers, and one that had an active developer community around it. It had to support both procedural and object-oriented programming. And most importantly, it had to be easy to learn and teach. When I investigated the choices with these goals in mind, Python stood out as the best candidate for the job.

I asked one of Yorktown’s talented students, Matt Ahrens, to give Python a try. In two months he not only learned the language but wrote an application called pyTicket that enabled our staff to report technology problems via the Web. I knew that Matt could not have finished an application of that

scale in so short a time in C++, and this accomplishment, combined with Matt's positive assessment of Python, suggested that Python was the solution I was looking for.

Finding a textbook

Having decided to use Python in both of my introductory computer science classes the following year, the most pressing problem was the lack of an available textbook.

Free documents came to the rescue. Earlier in the year, Richard Stallman had introduced me to Allen Downey. Both of us had written to Richard expressing an interest in developing free educational materials. Allen had already written a first-year computer science textbook, *How to Think Like a Computer Scientist*. When I read this book, I knew immediately that I wanted to use it in my class. It was the clearest and most helpful computer science text I had seen. It emphasized the processes of thought involved in programming rather than the features of a particular language. Reading it immediately made me a better teacher.

How to Think Like a Computer Scientist was not just an excellent book, but it had been released under the GNU public license, which meant it could be used freely and modified to meet the needs of its user. Once I decided to use Python, it occurred to me that I could translate Allen's original Java version of the book into the new language. While I would not have been able to write a textbook on my own, having Allen's book to work from made it possible for me to do so, at the same time demonstrating that the cooperative development model used so well in software could also work for educational materials.

Working on this book for the last two years has been rewarding for both my students and me, and my students played a big part in the process. Since I could make instant changes whenever someone found a spelling error or difficult passage, I encouraged them to look for mistakes in the book by giving them a bonus point each time they made a suggestion that resulted in a change in the text. This had the double benefit of encouraging them to read the text more carefully and of getting the text thoroughly reviewed by its most important critics, students using it to learn computer science.

For the second half of the book on object-oriented programming, I knew that someone with more real programming experience than I had would be needed to do it right. The book sat in an unfinished state for the better part of a year until the open source community once again provided the needed means for its completion.

I received an email from Chris Meyers expressing interest in the book. Chris is a professional programmer who started teaching a programming course last year using Python at Lane Community College in Eugene, Oregon. The prospect of teaching the course had led Chris to the book, and he started helping out with it immediately. By the end of the school year he had created a companion project on our Website at <http://openbookproject.net> called *Python for Fun* and was working with some of my most advanced students as a master teacher, guiding them beyond where I could take them.

Introducing programming with Python

The process of translating and using *How to Think Like a Computer Scientist* for the past two years has confirmed Python's suitability for teaching beginning students. Python greatly simplifies programming examples and makes important programming ideas easier to teach.

The first example from the text illustrates this point. It is the traditional `hello, world` program, which in the Java version of the book looks like this:

```
1  class Hello {  
2  
3      public static void main (String[] args) {  
4          System.out.println ("Hello, world.");  
5      }  
6  }
```

in the Python version it becomes:

```
1  print("Hello, World!")
```

Even though this is a trivial example, the advantages of Python stand out. Yorktown's Computer Science I course has no prerequisites, so many of the students seeing this example are looking at their first program. Some of them are undoubtedly a little nervous, having heard that computer programming is difficult to learn. The Java version has always forced me to choose between two unsatisfying options: either to explain the `class Hello`, `public static void main`, `String[] args`, statements and risk confusing or intimidating some of the students right at the start, or to tell them, Just don't worry about all of that stuff now; we will talk about it later, and risk the same thing. The educational objectives at this point in the course are to introduce students to the idea of a programming statement and to get them to write their first program, thereby introducing them to the programming environment. The Python program has exactly what is needed to do these things, and nothing more.

Comparing the explanatory text of the program in each version of the book further illustrates what this means to the beginning student. There are seven paragraphs of explanation of `Hello, world!` in the Java version; in the Python version, there are only a few sentences. More importantly, the missing six paragraphs do not deal with the big ideas in computer programming but with the minutia of Java syntax. I found this same thing happening throughout the book. Whole paragraphs simply disappear from the Python version of the text because Python's much clearer syntax renders them unnecessary.

Using a very high-level language like Python allows a teacher to postpone talking about low-level details of the machine until students have the background that they need to better make sense of the details. It thus creates the ability to put first things first pedagogically. One of the best examples of this is the way in which Python handles variables. In Java a variable is a name for a place that

holds a value if it is a built-in type, and a reference to an object if it is not. Explaining this distinction requires a discussion of how the computer stores data. Thus, the idea of a variable is bound up with the hardware of the machine. The powerful and fundamental concept of a variable is already difficult enough for beginning students (in both computer science and algebra). Bytes and addresses do not help the matter. In Python a variable is a name that refers to a thing. This is a far more intuitive concept for beginning students and is much closer to the meaning of variable that they learned in their math courses. I had much less difficulty teaching variables this year than I did in the past, and I spent less time helping students with problems using them.

Another example of how Python aids in the teaching and learning of programming is in its syntax for functions. My students have always had a great deal of difficulty understanding functions. The main problem centers around the difference between a function definition and a function call, and the related distinction between a parameter and an argument. Python comes to the rescue with syntax that is nothing short of beautiful. Function definitions begin with the keyword `def`, so I simply tell my students, When you define a function, begin with `def`, followed by the name of the function that you are defining; when you call a function, simply call (type) out its name. Parameters go with definitions; arguments go with calls. There are no return types, parameter types, or reference and value parameters to get in the way, so I am now able to teach functions in less than half the time that it previously took me, with better comprehension.

Using Python improved the effectiveness of our computer science program for all students. I saw a higher general level of success and a lower level of frustration than I experienced teaching with either C++ or Java. I moved faster with better results. More students left the course with the ability to create meaningful programs and with the positive attitude toward the experience of programming that this engenders.

Building a community

I have received emails from all over the globe from people using this book to learn or to teach programming. A user community has begun to emerge, and many people have been contributing to the project by sending in materials for the companion Website at <http://openbookproject.net/pybiblio>.

With the continued growth of Python, I expect the growth in the user community to continue and accelerate. The emergence of this user community and the possibility it suggests for similar collaboration among educators have been the most exciting parts of working on this project for me. By working together, we can increase the quality of materials available for our use and save valuable time. I invite you to join our community and look forward to hearing from you. Please write to me at jeff@elkner.net.

Jeffrey Elkner
Governor's Career and Technical Academy in Arlington
Arlington, Virginia

Contributor List

To paraphrase the philosophy of the Free Software Foundation, this book is free like free speech, but not necessarily free like free pizza. It came about because of a collaboration that would not have been possible without the GNU Free Documentation License. So we would like to thank the Free Software Foundation for developing this license and, of course, making it available to us.

We would also like to thank the more than 100 sharp-eyed and thoughtful readers who have sent us suggestions and corrections over the past few years. In the spirit of free software, we decided to express our gratitude in the form of a contributor list. Unfortunately, this list is not complete, but we are doing our best to keep it up to date. It was also getting too large to include everyone who sends in a typo or two. You have our gratitude, and you have the personal satisfaction of making a book you found useful better for you and everyone else who uses it. New additions to the list for the 2nd edition will be those who have made on-going contributions.

If you have a chance to look through the list, you should realize that each person here has spared you and all subsequent readers from the confusion of a technical error or a less-than-transparent explanation, just by sending us a note.

Impossible as it may seem after so many corrections, there may still be errors in this book. If you should stumble across one, we hope you will take a minute to contact us. The email address (for the Python 3 version of the book) is p.wentworth@ru.ac.za. Substantial changes made due to your suggestions will add you to the next version of the contributor list (unless you ask to be omitted). Thank you!

Second Edition

- An email from Mike MacHenry set me straight on tail recursion. He not only pointed out an error in the presentation, but suggested how to correct it.
- It wasn't until 5th Grade student Owen Davies came to me in a Saturday morning Python enrichment class and said he wanted to write the card game, Gin Rummy, in Python that I finally knew what I wanted to use as the case study for the object oriented programming chapters.
- A special thanks to pioneering students in Jeff's Python Programming class at GCTAA during the 2009-2010 school year: Safath Ahmed, Howard Batiste, Louis Elkner-Alfaro, and Rachel Hancock. Your continual and thoughtful feedback led to changes in most of the chapters of the book. You set the standard for the active and engaged learners that will help make the new Governor's Academy what it is to become. Thanks to you this is truly a student tested text.
- Thanks in a similar vein to the students in Jeff's Computer Science class at the HB-Woodlawn program during the 2007-2008 school year: James Crowley, Joshua Eddy, Eric Larson, Brian McGrail, and Iliana Vazuka.

- Ammar Nabulsi sent in numerous corrections from Chapters 1 and 2.
- Aldric Giacomoni pointed out an error in our definition of the Fibonacci sequence in Chapter 5.
- Roger Sperberg sent in several spelling corrections and pointed out a twisted piece of logic in Chapter 3.
- Adele Goldberg sat down with Jeff at PyCon 2007 and gave him a list of suggestions and corrections from throughout the book.
- Ben Bruno sent in corrections for chapters 4, 5, 6, and 7.
- Carl LaCombe pointed out that we incorrectly used the term commutative in chapter 6 where symmetric was the correct term.
- Alessandro Montanile sent in corrections for errors in the code examples and text in chapters 3, 12, 15, 17, 18, 19, and 20.
- Emanuele Rusconi found errors in chapters 4, 8, and 15.
- Michael Vogt reported an indentation error in an example in chapter 6, and sent in a suggestion for improving the clarity of the shell vs. script section in chapter 1.

First Edition

- Lloyd Hugh Allen sent in a correction to Section 8.4.
- Yvon Boulianne sent in a correction of a semantic error in Chapter 5.
- Fred Bremmer submitted a correction in Section 2.1.
- Jonah Cohen wrote the Perl scripts to convert the LaTeX source for this book into beautiful HTML.
- Michael Conlon sent in a grammar correction in Chapter 2 and an improvement in style in Chapter 1, and he initiated discussion on the technical aspects of interpreters.
- Benoit Girard sent in a correction to a humorous mistake in Section 5.6.
- Courtney Gleason and Katherine Smith wrote horsebet.py, which was used as a case study in an earlier version of the book. Their program can now be found on the website.
- Lee Harr submitted more corrections than we have room to list here, and indeed he should be listed as one of the principal editors of the text.
- James Kaylin is a student using the text. He has submitted numerous corrections.
- David Kershaw fixed the broken catTwice function in Section 3.10.
- Eddie Lam has sent in numerous corrections to Chapters 1, 2, and 3. He also fixed the Makefile so that it creates an index the first time it is run and helped us set up a versioning scheme.
- Man-Yong Lee sent in a correction to the example code in Section 2.4.
- David Mayo pointed out that the word unconsciously in Chapter 1 needed to be changed to subconsciously .
- Chris McAloon sent in several corrections to Sections 3.9 and 3.10.
- Matthew J. Moelter has been a long-time contributor who sent in numerous corrections and suggestions to the book.
- Simon Dicon Montford reported a missing function definition and several typos in Chapter 3. He also found errors in the increment function in Chapter 13.

- John Ouzts corrected the definition of return value in Chapter 3.
- Kevin Parks sent in valuable comments and suggestions as to how to improve the distribution of the book.
- David Pool sent in a typo in the glossary of Chapter 1, as well as kind words of encouragement.
- Michael Schmitt sent in a correction to the chapter on files and exceptions.
- Robin Shaw pointed out an error in Section 13.1, where the `printTime` function was used in an example without being defined.
- Paul Sleigh found an error in Chapter 7 and a bug in Jonah Cohen's Perl script that generates HTML from LaTeX.
- Craig T. Snyder is testing the text in a course at Drew University. He has contributed several valuable suggestions and corrections.
- Ian Thomas and his students are using the text in a programming course. They are the first ones to test the chapters in the latter half of the book, and they have made numerous corrections and suggestions.
- Keith Verheyden sent in a correction in Chapter 3.
- Peter Winstanley let us know about a longstanding error in our Latin in Chapter 3.
- Chris Wrobel made corrections to the code in the chapter on file I/O and exceptions.
- Moshe Zadka has made invaluable contributions to this project. In addition to writing the first draft of the chapter on Dictionaries, he provided continual guidance in the early stages of the book.
- Christoph Zwerschke sent several corrections and pedagogic suggestions, and explained the difference between `gleich` and `selbe`.
- James Mayer sent us a whole slew of spelling and typographical errors, including two in the contributor list.
- Hayden McAfee caught a potentially confusing inconsistency between two examples.
- Angel Arnal is part of an international team of translators working on the Spanish version of the text. He has also found several errors in the English version.
- Tauhidul Hoque and Lex Berezhny created the illustrations in Chapter 1 and improved many of the other illustrations.
- Dr. Michele Alzetta caught an error in Chapter 8 and sent some interesting pedagogic comments and suggestions about Fibonacci and Old Maid.
- Andy Mitchell caught a typo in Chapter 1 and a broken example in Chapter 2.
- Kalin Harvey suggested a clarification in Chapter 7 and caught some typos.
- Christopher P. Smith caught several typos and is helping us prepare to update the book for Python 2.2.
- David Hutchins caught a typo in the Foreword.
- Gregor Lingl is teaching Python at a high school in Vienna, Austria. He is working on a German translation of the book, and he caught a couple of bad errors in Chapter 5.
- Julie Peters caught a typo in the Preface.

Chapter 1: The way of the program

(Watch a video based on this chapter [here on YouTube¹](https://youtu.be/lhtUREG6vAg).)

The goal of this book is to teach you to think like a computer scientist. This way of thinking combines some of the best features of mathematics, engineering, and natural science. Like mathematicians, computer scientists use formal languages to denote ideas (specifically computations). Like engineers, they design things, assembling components into systems and evaluating tradeoffs among alternatives. Like scientists, they observe the behavior of complex systems, form hypotheses, and test predictions.

The single most important skill for a computer scientist is **problem solving**. Problem solving means the ability to formulate problems, think creatively about solutions, and express a solution clearly and accurately. As it turns out, the process of learning to program is an excellent opportunity to practice problem-solving skills. That's why this chapter is called, The way of the program.

On one level, you will be learning to program, a useful skill by itself. On another level, you will use programming as a means to an end. As we go along, that end will become clearer.

1.1. The Python programming language

The programming language you will be learning is Python. Python is an example of a high-level language; other **high-level languages** you might have heard of are C++, PHP, Pascal, C#, and Java.

As you might infer from the name high-level language, there are also **low-level languages**, sometimes referred to as machine languages or assembly languages. Loosely speaking, computers can only execute programs written in low-level languages. Thus, programs written in a high-level language have to be translated into something more suitable before they can run.


Almost all programs are written in high-level languages because of their advantages. It is much easier to program in a high-level language so programs take less time to write, they are shorter and easier to read, and they are more likely to be correct. Second, high-level languages are **portable**, meaning that they can run on different kinds of computers with few or no modifications.

In this edition of the textbook, we use an online programming environment called **Replit**. To follow along with the examples and complete the exercises, all you need is a free account - just navigate to <https://replit.com> and complete the sign up process.

Once you have an account, create a new repl and choose Python as the language from the dropdown. You'll see it automatically creates a file called `main.py`. By convention, files that contain Python programs have names that end with `.py`.

¹<https://youtu.be/lhtUREG6vAg>


The engine that translates and runs Python is called the **Python Interpreter**: There are two ways to use it: *immediate mode* and *script mode*. In immediate mode, you type Python expressions into the Python Interpreter window, and the interpreter immediately shows the result:



Running code in the interpreter (immediate mode)

The `>>>` or `>` is called the **Python prompt**. The interpreter uses the prompt to indicate that it is ready for instructions. We typed `2 + 2`, and the interpreter evaluated our expression, and replied `4`, and on the next line it gave a new prompt, indicating that it is ready for more input.

Working directly in the interpreter is convenient for testing short bits of code because you get immediate feedback. Think of it as scratch paper used to help you work out problems. Anything longer than a few lines should be put into a script. Scripts have the advantage that they can be saved to disk, printed, and so on. To create a script, you can enter the code into the middle pane, as shown below



Running code from a file (script mode)

```
1 print("My first program adds two numbers")
2 print(2+3)
```

To execute the program, click the **Run** button in Replit. You're now a computer programmer! Let's take a look at some more theory before we start writing more advanced programs.

1.2. What is a program?

A **program** is a sequence of instructions that specifies how to perform a computation. The computation might be something mathematical, such as solving a system of equations or finding the roots of a polynomial, but it can also be a symbolic computation, such as searching and replacing text in a document or (strangely enough) compiling a program.

The details look different in different languages, but a few basic instructions appear in just about every language:

input

- Get data from the keyboard, a file, or some other device.

output

- Display data on the screen or send data to a file or other device.

math

- Perform basic mathematical operations like addition and multiplication.

conditional execution

- Check for certain conditions and execute the appropriate sequence of statements.

repetition

- Perform some action repeatedly, usually with some variation.

Believe it or not, that's pretty much all there is to it. Every program you've ever used, no matter how complicated, is made up of instructions that look more or less like these. Thus, we can describe programming as the process of breaking a large, complex task into smaller and smaller subtasks until the subtasks are simple enough to be performed with sequences of these basic instructions.

That may be a little vague, but we will come back to this topic later when we talk about **algorithms**.

1.3. What is debugging?

Programming is a complex process, and because it is done by human beings, it often leads to errors. Programming errors are called **bugs** and the process of tracking them down and correcting them is called **debugging**. Use of the term bug to describe small engineering difficulties dates back to at least 1889, when Thomas Edison had a bug with his phonograph.

Three kinds of errors can occur in a program: [syntax errors](https://en.wikipedia.org/wiki/Syntax_error)², [runtime errors](https://en.wikipedia.org/wiki/Runtime_(program_lifecycle_phase))³, and [semantic errors](https://en.wikipedia.org/wiki/Logic_error)⁴.

²https://en.wikipedia.org/wiki/Syntax_error

³[https://en.wikipedia.org/wiki/Runtime_\(program_lifecycle_phase\)](https://en.wikipedia.org/wiki/Runtime_(program_lifecycle_phase))

⁴https://en.wikipedia.org/wiki/Logic_error

It is useful to distinguish between them in order to track them down more quickly.

1.4. Syntax errors

Python can only execute a program if the program is syntactically correct; otherwise, the process fails and returns an error message. **Syntax** refers to the structure of a program and the rules about that structure. For example, in English, a sentence must begin with a capital letter and end with a period. this sentence contains a **syntax error**. So does this one

For most readers, a few syntax errors are not a significant problem, which is why we can read the poetry of E. E. Cummings without problems. Python is not so forgiving. If there is a single syntax error anywhere in your program, Python will display an error message and quit, and you will not be able to run your program. During the first few weeks of your programming career, you will probably spend a lot of time tracking down syntax errors. As you gain experience, though, you will make fewer errors and find them faster.

1.5. Runtime errors

The second type of error is a runtime error, so called because the error does not appear until you run the program. These errors are also called **exceptions** because they usually indicate that something exceptional (and bad) has happened.

Runtime errors are rare in the simple programs you will see in the first few chapters, so it might be a while before you encounter one.

1.6. Semantic errors

The third type of error is the **semantic error**. If there is a semantic error in your program, it will run successfully, in the sense that the computer will not generate any error messages, but it will not do the right thing. It will do something else. Specifically, it will do what you told it to do.

The problem is that the program you wrote is not the program you wanted to write. The meaning of the program (its semantics) is wrong. Identifying semantic errors can be tricky because it requires you to work backward by looking at the output of the program and trying to figure out what it is doing.

1.7. Experimental debugging

One of the most important skills you will acquire is debugging. Although it can be frustrating, debugging is one of the most intellectually rich, challenging, and interesting parts of programming.

In some ways, debugging is like detective work. You are confronted with clues, and you have to infer the processes and events that led to the results you see.

Debugging is also like an experimental science. Once you have an idea what is going wrong, you modify your program and try again. If your hypothesis was correct, then you can predict the result of the modification, and you take a step closer to a working program. If your hypothesis was wrong, you have to come up with a new one. As Sherlock Holmes pointed out, When you have eliminated the impossible, whatever remains, however improbable, must be the truth. (A. Conan Doyle, *The Sign of Four*)

For some people, programming and debugging are the same thing. That is, programming is the process of gradually debugging a program until it does what you want. The idea is that you should start with a program that does something and make small modifications, debugging them as you go, so that you always have a working program.

For example, Linux is an operating system kernel that contains millions of lines of code, but it started out as a simple program Linus Torvalds used to explore the Intel 80386 chip. According to Larry Greenfield, one of Linus's earlier projects was a program that would switch between displaying AAAA and BBBB. This later evolved to Linux (*The Linux Users' Guide* Beta Version 1).

Later chapters will make more suggestions about debugging and other programming practices.

1.8. Formal and natural languages

Natural languages are the languages that people speak, such as English, Spanish, and French. They were not designed by people (although people try to impose some order on them); they evolved naturally.

Formal languages are languages that are designed by people for specific applications. For example, the notation that mathematicians use is a formal language that is particularly good at denoting relationships among numbers and symbols. Chemists use a formal language to represent the chemical structure of molecules. And most importantly:

Programming languages are formal languages that have been designed to express computations.

Formal languages tend to have strict rules about syntax. For example, $3+3=6$ is a syntactically correct mathematical statement, but $3=+6\$$ is not. H_2O is a syntactically correct chemical name, but $2Zz$ is not.

Syntax rules come in two flavors, pertaining to **tokens** and structure. Tokens are the basic elements of the language, such as words, numbers, parentheses, commas, and so on. In Python, a statement like `print("Happy New Year for ", 2013)` has 6 tokens: a function name, an open parenthesis (round bracket), a string, a comma, a number, and a close parenthesis.

It is possible to make errors in the way one constructs tokens. One of the problems with $3=+6\$$ is that $\$$ is not a legal token in mathematics (at least as far as we know). Similarly, $2Zz$ is not a legal token in chemistry notation because there is no element with the abbreviation Zz .

The second type of syntax rule pertains to the **structure** of a statement— that is, the way the tokens are arranged. The statement `3+=6$` is structurally illegal because you can't place a plus sign immediately after an equal sign. Similarly, molecular formulas have to have subscripts after the element name, not before. And in our Python example, if we omitted the comma, or if we changed the two parentheses around to say `print)"Happy New Year for ",2013(` our statement would still have six legal and valid tokens, but the structure is illegal.

When you read a sentence in English or a statement in a formal language, you have to figure out what the structure of the sentence is (although in a natural language you do this subconsciously). This process is called **parsing**.

For example, when you hear the sentence, “The other shoe fell”, you understand that the other shoe is the subject and fell is the verb. Once you have parsed a sentence, you can figure out what it means, or the **semantics** of the sentence. Assuming that you know what a shoe is and what it means to fall, you will understand the general implication of this sentence.

Although formal and natural languages have many features in common — tokens, structure, syntax, and semantics — there are many differences:

ambiguity

- Natural languages are full of ambiguity, which people deal with by using contextual clues and other information. Formal languages are designed to be nearly or completely unambiguous, which means that any statement has exactly one meaning, regardless of context.

redundancy

- In order to make up for ambiguity and reduce misunderstandings, natural languages employ lots of redundancy. As a result, they are often verbose. Formal languages are less redundant and more concise.

literalness

- Formal languages mean exactly what they say. On the other hand, natural languages are full of idiom and metaphor. If someone says, “The other shoe fell”, there is probably no shoe and nothing falling. You'll need to find the original joke to understand the idiomatic meaning of the other shoe falling. Yahoo! Answers thinks it knows!

People who grow up speaking a natural language—everyone—often have a hard time adjusting to formal languages. In some ways, the difference between formal and natural language is like the difference between poetry and prose, but more so:

poetry

- Words are used for their sounds as well as for their meaning, and the whole poem together creates an effect or emotional response. Ambiguity is not only common but often deliberate.

prose

- The literal meaning of words is more important, and the structure contributes more meaning. Prose is more amenable to analysis than poetry but still often ambiguous.

program

- The meaning of a computer program is unambiguous and literal, and can be understood entirely by analysis of the tokens and structure.

Here are some suggestions for reading programs (and other formal languages). First, remember that formal languages are much more dense than natural languages, so it takes longer to read them. Also, the structure is very important, so it is usually not a good idea to read from top to bottom, left to right. Instead, learn to parse the program in your head, identifying the tokens and interpreting the structure. Finally, the details matter. Little things like spelling errors and bad punctuation, which you can get away with in natural languages, can make a big difference in a formal language.

1.9. The first program

Traditionally, the first program written in a new language is called Hello, World! because all it does is display the words, Hello, World! In Python, the script looks like this: (For scripts, we'll show line numbers to the left of the Python statements.)

```
1 print("Hello, World!")
```

This is an example of using the **print function**, which doesn't actually print anything on paper. It displays a value on the screen. In this case, the result shown is

```
1 Hello, World!
```

The quotation marks in the program mark the beginning and end of the value; they don't appear in the result.

Some people judge the quality of a programming language by the simplicity of the Hello, World! program. By this standard, Python does about as well as possible.

1.10. Comments

As programs get bigger and more complicated, they get more difficult to read. Formal languages are dense, and it is often difficult to look at a piece of code and figure out what it is doing, or why.

For this reason, it is a good idea to add notes to your programs to explain in natural language what the program is doing.

A **comment** in a computer program is text that is intended only for the human reader — it is completely ignored by the interpreter.

In Python, the `#` token starts a comment. The rest of the line is ignored. Here is a new version of Hello, World!.

```

1  #-----
2  # This demo program shows off how elegant Python is!
3  # Written by Joe Soap, December 2010.
4  # Anyone may freely copy or modify this program.
5  #-----
6
7  print("Hello, World!")    # Isn't this easy!
```

You'll also notice that we've left a blank line in the program. Blank lines are also ignored by the interpreter, but comments and blank lines can make your programs much easier for humans to parse. Use them liberally!

1.11. Glossary

algorithm

A set of specific steps for solving a category of problems.

bug

An error in a program.

comment

Information in a program that is meant for other programmers (or anyone reading the source code) and has no effect on the execution of the program.

debugging

The process of finding and removing any of the three kinds of programming errors.

exception

Another name for a runtime error.

formal language

Any one of the languages that people have designed for specific purposes, such as representing mathematical ideas or computer programs; all programming languages are formal languages.

high-level language

A programming language like Python that is designed to be easy for humans to read and write.

immediate mode

A style of using Python where we type expressions at the command prompt, and the results are shown immediately. Contrast with script, and see the entry under Python shell.

interpreter

The engine that executes your Python scripts or expressions.

low-level language

A programming language that is designed to be easy for a computer to execute; also called machine language or assembly language.

natural language

Any one of the languages that people speak that evolved naturally.

object code

The output of the compiler after it translates the program.

parse

To examine a program and analyze the syntactic structure.

portability

A property of a program that can run on more than one kind of computer.

print function

A function used in a program or script that causes the Python interpreter to display a value on its output device.

problem solving

The process of formulating a problem, finding a solution, and expressing the solution.

program

a sequence of instructions that specifies to a computer actions and computations to be performed.

Python shell

An interactive user interface to the Python interpreter. The user of a Python shell types commands at the prompt (`>>>`), and presses the return key to send these commands immediately to the interpreter

for processing. The word shell comes from Unix. In the PyScripter used in this RLE version of the book, the Interpreter Window is where we'd do the immediate mode interaction.

runtime error

An error that does not occur until the program has started to execute but that prevents the program from continuing.

script

A program stored in a file (usually one that will be interpreted).

semantic error

An error in a program that makes it do something other than what the programmer intended.

semantics

The meaning of a program.

source code

A program in a high-level language before being compiled.

syntax

The structure of a program.

syntax error

An error in a program that makes it impossible to parse — and therefore impossible to interpret.

token

One of the basic elements of the syntactic structure of a program, analogous to a word in a natural language.

1.12. Exercises

1. Write an English sentence with understandable semantics but incorrect syntax. Write another English sentence which has correct syntax but has semantic errors.
2. Using the Python interpreter, type `1 + 2` and then hit return. Python evaluates this expression, displays the result, and then shows another prompt. `*` is the multiplication operator, and `**` is the exponentiation operator. Experiment by entering different expressions and recording what is displayed by the Python interpreter.
3. Type `1 2` and then hit return. Python tries to evaluate the expression, but it can't because the expression is not syntactically legal. Instead, it shows the error message:


```

1 File "<interactive input>", line 1
2     1 2
3     ^
4 SyntaxError: invalid syntax

```

In many cases, Python indicates where the syntax error occurred, but it is not always right, and it doesn't give you much information about what is wrong.

So, for the most part, the burden is on you to learn the syntax rules.

In this case, Python is complaining because there is no operator between the numbers.

See if you can find a few more examples of things that will produce error messages when you enter them at the Python prompt. Write down what you enter at the prompt and the last line of the error message that Python reports back to you.

4. Type `print("hello")`. Python executes this, which has the effect of printing the letters h-e-l-l-o. Notice that the quotation marks that you used to enclose the string are not part of the output. Now type `"hello"` and describe your result. Make notes of when you see the quotation marks and when you don't.
5. Type `cheese` without the quotation marks. The output will look something like this:

```

1 Traceback (most recent call last):
2   File "<interactive input>", line 1, in ?
3   NameError: name 'cheese' is not defined

```

This is a run-time error; specifically, it is a `NameError`, and even more specifically, it is an error because the name `cheese` is not defined. If you don't know what that means yet, you will soon.

6. Type `6 + 4 * 9` at the Python prompt and hit enter. Record what happens.

Now create a Python script with the following contents:

```

1 6 + 4 * 9

```

What happens when you run this script? Now change the script contents to:

```

1 print(6 + 4 * 9)

```

and run it again.

What happened this time?

Whenever an expression is typed at the Python prompt, it is evaluated and the result is automatically shown on the line below. (Like on your calculator, if you type this expression you'll get the result 42.)

A script is different, however. Evaluations of expressions are not automatically displayed, so it is necessary to use the **print** function to make the answer show up.

It is hardly ever necessary to use the print function in immediate mode at the command prompt.

Chapter 2: Variables, expressions and statements

(Watch a video based on this chapter [here on YouTube](#)⁵.)

2.1. Values and data types

A **value** is one of the fundamental things — like a letter or a number — that a program manipulates. The values we have seen so far are 4 (the result when we added $2 + 2$), and "Hello, World!".

These values are classified into different **classes**, or **data types**: 4 is an *integer*, and "Hello, World!" is a *string*, so-called because it contains a string of letters. You (and the interpreter) can identify strings because they are enclosed in quotation marks.

If you are not sure what class a value falls into, Python has a function called **type** which can tell you.

```
1 >>> type("Hello, World!")
2 <class 'str'>
3 >>> type(17)
4 <class 'int'>
```

Not surprisingly, strings belong to the class **str** and integers belong to the class **int**. Less obviously, numbers with a decimal point belong to a class called **float**, because these numbers are represented in a format called *floating-point*. At this stage, you can treat the words *class* and *type* interchangeably. We'll come back to a deeper understanding of what a class is in later chapters.

```
1 >>> type(3.2)
2 <class 'float'>
```

What about values like "17" and "3.2"? They look like numbers, but they are in quotation marks like strings.

⁵<https://youtu.be/gIvstR16coI>

```
1 >>> type("17")
2 <class 'str'>
3 >>> type("3.2")
4 <class 'str'>
```

They're strings!

Strings in Python can be enclosed in either single quotes (') or double quotes ("), or three of each (''' or """)

```
1 >>> type('This is a string.')
2 <class 'str'>
3 >>> type("And so is this.")
4 <class 'str'>
5 >>> type("""and this.""")
6 <class 'str'>
7 >>> type(''and even this...''')
8 <class 'str'>
```

Double quoted strings can contain single quotes inside them, as in "Bruce's beard", and single quoted strings can have double quotes inside them, as in 'The knights who say "Ni!"'.

Strings enclosed with three occurrences of either quote symbol are called triple quoted strings. They can contain either single or double quotes:

```
1 >>> print('""Oh no", she exclaimed, "Ben's bike is broken!""')
2 "Oh no", she exclaimed, "Ben's bike is broken!"
3 >>>
```

Triple quoted strings can even span multiple lines:

```
1 >>> message = """This message will
2 ... span several
3 ... lines."""
4 >>> print(message)
5 This message will
6 span several
7 lines.
8 >>>
```

Python doesn't care whether you use single or double quotes or the three-of-a-kind quotes to surround your strings: once it has parsed the text of your program or command, the way it stores the value is identical in all cases, and the surrounding quotes are not part of the value. But when the interpreter wants to display a string, it has to decide which quotes to use to make it look like a string.

```
1 >>> 'This is a string.'
2 'This is a string.'
3 >>> """And so is this."""
4 'And so is this.'
```

So the Python language designers usually chose to surround their strings by single quotes. What do you think would happen if the string already contained single quotes?

When you type a large integer, you might be tempted to use commas between groups of three digits, as in 42,000. This is not a legal integer in Python, but it does mean something else, which is legal:

```
1 >>> 42000
2 42000
3 >>> 42,000
4 (42, 0)
```

Well, that's not what we expected at all! Because of the comma, Python chose to treat this as a pair of values. We'll come back to learn about pairs later. But, for the moment, remember not to put commas or spaces in your integers, no matter how big they are. Also revisit what we said in the previous chapter: formal languages are strict, the notation is concise, and even the smallest change might mean something quite different from what you intended.

2.2. Variables

One of the most powerful features of a programming language is the ability to manipulate **variables**. A variable is a name that refers to a value.

The **assignment statement** gives a value to a variable:

```
1 >>> message = "What's up, Doc?"
2 >>> n = 17
3 >>> pi = 3.14159
```

This example makes three assignments. The first assigns the string value "What's up, Doc?" to a variable named `message`. The second gives the integer 17 to `n`, and the third assigns the floating-point number 3.14159 to a variable called `pi`.

The assignment token, `=`, should not be confused with *equals*, which uses the token `==`. The assignment statement binds a *name*, on the left-hand side of the operator, to a *value*, on the right-hand side. This is why you will get an error if you enter:

```


1 >>> 17 = n
2 File "<interactive input>", line 1
3 SyntaxError: can't assign to literal

```

Tip:

*When reading or writing code, say to yourself “*n* is assigned 17” or “*n* gets the value 17”. Don’t say “*n* equals 17”.*

A common way to represent variables on paper is to write the name with an arrow pointing to the variable’s value. This kind of figure is called a **state snapshot** because it shows what state each of the variables is in at a particular instant in time. (Think of it as the variable’s state of mind). This diagram shows the result of executing the assignment statements:



State Snapshot

If you ask the interpreter to evaluate a variable, it will produce the value that is currently linked to the variable:

```

1 >>> message
2 "What's up, Doc?"
3 >>> n
4 17
5 >>> pi
6 3.14159

```

We use variables in a program to “remember” things, perhaps the current score at the football game. But variables are *variable*. This means they can change over time, just like the scoreboard at a football game. You can assign a value to a variable, and later assign a different value to the same variable. (*This is different from maths. In maths, if you give *x* the value 3, it cannot change to link to a different value half-way through your calculations!*)

```

1 >>> day = "Thursday"
2 >>> day
3 'Thursday'
4 >>> day = "Friday"
5 >>> day
6 'Friday'
7 >>> day = 21
8 >>> day
9 21

```

You'll notice we changed the value of `day` three times, and on the third assignment we even made it refer to a value that was of a different type.

A great deal of programming is about having the computer remember things, e.g. *The number of missed calls on your phone*, and then arranging to update or change the variable when you miss another call.

2.3. Variable names and keywords

Variable names can be arbitrarily long. They can contain both letters and digits, but they have to begin with a letter or an underscore. Although it is legal to use uppercase letters, by convention we don't. If you do, remember that case matters. `Bruce` and `bruce` are different variables.

The underscore character (`_`) can appear in a name. It is often used in names with multiple words, such as `my_name` or `price_of_tea_in_china`.

There are some situations in which names beginning with an underscore have special meaning, so a safe rule for beginners is to start all names with a letter.

If you give a variable an illegal name, you get a syntax error:

```

1 >>> 76trombones = "big parade"
2 SyntaxError: invalid syntax
3 >>> more$ = 1000000
4 SyntaxError: invalid syntax
5 >>> class = "Computer Science 101"
6 SyntaxError: invalid syntax

```

`76trombones` is illegal because it does not begin with a letter. `more$` is illegal because it contains an illegal character, the dollar sign. But what's wrong with `class`?

It turns out that `class` is one of the Python **keywords**. Keywords define the language's syntax rules and structure, and they cannot be used as variable names.

Python has thirty-something keywords (and every now and again improvements to Python introduce or eliminate one or two):

and	as	assert	break	class	continue
def	del	elif	else	except	exec
finally	for	from	global	if	import
in	is	lambda	nonlocal	not	or
pass	raise	return	try	while	with
yield	True	False	None		

You might want to keep this list handy. If the interpreter complains about one of your variable names and you don't know why, see if it is on this list.

Programmers generally choose names for their variables that are meaningful to the human readers of the program — they help the programmer document, or remember, what the variable is used for.

Caution

Beginners sometimes confuse “meaningful to the human readers” with “meaningful to the computer”. So they’ll wrongly think that because they’ve called some variable `average` or `pi`, it will somehow magically calculate an average, or magically know that the variable `pi` should have a value like 3.14159. No! The computer doesn’t understand what you intend the variable to mean.

So you’ll find some instructors who deliberately don’t choose meaningful names when they teach beginners — not because we don’t think it is a good habit, but because we’re trying to reinforce the message that you — the programmer — must write the program code to calculate the average, and you must write an assignment statement to give the variable `pi` the value you want it to have.

2.4. Statements

A **statement** is an instruction that the Python interpreter can execute. We have only seen the assignment statement so far. Some other kinds of statements that we’ll see shortly are `while` statements, `for` statements, `if` statements, and `import` statements. (There are other kinds too!)

When you type a statement on the command line, Python executes it. Statements don’t produce any result.

2.5. Evaluating expressions

An **expression** is a combination of values, variables, operators, and calls to functions. If you type an expression at the Python prompt, the interpreter **evaluates** it and displays the result:

```

1 >>> 1 + 1
2 2
3 >>> len("hello")
4 5

```


In this example `len` is a built-in Python function that returns the number of characters in a string. We've previously seen the `print` and the `type` functions, so this is our third example of a function!

The *evaluation* of an *expression* produces a value, which is why expressions can appear on the right hand side of assignment statements. A value all by itself is a simple expression, and so is a variable.

```
1 >>> 17
2 17
3 >>> y = 3.14
4 >>> x = len("hello")
5 >>> x
6 5
7 >>> y
8 3.14
```

2.6. Operators and operands

Operators are special tokens that represent computations like addition, multiplication and division. The values the operator uses are called **operands**.

The following are all legal Python expressions whose meaning is more or less clear:

```
1 20+32    hour-1    hour*60+minute    minute/60    5**2    (5+9)*(15-7)
```

The tokens `+`, `-`, and `*`, and the use of parenthesis for grouping, mean in Python what they mean in mathematics. The asterisk (`*`) is the token for multiplication, and `**` is the token for exponentiation.

```
1 >>> 2 ** 3
2 8
3 >>> 3 ** 2
4 9
```

When a variable name appears in the place of an operand, it is replaced with its value before the operation is performed.

Addition, subtraction, multiplication, and exponentiation all do what you expect.

Example: so let us convert 645 minutes into hours:

```
1 >>> minutes = 645
2 >>> hours = minutes / 60
3 >>> hours
4 10.75
```

Oops! In Python 3, the division operator `/` always yields a floating point result. What we might have wanted to know was how many whole hours there are, and how many minutes remain. Python gives us two different flavors of the division operator. The second, called **floor division** uses the token `//`. Its result is always a whole number — and if it has to adjust the number it always moves it to the left on the number line. So `6 // 4` yields 1, but `-6 // 4` might surprise you!

```
1 >>> 7 / 4
2 1.75
3 >>> 7 // 4
4 1
5 >>> minutes = 645
6 >>> hours = minutes // 60
7 >>> hours
8 10
```

Take care that you choose the correct flavor of the division operator. If you're working with expressions where you need floating point values, use the division operator that does the division accurately.

2.7. Type converter functions

Here we'll look at three more Python functions, `int`, `float` and `str`, which will (attempt to) convert their arguments into types `int`, `float` and `str` respectively. We call these **type converter** functions.

The `int` function can take a floating point number or a string, and turn it into an `int`. For floating point numbers, it discards the decimal portion of the number — a process we call truncation towards zero on the number line. Let us see this in action:

```
1 >>> int(3.14)
2 3
3 >>> int(3.9999)           # This doesn't round to the closest int!
4 3
5 >>> int(3.0)
6 3
7 >>> int(-3.999)           # Note that the result is closer to zero
8 -3
9 >>> int(minutes / 60)
10 10
11 >>> int("2345")           # Parse a string to produce an int
12 2345
13 >>> int(17)               # It even works if arg is already an int
14 17
15 >>> int("23 bottles")
```

This last case doesn't look like a number — what do we expect?

```
1 Traceback (most recent call last):
2   File "<interactive input>", line 1, in <module>
3   ValueError: invalid literal for int() with base 10: '23 bottles'
```

The type converter `float` can turn an integer, a float, or a syntactically legal string into a float:

```
1 >>> float(17)
2 17.0
3 >>> float("123.45")
4 123.45
```

The type converter `str` turns its argument into a string:

```
1 >>> str(17)
2 '17'
3 >>> str(123.45)
4 '123.45'
```

2.8. Order of operations

When more than one operator appears in an expression, the order of evaluation depends on the **rules of precedence**. Python follows the same precedence rules for its mathematical operators that mathematics does. The acronym PEMDAS is a useful way to remember the order of operations:

1. Parentheses have the highest precedence and can be used to force an expression to evaluate in the order you want. Since expressions in parentheses are evaluated first, $2 * (3-1)$ is 4, and $(1+1)**(5-2)$ is 8. You can also use parentheses to make an expression easier to read, as in $(\text{minute} * 100) / 60$, even though it doesn't change the result.
2. Exponentiation has the next highest precedence, so $2**1+1$ is 3 and not 4, and $3*1**3$ is 3 and not 27.
3. Multiplication and both Division operators have the same precedence, which is higher than Addition and Subtraction, which also have the same precedence. So $2*3-1$ yields 5 rather than 4, and $5-2*2$ is 1, not 6.

Operators with the same precedence are evaluated from left-to-right. In algebra we say they are left-associative. So in the expression $6-3+2$, the subtraction happens first, yielding 3. We then add 2 to get the result 5. If the operations had been evaluated from right to left, the result would have been $6-(3+2)$, which is 1. (The acronym PEDMAS could mislead you to thinking that division has higher precedence than multiplication, and addition is done ahead of subtraction - don't be misled. Subtraction and addition are at the same precedence, and the left-to-right rule applies.)

Due to some historical quirk, an exception to the left-to-right left-associative rule is the exponentiation operator `**`, so a useful hint is to always use parentheses to force exactly the order you want when exponentiation is involved:

```

1 >>> 2 ** 3 ** 2      # The right-most ** operator gets done first!
2 512
3 >>> (2 ** 3) ** 2    # Use parentheses to force the order you want!
4 64

```

The immediate mode command prompt of Python is great for exploring and experimenting with expressions like this.

2.9. Operations on strings

In general, you cannot perform mathematical operations on strings, even if the strings look like numbers. The following are illegal (assuming that `message` has type string):

```

1 >>> message - 1      # Error
2 >>> "Hello" / 123     # Error
3 >>> message * "Hello" # Error
4 >>> "15" + 2         # Error

```

Interestingly, the `+` operator does work with strings, but for strings, the `+` operator represents **concatenation**, not addition. Concatenation means joining the two operands by linking them end-to-end. For example:

```
1 fruit = "banana"
2 baked_good = " nut bread"
3 print(fruit + baked_good)
```

The output of this program is banana nut bread. The space before the word nut is part of the string, and is necessary to produce the space between the concatenated strings.

The `*` operator also works on strings; it performs repetition. For example, `'Fun'*3` is `'FunFunFun'`. One of the operands has to be a string; the other has to be an integer.


On one hand, this interpretation of `+` and `*` makes sense by analogy with addition and multiplication. Just as $4*3$ is equivalent to $4+4+4$, we expect `"Fun"*3` to be the same as `"Fun"+"Fun"+"Fun"`, and it is. On the other hand, there is a significant way in which string concatenation and repetition are different from integer addition and multiplication. Can you think of a property that addition and multiplication have that string concatenation and repetition do not?

2.10. Input

There is a built-in function in Python for getting input from the user:

```
1 n = input("Please enter your name: ")
```

A sample run of this script in Replit would populate your input question in the console to the left like this:



Input Prompt

The user of the program can enter the name and press enter, and when this happens the text that has been entered is returned from the input function, and in this case assigned to the variable `n`.

Even if you asked the user to enter their age, you would get back a string like `"17"`. It would be your job, as the programmer, to convert that string into a `int` or a `float`, using the `int` or `float` converter functions we saw earlier.

2.11. Composition

So far, we have looked at the elements of a program — variables, expressions, statements, and function calls — in isolation, without talking about how to combine them.

One of the most useful features of programming languages is their ability to take small building blocks and **compose** them into larger chunks.

For example, we know how to get the user to enter some input, we know how to convert the string we get into a float, we know how to write a complex expression, and we know how to print values. Let's put these together in a small four-step program that asks the user to input a value for the radius of a circle, and then computes the area of the circle from the formula

$$A = \pi r^2$$

Area of a circle

Firstly, we'll do the four steps one at a time:

```
1 response = input("What is your radius? ")
2 r = float(response)
3 area = 3.14159 * r**2
4 print("The area is ", area)
```

Now let's compose the first two lines into a single line of code, and compose the second two lines into another line of code.

```
1 r = float( input("What is your radius? ") )
2 print("The area is ", 3.14159 * r**2)
```

If we really wanted to be tricky, we could write it all in one statement:

```
1 print("The area is ", 3.14159*float(input("What is your radius?"))**2)
```

Such compact code may not be most understandable for humans, but it does illustrate how we can compose bigger chunks from our building blocks.

If you're ever in doubt about whether to compose code or fragment it into smaller steps, try to make it as simple as you can for the human to follow. My choice would be the first case above, with four separate steps.

2.12. The modulus operator

The modulus operator works on integers (and integer expressions) and gives the remainder when the first number is divided by the second. In Python, the modulus operator is a percent sign (%). The syntax is the same as for other operators. It has the same precedence as the multiplication operator.

```
1 >>> q = 7 // 3      # This is integer division operator
2 >>> print(q)
3 2
4 >>> r = 7 % 3
5 >>> print(r)
6 1
```

So 7 divided by 3 is 2 with a remainder of 1.

The modulus operator turns out to be surprisingly useful. For example, you can check whether one number is divisible by another—if `x % y` is zero, then `x` is divisible by `y`.

Also, you can extract the right-most digit or digits from a number. For example, `x % 10` yields the right-most digit of `x` (in base 10). Similarly `x % 100` yields the last two digits.

It is also extremely useful for doing conversions, say from seconds, to hours, minutes and seconds. So let's write a program to ask the user to enter some seconds, and we'll convert them into hours, minutes, and remaining seconds.

```
1 total_secs = int(input("How many seconds, in total?"))
2 hours = total_secs // 3600
3 secs_still_remaining = total_secs % 3600
4 minutes = secs_still_remaining // 60
5 secs_finally_remaining = secs_still_remaining % 60
6
7 print("Hrs=", hours, " mins=", minutes,
8       "secs=", secs_finally_remaining)
```

2.13. Glossary

assignment statement

A statement that assigns a value to a name (variable). To the left of the assignment operator, `=`, is a name. To the right of the assignment token is an expression which is evaluated by the Python interpreter and then assigned to the name. The difference between the left and right hand sides of the assignment statement is often confusing to new programmers. In the following assignment:

```
1 n = n + 1
```

`n` plays a very different role on each side of the `=`. On the right it is a value and makes up part of the expression which will be evaluated by the Python interpreter before assigning it to the name on the left.

assignment token

`=` is Python's assignment token. Do not confuse it with *equals*, which is an operator for comparing values.

composition

The ability to combine simple expressions and statements into compound statements and expressions in order to represent complex computations concisely.

concatenate

To join two strings end-to-end.

data type

A set of values. The type of a value determines how it can be used in expressions. So far, the types you have seen are integers (`int`), floating-point numbers (`float`), and strings (`str`).

evaluate

To simplify an expression by performing the operations in order to yield a single value.

expression

A combination of variables, operators, and values that represents a single result value.

float

A Python data type which stores *floating-point* numbers. Floating-point numbers are stored internally in two parts: a *base* and an *exponent*. When printed in the standard format, they look like decimal numbers. Beware of rounding errors when you use `floats`, and remember that they are only approximate values.

floor division

An operator (denoted by the token `//`) that divides one number by another and yields an integer, or, if the result is not already an integer, it yields the next smallest integer.

int

A Python data type that holds positive and negative whole numbers.

keyword

A reserved word that is used by the compiler to parse programs; you cannot use keywords like `if`, `def`, and `while` as variable names.

modulus operator

An operator, denoted with a percent sign (%), that works on integers and yields the remainder when one number is divided by another.

operand

One of the values on which an operator operates.

operator

A special symbol that represents a simple computation like addition, multiplication, or string concatenation.

rules of precedence

The set of rules governing the order in which expressions involving multiple operators and operands are evaluated.

state snapshot

A graphical representation of a set of variables and the values to which they refer, taken at a particular instant during the program's execution.

statement

An instruction that the Python interpreter can execute. So far we have only seen the assignment statement, but we will soon meet the `import` statement and the `for` statement.

str

A Python data type that holds a string of characters.

value

A number or string (or other things to be named later) that can be stored in a variable or computed in an expression.

variable

A name that refers to a value.

variable name

A name given to a variable. Variable names in Python consist of a sequence of letters (`a..z`, `A..Z`, and `_`) and digits (`0..9`) that begins with a letter. In best programming practice, variable names should be chosen so that they describe their use in the program, making the program *self documenting*.

2.14. Exercises

1. Take the sentence: All work and no play makes Jack a dull boy. Store each word in a separate variable, then print out the sentence on one line using print.
2. Add parenthesis to the expression `6 * 1 - 2` to change its value from 4 to -6.
3. Place a comment before a line of code that previously worked, and record what happens when you rerun the program.
4. Start the Python interpreter and enter `bruce + 4` at the prompt. This will give you an error:

```
1  NameError: name 'bruce' is not defined
```

Assign a value to `bruce` so that `bruce + 4` evaluates to 10.

5. The formula for computing the final amount if one is earning compound interest is given on Wikipedia as
Compounded Interest Formula

$$P' = P \left(1 + \frac{r}{n} \right)^{nt}$$

where:

P is the original principal sum

P' is the new principal sum

r is the [nominal annual interest rate](#)

n is the compounding frequency

t is the overall length of time the interest is applied (expressed using the same time units as r , usually years).

Compounded Interest Formula

Write a Python program that assigns the principal amount of \$10000 to variable `P`, assign to `n` the value 12, and assign to `r` the interest rate of 8%. Then have the program prompt the user for the number of years `t` that the money will be compounded for. Calculate and print the final amount after `t` years.

6. Evaluate the following numerical expressions in your head, then use the Python interpreter to check your results:

```
1  >>> 5 % 2
2  >>> 9 % 5
3  >>> 15 % 12
4  >>> 12 % 15
5  >>> 6 % 6
6  >>> 0 % 7
7  >>> 7 % 0
```

What happened with the last example? Why? If you were able to correctly anticipate the computer's response in all but the last one, it is time to move on. If not, take time now to

make up examples of your own. Explore the modulus operator until you are confident you understand how it works.

7. You look at the clock and it is exactly 2pm. You set an alarm to go off in 51 hours. At what time does the alarm go off? (*Hint: you could count on your fingers, but this is not what we're after. If you are tempted to count on your fingers, change the 51 to 5100.*)
8. Write a Python program to solve the general version of the above problem. Ask the user for the time now (in hours), and ask for the number of hours to wait. Your program should output what the time will be on the clock when the alarm goes off.

Chapter 3: Hello, little turtles!

There are many *modules* in Python that provide very powerful features that we can use in our own programs. Some of these can send email, or fetch web pages. The one we'll look at in this chapter allows us to create turtles and get them to draw shapes and patterns.


The turtles are fun, but the real purpose of the chapter is to teach ourselves a little more Python, and to develop our theme of *computational thinking*, or *thinking like a computer scientist*. Most of the Python covered here will be explored in more depth later.

3.1. Our first turtle program

Let's write a couple of lines of Python program to create a new turtle and start drawing a rectangle. (We'll call the variable that refers to our first turtle `alex`, but we can choose another name if we follow the naming rules from the previous chapter).

```
1  import turtle                # Allows us to use turtles
2  wn = turtle.Screen()        # Creates a playground for turtles
3  alex = turtle.Turtle()      # Create a turtle, assign to alex
4
5  alex.forward(50)             # Tell alex to move forward by 50 units
6  alex.left(90)                # Tell alex to turn by 90 degrees
7  alex.forward(30)             # Complete the second side of a rectangle
8
9  wn.mainloop()               # Wait for user to close window
```

When we run this program, a new window pops up:



Turtle Window

Here are a couple of things we'll need to understand about this program.

The first line tells Python to load a module named `turtle`. That module brings us two new types that we can use: the `Turtle` type, and the `Screen` type. The dot notation `turtle.Turtle` means “*The Turtle type that is defined within the turtle module*”. (Remember that Python is case sensitive, so the module name, with a lowercase `t`, is different from the type `Turtle`.)

We then create and open what it calls a screen (we would prefer to call it a window), which we assign to variable `wn`. Every window contains a **canvas**, which is the area inside the window on which we can draw.

In line 3 we create a turtle. The variable `alex` is made to refer to this turtle.

So these first three lines have set things up, we're ready to get our turtle to draw on our canvas.

In lines 5-7, we instruct the **object** `alex` to move, and to turn. We do this by **invoking**, or activating, `alex`'s **methods** — these are the instructions that all turtles know how to respond to.

The last line plays a part too: the `wn` variable refers to the window shown above. When we invoke its `mainloop` method, it enters a state where it waits for events (like keypresses, or mouse movement and clicks). The program will terminate when the user closes the window.

An object can have various methods — things it can do — and it can also have **attributes** — (sometimes called properties). For example, each turtle has a `color` attribute. The method invocation `alex.color("red")` will make `alex` red, and drawing will be red too. (Note the word *color* is spelled the American way!)


The color of the turtle, the width of its pen, the position of the turtle within the window, which way it is facing, and so on are all part of its current **state**. Similarly, the window object has a background

color, and some text in the title bar, and a size and position on the screen. These are all part of the state of the window object.

Quite a number of methods exist that allow us to modify the turtle and the window objects. We'll just show a couple. In this program we've only commented those lines that are different from the previous example (and we've used a different variable name for this turtle):

```
1 import turtle
2 wn = turtle.Screen()
3 wn.bgcolor("lightgreen")      # Set the window background color
4 wn.title("Hello, Tess!")     # Set the window title
5
6 tess = turtle.Turtle()
7 tess.color("blue")           # Tell tess to change her color
8 tess.pensize(3)              # Tell tess to set her pen width
9
10 tess.forward(50)
11 tess.left(120)
12 tess.forward(50)
13
14 wn.mainloop()
```

When we run this program, this new window pops up, and will remain on the screen until we close it.



tess.mainloop()

Extend this program ...

1. Modify this program so that before it creates the window, it prompts the user to enter the desired background color. It should store the user's responses in a variable, and modify the color of the window according to the user's wishes. (*Hint: you can find a list of permitted color names at <http://www.tcl.tk/man/tcl8.4/TkCmd/colors.htm>. It includes some quite unusual ones, like "peach puff" and "HotPink".*)
2. Do similar changes to allow the user, at runtime, to set tess' color.
3. Do the same for the width of tess' pen. *Hint: your dialog with the user will return a string, but tess' pensize method expects its argument to be an int. So you'll need to convert the string to an int before you pass it to pensize.*

3.2. Instances — a herd of turtles

Just like we can have many different integers in a program, we can have many turtles. Each of them is called an **instance**. Each instance has its own attributes and methods — so alex might draw with a thin black pen and be at some position, while tess might be going in her own direction with a fat pink pen.


```

1  import turtle
2  wn = turtle.Screen()           # Set up the window and its attributes
3  wn.bgcolor("lightgreen")
4  wn.title("Tess & Alex")
5
6  tess = turtle.Turtle()        # Create tess and set some attributes
7  tess.color("hotpink")
8  tess.pensize(5)
9
10 alex = turtle.Turtle()        # Create alex
11
12 tess.forward(80)              # Make tess draw equilateral triangle
13 tess.left(120)
14 tess.forward(80)
15 tess.left(120)
16 tess.forward(80)
17 tess.left(120)               # Complete the triangle
18
19 tess.right(180)               # Turn tess around
20 tess.forward(80)             # Move her away from the origin
21
22 alex.forward(50)              # Make alex draw a square
23 alex.left(90)
24 alex.forward(50)
25 alex.left(90)

```

```
26 alex.forward(50)
27 alex.left(90)
28 alex.forward(50)
29 alex.left(90)
30
31 wn.mainloop()
```

Here is what happens when alex completes his rectangle, and tess completes her triangle:



Alex and Tess

Here are some *How to think like a computer scientist* observations:

- There are 360 degrees in a full circle. If we add up all the turns that a turtle makes, no matter what steps occurred between the turns, we can easily figure out if they add up to some multiple of 360. This should convince us that alex is facing in exactly the same direction as he was when he was first created. (Geometry conventions have 0 degrees facing East, and that is the case here too!)
- We could have left out the last turn for alex, but that would not have been as satisfying. If we're asked to draw a closed shape like a square or a rectangle, it is a good idea to complete all the turns and to leave the turtle back where it started, facing the same direction as it started in. This makes reasoning about the program and composing chunks of code into bigger programs easier for us humans!

- We did the same with tess: she drew her triangle, and turned through a full 360 degrees. Then we turned her around and moved her aside. Even the blank line 18 is a hint about how the programmer’s mental chunking is working: in big terms, tess’ movements were chunked as “draw the triangle” (lines 12-17) and then “move away from the origin” (lines 19 and 20).
- One of the key uses for comments is to record our mental chunking, and big ideas. They’re not always explicit in the code.
- And, uh-huh, two turtles may not be enough for a herd. But the important idea is that the turtle module gives us a kind of factory that lets us create as many turtles as we need. Each instance has its own state and behaviour.

3.3. The for loop

When we drew the square, it was quite tedious. We had to explicitly repeat the steps of moving and turning four times. If we were drawing a hexagon, or an octagon, or a polygon with 42 sides, it would have been worse.

So a basic building block of all programs is to be able to repeat some code, over and over again.

Python’s **for** loop solves this for us. Let’s say we have some friends, and we’d like to send them each an email inviting them to our party. We don’t quite know how to send email yet, so for the moment we’ll just print a message for each friend:

```
1  for f in ["Joe", "Zoe", "Brad", "Angelina", "Zuki", "Thandi", "Paris"]:
2      invite = "Hi " + f + ". Please come to my party on Saturday!"
3      print(invite)
4  # more code can follow here ...
```

When we run this, the output looks like this:

```
1  Hi Joe. Please come to my party on Saturday!
2  Hi Zoe. Please come to my party on Saturday!
3  Hi Brad. Please come to my party on Saturday!
4  Hi Angelina. Please come to my party on Saturday!
5  Hi Zuki. Please come to my party on Saturday!
6  Hi Thandi. Please come to my party on Saturday!
7  Hi Paris. Please come to my party on Saturday!
```

- The variable `f` in the **for** statement at line 1 is called the **loop variable**. We could have chosen any other variable name instead.

Lines 2 and 3 are the **loop body**. The loop body is always indented. The indentation determines exactly what statements are “in the body of the loop”.

- On each *iteration* or *pass* of the loop, first a check is done to see if there are still more items to be processed. If there are none left (this is called the **terminating condition** of the loop), the loop has finished. Program execution continues at the next statement after the loop body, (e.g. in this case the next statement below the comment in line 4).
- If there are items still to be processed, the loop variable is updated to refer to the next item in the list. This means, in this case, that the loop body is executed here 7 times, and each time `f` will refer to a different friend.
- At the end of each execution of the body of the loop, Python returns to the `for` statement, to see if there are more items to be handled, and to assign the next one to `f`.


3.4. Flow of Execution of the `for` loop

As a program executes, the interpreter always keeps track of which statement is about to be executed. We call this the **control flow**, of the **flow of execution** of the program. When humans execute programs, they often use their finger to point to each statement in turn. So we could think of control flow as “Python’s moving finger”.

Control flow until now has been strictly top to bottom, one statement at a time. The `for` loop changes this.

Flowchart of a `for` loop

Control flow is often easy to visualize and understand if we draw a flowchart. This shows the exact steps and logic of how the `for` statement executes.



For loop flowchart

3.5. The loop simplifies our turtle program

To draw a square we’d like to do the same thing four times — move the turtle, and turn. We previously used 8 lines to have alex draw the four sides of a square. This does exactly the same, but using just three lines:

```
1 for i in [0,1,2,3]:
2     alex.forward(50)
3     alex.left(90)
```

Some observations:

- While “saving some lines of code” might be convenient, it is not the big deal here. What is much more important is that we’ve found a “repeating pattern” of statements, and reorganized our program to repeat the pattern. Finding the chunks and somehow getting our programs arranged around those chunks is a vital skill in computational thinking.

- The values `[0,1,2,3]` were provided to make the loop body execute 4 times. We could have used any four values, but these are the conventional ones to use. In fact, they are so popular that Python gives us special built-in range objects:

```
1  for i in range(4):  
2      # Executes the body with i = 0, then 1, then 2, then 3  
3  for x in range(10):  
4      # Sets x to each of ... [0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
```

- Computer scientists like to count from 0!
- range can deliver a sequence of values to the loop variable in the for loop. They start at 0, and in these cases do not include the 4 or the 10.
- Our little trick earlier to make sure that alex did the final turn to complete 360 degrees has paid off: if we had not done that, then we would not have been able to use a loop for the fourth side of the square. It would have become a “special case”, different from the other sides. When possible, we’d much prefer to make our code fit a general pattern, rather than have to create a special case.

So to repeat something four times, a good Python programmer would do this:

```
1  for i in range(4):  
2      alex.forward(50)  
3      alex.left(90)
```

By now you should be able to see how to change our previous program so that tess can also use a for loop to draw her equilateral triangle.

But now, what would happen if we made this change?

```
1  for c in ["yellow", "red", "purple", "blue"]:  
2      alex.color(c)  
3      alex.forward(50)  
4      alex.left(90)
```

A variable can also be assigned a value that is a list. So lists can also be used in more general situations, not only in the for loop. The code above could be rewritten like this:

```
1 # Assign a list to a variable
2 clr = ["yellow", "red", "purple", "blue"]
3 for c in clr:
4     alex.color(c)
5     alex.forward(50)
6     alex.left(90)
```

3.6. A few more turtle methods and tricks

Turtle methods can use negative angles or distances. So `tess.forward(-100)` will move tess backwards, and `tess.left(-30)` turns her to the right. Additionally, because there are 360 degrees in a circle, turning 30 to the left will get tess facing in the same direction as turning 330 to the right! (The on-screen animation will differ, though — you will be able to tell if tess is turning clockwise or counter-clockwise!)

This suggests that we don't need both a left and a right turn method — we could be minimalists, and just have one method. There is also a *backward* method. (If you are very nerdy, you might enjoy saying `alex.backward(-100)` to move alex forward!)


Part of thinking like a scientist is to understand more of the structure and rich relationships in our field. So revising a few basic facts about geometry and number lines, and spotting the relationships between left, right, backward, forward, negative and positive distances or angles values is a good start if we're going to play with turtles.

A turtle's pen can be picked up or put down. This allows us to move a turtle to a different place without drawing a line. The methods are

```
1 alex.penup()
2 alex.forward(100)    # This moves alex, but no line is drawn
3 alex.pendown()
```

Every turtle can have its own shape. The ones available “out of the box” are arrow, blank, circle, classic, square, triangle, turtle.

```
1 alex.shape("turtle")
```



Turtle Shape

We can speed up or slow down the turtle’s animation speed. (Animation controls how quickly the turtle turns and moves forward). Speed settings can be set between 1 (slowest) to 10 (fastest). But if we set the speed to 0, it has a special meaning — turn off animation and go as fast as possible.


```
1 alex.speed(10)
```

A turtle can “stamp” its footprint onto the canvas, and this will remain after the turtle has moved somewhere else. Stamping works, even when the pen is up.

Let’s do an example that shows off some of these new features:

```
1 import turtle
2 wn = turtle.Screen()
3 wn.bgcolor("lightgreen")
4 tess = turtle.Turtle()
5 tess.shape("turtle")
6 tess.color("blue")
7
8 tess.penup()           # This is new
9 size = 20
10 for i in range(30):
11     tess.stamp()       # Leave an impression on the canvas
12     size = size + 3    # Increase the size on every iteration
13     tess.forward(size) # Move tess along
14     tess.right(24)     # ... and turn her
```

```
15  
16 wn.mainloop()
```



Turtle Spiral

Be careful now! How many times was the body of the loop executed? How many turtle images do we see on the screen? All except one of the shapes we see on the screen here are footprints created by stamp. But the program still only has one turtle instance — can you figure out which one here is the real tess? (*Hint: if you're not sure, write a new line of code after the for loop to change tess' color, or to put her pen down and draw a line, or to change her shape, etc.*)

3.7. Glossary

attribute

Some state or value that belongs to a particular object. For example, tess has a color.

canvas

A surface within a window where drawing takes place.

control flow

See flow of execution in the next chapter.

for loop

A statement in Python for convenient repetition of statements in the body of the loop.

loop body

Any number of statements nested inside a loop. The nesting is indicated by the fact that the statements are indented under the `for` loop statement.

loop variable

A variable used as part of a `for` loop. It is assigned a different value on each iteration of the loop.

instance

An object of a certain type, or class. tess and alex are different instances of the class `Turtle`.

method

A function that is attached to an object. Invoking or activating the method causes the object to respond in some way, e.g. `forward` is the method when we say `tess.forward(100)`.

invoke

An object has methods. We use the verb `invoke` to mean activate the method. Invoking a method is done by putting parentheses after the method name, with some possible arguments. So `tess.forward()` is an invocation of the `forward` method.

module

A file containing Python definitions and statements intended for use in other Python programs. The contents of a module are made available to the other program by using the `import` statement.

object

A “thing” to which a variable can refer. This could be a screen window, or one of the turtles we have created.

range

A built-in function in Python for generating sequences of integers. It is especially useful when we need to write a `for` loop that executes a fixed number of times.

terminating condition

A condition that occurs which causes a loop to stop repeating its body. In the for loops we saw in this chapter, the terminating condition has been when there are no more elements to assign to the loop variable.

3.8. Exercises

1. Write a program that prints `We like Python's turtles! 1000 times`.
2. Give three attributes of your cellphone object. Give three methods of your cellphone.
3. Write a program that uses a for loop to print


```
1 One of the months of the year is January
2 One of the months of the year is February
3 ...
```
4. Suppose our turtle `tess` is at heading 0 — facing east. We execute the statement `tess.left(3645)`. What does `tess` do, and what is her final heading?
5. Assume you have the assignment `xs = [12, 10, 32, 3, 66, 17, 42, 99, 20]`
 - a. Write a loop that prints each of the numbers on a new line.
 - b. Write a loop that prints each number and its square on a new line.
 - c. Write a loop that adds all the numbers from the list into a variable called `total`. You should set the `total` variable to have the value 0 before you start adding them up, and print the value in `total` after the loop has completed.
 - d. Print the product of all the numbers in the list. (product means all multiplied together)
6. Use for loops to make a turtle draw these regular polygons (regular means all sides the same lengths, all angles the same):
 - An equilateral triangle
 - A square
 - A hexagon (six sides)
 - An octagon (eight sides)
7. A drunk pirate makes a random turn and then takes 100 steps forward, makes another random turn, takes another 100 steps, turns another random amount, etc. A social science student records the angle of each turn before the next 100 steps are taken. Her experimental data is `[160, -43, 270, -97, -43, 200, -940, 17, -86]`. (Positive angles are counter-clockwise.) Use a turtle to draw the path taken by our drunk friend.
8. Enhance your program above to also tell us what the drunk pirate's heading is after he has finished stumbling around. (Assume he begins at heading 0).
9. If you were going to draw a regular polygon with 18 sides, what angle would you need to turn the turtle at each corner?
10. At the interactive prompt, anticipate what each of the following lines will do, and then record what happens. Score yourself, giving yourself one point for each one you anticipate correctly:

```
1 >>> import turtle
2 >>> wn = turtle.Screen()
3 >>> tess = turtle.Turtle()
4 >>> tess.right(90)
5 >>> tess.left(3600)
6 >>> tess.right(-90)
7 >>> tess.speed(10)
8 >>> tess.left(3600)
9 >>> tess.speed(0)
10 >>> tess.left(3645)
11 >>> tess.forward(-100)
```

11. Write a program to draw a shape like this:




Star

Hints:

- Try this on a piece of paper, moving and turning your cellphone as if it was a turtle. Watch how many complete rotations your cellphone makes before you complete the star. Since each full rotation is 360 degrees, you can figure out the total number of degrees that your phone was rotated through. If you divide that by 5, because there are five points to the star, you'll know how many degrees to turn the turtle at each point.

- You can hide a turtle behind its invisibility cloak if you don't want it shown. It will still draw its lines if its pen is down. The method is invoked as `tess.hideturtle()`. To make the turtle visible again, use `tess.showturtle()`.

12. Write a program to draw a face of a clock that looks something like this:



Clock face

13. Create a turtle, and assign it to a variable. When you ask for its type, what do you get?
14. What is the collective noun for turtles? (Hint: they don't come in *herds*.)
15. What the collective noun for pythons? Is a python a viper? Is a python venomous?

Chapter 4: Functions

4.1. Functions

In Python, a **function** is a named sequence of statements that belong together. Their primary purpose is to help us organize programs into chunks that match how we think about the problem.

The syntax for a **function definition** is:

```
1 def NAME( PARAMETERS ):  
2     STATEMENTS
```

We can make up any names we want for the functions we create, except that we can't use a name that is a Python keyword, and the names must follow the rules for legal identifiers.

There can be any number of statements inside the function, but they have to be indented from the `def`. In the examples in this book, we will use the standard indentation of four spaces. Function definitions are the second of several **compound statements** we will see, all of which have the same pattern:


1. A header line which begins with a keyword and ends with a colon.
2. A **body** consisting of one or more Python statements, each indented the same amount — the *Python style guide recommends 4 spaces* — from the header line.

We've already seen the `for` loop which follows this pattern.

So looking again at the function definition, the keyword in the header is `def`, which is followed by the name of the function and some *parameters* enclosed in parentheses. The parameter list may be empty, or it may contain any number of parameters separated from one another by commas. In either case, the parentheses are required. The parameters specifies what information, if any, we have to provide in order to use the new function.

Suppose we're working with turtles, and a common operation we need is to draw squares. "Draw a square" is an abstraction, or a mental chunk, of a number of smaller steps. So let's write a function to capture the pattern of this "building block":

```
1  import turtle
2
3  def draw_square(t, sz):
4      """Make turtle t draw a square of sz."""
5      for i in range(4):
6          t.forward(sz)
7          t.left(90)
8
9
10 wn = turtle.Screen()           # Set up the window and its attributes
11 wn.bgcolor("lightgreen")
12 wn.title("Alex meets a function")
13
14 alex = turtle.Turtle()         # Create alex
15 draw_square(alex, 50)          # Call the function to draw the square
16 wn.mainloop()
```



alex function

This function is named `draw_square`. It has two parameters: one to tell the function which turtle to move around, and the other to tell it the size of the square we want drawn. Make sure you know where the body of the function ends — it depends on the indentation, and the blank lines don't count for this purpose!

Docstrings for documentation

If the first thing after the function header is a string, it is treated as a **docstring** and gets special treatment in Python and in some programming tools. For example, when we type a built-in function name with an unclosed parenthesis in Repl.it, a tooltip pops up, telling us what arguments the function takes, and it shows us any other text contained in the docstring.

Docstrings are the key way to document our functions in Python and the documentation part is important. Because whoever calls our function shouldn't have to need to know what is going on in the function or how it works; they just need to know what arguments our function takes, what it does, and what the expected result is. Enough to be able to use the function without having to look underneath. This goes back to the concept of abstraction of which we'll talk more about.

Docstrings are usually formed using triple-quoted strings as they allow us to easily expand the docstring later on should we want to write more than a one-liner.

Just to differentiate from comments, a string at the start of a function (a docstring) is retrievable by Python tools at runtime. By contrast, comments are completely eliminated when the program is parsed.

Defining a new function does not make the function run. To do that we need a **function call**. We've already seen how to call some built-in functions like `print`, `range` and `int`. Function calls contain the name of the function being executed followed by a list of values, called *arguments*, which are assigned to the parameters in the function definition. So in the second last line of the program, we call the function, and pass alex as the turtle to be manipulated, and 50 as the size of the square we want. While the function is executing, then, the variable `sz` refers to the value 50, and the variable `t` refers to the same turtle instance that the variable `alex` refers to.

Once we've defined a function, we can call it as often as we like, and its statements will be executed each time we call it. And we could use it to get any of our turtles to draw a square. In the next example, we've changed the `draw_square` function a little, and we get tess to draw 15 squares, with some variations.

```


1  import turtle
2
3  def draw_multicolor_square(t, sz):
4      """Make turtle t draw a multi-color square of sz."""
5      for i in ["red", "purple", "hotpink", "blue"]:
6          t.color(i)
7          t.forward(sz)
8          t.left(90)
9
10 wn = turtle.Screen()           # Set up the window and its attributes
11 wn.bgcolor("lightgreen")
12
13 tess = turtle.Turtle()         # Create tess and set some attributes
14 tess.pensize(3)
15
16 size = 20                      # Size of the smallest square
17 for i in range(15):
18     draw_multicolor_square(tess, size)
19     size = size + 10           # Increase the size for next time

```

```

20     tess.forward(10)      # Move tess along a little
21     tess.right(18)       #   and give her some turn
22
23 wn.mainloop()

```



Draw multicolor square

4.2. Functions can call other functions

Let's assume now we want a function to draw a rectangle. We need to be able to call the function with different arguments for width and height. And, unlike the case of the square, we cannot repeat the same thing 4 times, because the four sides are not equal.

So we eventually come up with this rather nice code that can draw a rectangle.

```

1  def draw_rectangle(t, w, h):
2      """Get turtle t to draw a rectangle of width w and height h."""
3      for i in range(2):
4          t.forward(w)
5          t.left(90)
6          t.forward(h)
7          t.left(90)

```

The parameter names are deliberately chosen as single letters to ensure they're not misunderstood. In real programs, once we've had more experience, we will insist on better variable names than this. But the point is that the program doesn't "understand" that we're drawing a rectangle, or that the parameters represent the width and the height. Concepts like rectangle, width, and height are the meaning we humans have, not concepts that the program or the computer understands.

Thinking like a scientist involves looking for patterns and relationships. In the code above, we've done that to some extent. We did not just draw four sides. Instead, we spotted that we could draw the rectangle as two halves, and used a loop to repeat that pattern twice.

But now we might spot that a square is a special kind of rectangle. We already have a function that draws a rectangle, so we can use that to draw our square.

```
1 def draw_square(tx, sz):          # A new version of draw_square
2     draw_rectangle(tx, sz, sz)
```

There are some points worth noting here:

- Functions can call other functions.
- Rewriting `draw_square` like this captures the relationship that we've spotted between squares and rectangles.
- A caller of this function might say `draw_square(tess, 50)`. The parameters of this function, `tx` and `sz`, are assigned the values of the `tess` object, and the `int 50` respectively.
- In the body of the function they are just like any other variable.
- When the call is made to `draw_rectangle`, the values in variables `tx` and `sz` are fetched first, then the call happens. So as we enter the top of function `draw_rectangle`, its variable `t` is assigned the `tess` object, and `w` and `h` in that function are both given the value `50`.

So far, it may not be clear why it is worth the trouble to create all of these new functions. Actually, there are a lot of reasons, but this example demonstrates two:

1. Creating a new function gives us an opportunity to name a group of statements. Functions can simplify a program by hiding a complex computation behind a single command. The function (including its name) can capture our mental chunking, or *abstraction*, of the problem.
2. Creating a new function can make a program smaller by eliminating repetitive code.

As we might expect, we have to create a function before we can execute it. In other words, the function definition has to be executed before the function is called.

4.3. Flow of execution

In order to ensure that a function is defined before its first use, we have to know the order in which statements are executed, which is called the **flow of execution**. We've already talked about this a little in the previous chapter.

Execution always begins at the first statement of the program. Statements are executed one at a time, in order from top to bottom.

Function definitions do not alter the flow of execution of the program, but remember that statements inside the function are not executed until the function is called. Although it is not common, we can define one function inside another. In this case, the inner definition isn't executed until the outer function is called.

Function calls are like a detour in the flow of execution. Instead of going to the next statement, the flow jumps to the first line of the called function, executes all the statements there, and then comes back to pick up where it left off.

That sounds simple enough, until we remember that one function can call another. While in the middle of one function, the program might have to execute the statements in another function. But while executing that new function, the program might have to execute yet another function!

Fortunately, Python is adept at keeping track of where it is, so each time a function completes, the program picks up where it left off in the function that called it. When it gets to the end of the program, it terminates.

What's the moral of this sordid tale? When we read a program, don't read from top to bottom. Instead, follow the flow of execution.

Watch the flow of execution in action

Repl.it does not have “single-stepping” functionality. For this we would recommend a different IDE like [PyScripter](#)⁶.

In PyScripter, we can watch the flow of execution by “single-stepping” through any program. PyScripter will highlight each line of code just before it is about to be executed.

PyScripter also lets us hover the mouse over any variable in the program, and it will pop up the current value of that variable. So this makes it easy to inspect the “state snapshot” of the program — the current values that are assigned to the program's variables.

This is a powerful mechanism for building a deep and thorough understanding of what is happening at each step of the way. Learn to use the single-stepping feature well, and be mentally proactive: as you work through the code, challenge yourself before each step: “*What changes will this line make to any variables in the program?*” and “Where will flow of execution go next?”

Let us go back and see how this works with the program above that draws 15 multicolor squares. First, we're going to add one line of magic below the import statement — not strictly necessary, but it will make our lives much simpler, because it prevents stepping into the module containing the turtle code.

```
1 import turtle
2 __import__("turtle").__traceable__ = False
```

Now we're ready to begin. Put the mouse cursor on the line of the program where we create the turtle screen, and press the F4 key. This will run the Python program up to, but not including, the line where we have the cursor. Our program will “break” now, and provide a highlight on the next line to be executed, something like this:

⁶<https://sourceforge.net/projects/pyscripter/>

```

• 1 import turtle
• 2 __import__("turtle").__traceable__ = False
  3
  4 def draw_multicolor_square(t, sz):
• 5     """Make turtle t draw a multi-color square of sz."""
• 6     for i in ["red", "purple", "hotpink", "blue"]:
• 7         t.color(i)
• 8         t.forward(sz)
• 9         t.left(90)
 10
• 11 wn = turtle.Screen()          # Set up the window and its attributes
• 12 wn.bgcolor("lightgreen")
 13
• 14 tess = turtle.Turtle()        # Create tess and set some attributes
• 15 tess.pensize(3)
 16
• 17 size = 20                     # Size of the smallest square
• 18 for i in range(15):
• 19     draw_multicolor_square(tess, size)
• 20     size = size + 10          # Increase the size for next time
• 21     tess.forward(10)         # Move tess along a little
• 22     tess.right(18)           # ... and give her some extra turn
 23
• 24 wn.mainloop()
 25

```

PyScripter Breakpoint

At this point we can press the F7 key (*step into*) repeatedly to single step through the code. Observe as we execute lines 10, 11, 12, ... how the turtle window gets created, how its canvas color is changed, how the title gets changed, how the turtle is created on the canvas, and then how the flow of execution gets into the loop, and from there into the function, and into the function's loop, and then repeatedly through the body of that loop.

While we do this, we can also hover our mouse over some of the variables in the program, and confirm that their values match our conceptual model of what is happening.

After a few loops, when we're about to execute line 20 and we're starting to get bored, we can use the key F8 to "step over" the function we are calling. This executes all the statements in the function, but without having to step through each one. We always have the choice to either "go for the detail", or to "take the high-level view" and execute the function as a single chunk.

There are some other options, including one that allow us to resume execution without further stepping. Find them under the *Run* menu of PyScripter.

4.4. Functions that require arguments

Most functions require arguments: the arguments provide for generalization. For example, if we want to find the absolute value of a number, we have to indicate what the number is. Python has a built-in function for computing the absolute value:

```
1 >>> abs(5)
2 5
3 >>> abs(-5)
4 5
```

In this example, the arguments to the `abs` function are 5 and -5.

Some functions take more than one argument. For example the built-in function `pow` takes two arguments, the base and the exponent. Inside the function, the values that are passed get assigned to variables called **parameters**.

```
1 >>> pow(2, 3)
2 8
3 >>> pow(7, 4)
4 2401
```

Another built-in function that takes more than one argument is `max`.

```
1 >>> max(7, 11)
2 11
3 >>> max(4, 1, 17, 2, 12)
4 17
5 >>> max(3 * 11, 5**3, 512 - 9, 1024**0)
6 503
```

`max` can be passed any number of arguments, separated by commas, and will return the largest value passed. The arguments can be either simple values or expressions. In the last example, 503 is returned, since it is larger than 33, 125, and 1.

4.5. Functions that return values

All the functions in the previous section return values. Furthermore, functions like `range`, `int`, `abs` all return values that can be used to build more complex expressions.

So an important difference between these functions and one like `draw_square` is that `draw_square` was not executed because we wanted it to compute a value — on the contrary, we wrote `draw_square` because we wanted it to execute a sequence of steps that caused the turtle to draw.

A function that returns a value is called a **fruitful function** in this book. The opposite of a fruitful function is **void function** — one that is not executed for its resulting value, but is executed because it does something useful. (Languages like Java, C#, C and C++ use the term “void function”, other languages like Pascal call it a **procedure**.) Even though void functions are not executed for their resulting value, Python always wants to return something. So if the programmer doesn’t arrange to return a value, Python will automatically return the value `None`.

How do we write our own fruitful function? In the exercises at the end of chapter 2 we saw the standard formula for compound interest, which we’ll now write as a fruitful function:

$$P' = P \left(1 + \frac{r}{n} \right)^{nt}$$

where:

P is the original principal sum

P' is the new principal sum

r is the **nominal annual interest rate**

n is the compounding frequency

t is the overall length of time the interest is applied (expressed using the same time units as r , usually years).

Compound interest

```

1  def final_amt(p, r, n, t):
2      """
3          Apply the compound interest formula to p
4          to produce the final amount.
5      """
6
7      a = p * (1 + r/n) ** (n*t)
8      return a          # This is new, and makes the function fruitful.
9
10 # now that we have the function above, let us call it.
11 toInvest = float(input("How much do you want to invest?"))
12 fnl = final_amt(toInvest, 0.08, 12, 5)
13 print("At the end of the period you'll have", fnl)
```

- The return statement is followed by an expression (a in this case). This expression will be evaluated and returned to the caller as the “fruit” of calling this function.
- We prompted the user for the principal amount. The type of `toInvest` is a string, but we need a number before we can work with it. Because it is money, and could have decimal places, we’ve used the `float` type converter function to parse the string and return a float.
- Notice how we entered the arguments for 8% interest, compounded 12 times per year, for 5 years.
- When we run this, we get the output

```
1 At the end of the period you'll have 14898.457083
```

This is a bit messy with all these decimal places, but remember that Python doesn't understand that we're working with money: it just does the calculation to the best of its ability, without rounding. Later we'll see how to format the string that is printed in such a way that it does get nicely rounded to two decimal places before printing.

- The line `toInvest = float(input("How much do you want to invest?"))` also shows yet another example of *composition* — we can call a function like `float`, and its arguments can be the results of other function calls (like `input`) that we've called along the way.

Notice something else very important here. The name of the variable we pass as an argument — `toInvest` — has nothing to do with the name of the parameter — `p`. It is as if `p = toInvest` is executed when `final_amt` is called. It doesn't matter what the value was named in the caller, in `final_amt` its name is `p`.

These short variable names are getting quite tricky, so perhaps we'd prefer one of these versions instead:

```
1 def final_amt_v2(principalAmount, nominalPercentageRate,
2                  numTimesPerYear, years):
3     a = principalAmount * (1 + nominalPercentageRate /
4                           numTimesPerYear) ** (numTimesPerYear*years)
5     return a
6
7 def final_amt_v3(amt, rate, compounded, years):
8     a = amt * (1 + rate/compounded) ** (compounded*years)
9     return a
```

They all do the same thing. Use your judgement to write code that can be best understood by other humans! Short variable names are more economical and sometimes make code easier to read: `E = mc2` would not be nearly so memorable if Einstein had used longer variable names! If you do prefer short names, make sure you also have some comments to enlighten the reader about what the variables are used for.

4.6. Variables and parameters are local

When we create a **local variable** inside a function, it only exists inside the function, and we cannot use it outside. For example, consider again this function:

```

1 def final_amt(p, r, n, t):
2     a = p * (1 + r/n) ** (n*t)
3     return a

```

If we try to use `a`, outside the function, we'll get an error:

```

1 >>> a
2 NameError: name 'a' is not defined

```

The variable `a` is local to `final_amt`, and is not visible outside the function.

Additionally, `a` only exists while the function is being executed — we call this its **lifetime**. When the execution of the function terminates, the local variables are destroyed.

Parameters are also local, and act like local variables. For example, the lifetimes of `p`, `r`, `n`, `t` begin when `final_amt` is called, and the lifetime ends when the function completes its execution.

So it is not possible for a function to set some local variable to a value, complete its execution, and then when it is called again next time, recover the local variable. Each call of the function creates new local variables, and their lifetimes expire when the function returns to the caller.

4.7. Turtles Revisited

Now that we have fruitful functions, we can focus our attention on reorganizing our code so that it fits more nicely into our mental chunks. This process of rearrangement is called **refactoring** the code.

Two things we're always going to want to do when working with turtles is to create the window for the turtle, and to create one or more turtles. We could write some functions to make these tasks easier in future:

```

1 def make_window(colr, ttle):
2     """
3     Set up the window with the given background color and title.
4     Returns the new window.
5     """
6     w = turtle.Screen()
7     w.bgcolor(colr)
8     w.title(ttle)
9     return w
10
11
12 def make_turtle(colr, sz):

```

```
13     """
14     Set up a turtle with the given color and pensize.
15     Returns the new turtle.
16     """
17     t = turtle.Turtle()
18     t.color(colr)
19     t.pensize(sz)
20     return t
21
22
23 wn = make_window("lightgreen", "Tess and Alex dancing")
24 tess = make_turtle("hotpink", 5)
25 alex = make_turtle("black", 1)
26 dave = make_turtle("yellow", 2)
```

The trick about refactoring code is to anticipate which things we are likely to want to change each time we call the function: these should become the parameters, or changeable parts, of the functions we write.

4.8. Glossary

argument

A value provided to a function when the function is called. This value is assigned to the corresponding parameter in the function. The argument can be the result of an expression which may involve operators, operands and calls to other fruitful functions.

body

The second part of a compound statement. The body consists of a sequence of statements all indented the same amount from the beginning of the header. The standard amount of indentation used within the Python community is 4 spaces.

compound statement

A statement that consists of two parts:

1. header - which begins with a keyword determining the statement type, and ends with a colon.
2. body - containing one or more statements indented the same amount from the header.

The syntax of a compound statement looks like this:

```
1 keyword ... :  
2     statement  
3     statement ...
```

docstring

A special string that is attached to a function as its `__doc__` attribute. Tools like Repl.it can use docstrings to provide documentation or hints for the programmer. When we get to modules, classes, and methods, we'll see that docstrings can also be used there.

flow of execution

The order in which statements are executed during a program run.

frame

A box in a stack diagram that represents a function call. It contains the local variables and parameters of the function.

function

A named sequence of statements that performs some useful operation. Functions may or may not take parameters and may or may not produce a result.

function call

A statement that executes a function. It consists of the name of the function followed by a list of arguments enclosed in parentheses.

function composition

Using the output from one function call as the input to another.

function definition

A statement that creates a new function, specifying its name, parameters, and the statements it executes.

fruitful function

A function that returns a value when it is called.

header line

The first part of a compound statement. A header line begins with a keyword and ends with a colon (:)

import statement

A statement which permits functions and variables defined in another Python module to be brought into the environment of another script. To use the features of the turtle, we need to first import the turtle module.

lifetime

Variables and objects have lifetimes — they are created at some point during program execution, and will be destroyed at some time.

local variable

A variable defined inside a function. A local variable can only be used inside its function. Parameters of a function are also a special kind of local variable.

parameter

A name used inside a function to refer to the value which was passed to it as an argument.

refactor

A fancy word to describe reorganizing our program code, usually to make it more understandable. Typically, we have a program that is already working, then we go back to “tidy it up”. It often involves choosing better variable names, or spotting repeated patterns and moving that code into a function.

stack diagram

A graphical representation of a stack of functions, their variables, and the values to which they refer.

traceback


A list of the functions that are executing, printed when a runtime error occurs. A traceback is also commonly referred to as a *stack trace*, since it lists the functions in the order in which they are stored in the [runtime stack](http://en.wikipedia.org/wiki/Runtime_stack).⁷

void function

The opposite of a fruitful function: one that does not return a value. It is executed for the work it does, rather than for the value it returns.

4.9. Exercises


1. Write a void (non-fruitful) function to draw a square. Use it in a program to draw the image shown below. Assume each side is 20 units. (*Hint: notice that the turtle has already moved away from the ending point of the last square when the program ends.*)



Five Squares


⁷http://en.wikipedia.org/wiki/Runtime_stack

2. Write a program to draw this. Assume the innermost square is 20 units per side, and each successive square is 20 units bigger, per side, than the one inside it.




Nested Squares

3. Write a void function `draw_poly(t, n, sz)` which makes a turtle draw a regular polygon. When called with `draw_poly(tess, 8, 50)`, it will draw a shape like this:




Regular polygon

4. Draw this pretty pattern.



Regular Polygon

5. The two spirals in this picture differ only by the turn angle. Draw both.




Spirals

6. Write a void function `draw_equitriangle(t, sz)` which calls `draw_poly` from the previous question to have its turtle draw an equilateral triangle.
7. Write a fruitful function `sum_to(n)` that returns the sum of all integer numbers up to and including `n`. So `sum_to(10)` would be `1+2+3...+10` which would return the value 55.
8. Write a function `area_of_circle(r)` which returns the area of a circle of radius `r`.
9. Write a void function to draw a star, where the length of each side is 100 units. (*Hint: You should turn the turtle by 144 degrees at each point.*)



Star

10. Extend your program above. Draw five stars, but between each, pick up the pen, move forward by 350 units, turn right by 144, put the pen down, and draw the next star. You'll get something like this:



Five Stars

What would it look like if you didn't pick up the pen?

Chapter 5: Conditionals

Programs get really interesting when we can test conditions and change the program behaviour depending on the outcome of the tests. That's what this chapter is about.

5.1. Boolean values and expressions

A Boolean value is either true or false. It is named after the British mathematician, George Boole, who first formulated Boolean algebra — some rules for reasoning about and combining these values. This is the basis of all modern computer logic.

In Python, the two Boolean values are `True` and `False` (the capitalization must be exactly as shown), and the Python type is `bool`.

```
1 >>> type(True)
2 <class 'bool'>
3 >>> type(true)
4 Traceback (most recent call last):
5   File "<interactive input>", line 1, in <module>
6   NameError: name 'true' is not defined
```

A **Boolean expression** is an expression that evaluates to produce a result which is a Boolean value. For example, the operator `==` tests if two values are equal. It produces (or *yields*) a Boolean value:

```
1 >>> 5 == (3 + 2)    # Is 5 equal to the result of 3 + 2?
2 True
3 >>> 5 == 6
4 False
5 >>> j = "hel"
6 >>> j + "lo" == "hello"
7 True
```

In the first statement, the two operands evaluate to equal values, so the expression evaluates to `True`; in the second statement, 5 is not equal to 6, so we get `False`.

The `==` operator is one of six common **comparison operators** which all produce a bool result; here are all six:

```

1  x == y          # Produce True if ... x is equal to y
2  x != y          # ... x is not equal to y
3  x > y           # ... x is greater than y
4  x < y           # ... x is less than y
5  x >= y          # ... x is greater than or equal to y
6  x <= y          # ... x is less than or equal to y

```

Although these operations are probably familiar, the Python symbols are different from the mathematical symbols. A common error is to use a single equal sign (=) instead of a double equal sign (==). Remember that = is an assignment operator and == is a comparison operator. Also, there is no such thing as =< or =>.

Like any other types we've seen so far, Boolean values can be assigned to variables, printed, etc.

```

1  >>> age = 18
2  >>> old_enough_to_get_driving_licence = age >= 17
3  >>> print(old_enough_to_get_driving_licence)
4  True
5  >>> type(old_enough_to_get_driving_licence)
6  <class 'bool'>

```

5.2. Logical operators

There are three **logical operators**, and, or, and not, that allow us to build more complex Boolean expressions from simpler Boolean expressions. The semantics (meaning) of these operators is similar to their meaning in English. For example, $x > 0$ and $x < 10$ produces True only if x is greater than 0 and at the same time, x is less than 10.

$n \% 2 == 0$ or $n \% 3 == 0$ is True if *either* of the conditions is True, that is, if the number n is divisible by 2 *or* it is divisible by 3. (What do you think happens if n is divisible by both 2 and by 3 at the same time? Will the expression yield True or False? Try it in your Python interpreter.)

Finally, the not operator negates a Boolean value, so not ($x > y$) is True if ($x > y$) is False, that is, if x is less than or equal to y .

The expression on the left of the or operator is evaluated first: if the result is True, Python does not (and need not) evaluate the expression on the right — this is called *short-circuit evaluation*. Similarly, for the and operator, if the expression on the left yields False, Python does not evaluate the expression on the right.

So there are no unnecessary evaluations.

5.3. Truth Tables

A truth table is a small table that allows us to list all the possible inputs, and to give the results for the logical operators. Because the `and` and `or` operators each have two operands, there are only four rows in a truth table that describes the semantics of `and`.

a	b	a and b
False	False	False
False	True	False
True	False	False
True	True	True

In a Truth Table, we sometimes use `T` and `F` as shorthand for the two Boolean values: here is the truth table describing `or`:

a	b	a or b
F	F	F
F	T	T
T	F	T
T	T	T

The third logical operator, `not`, only takes a single operand, so its truth table only has two rows:

a	not a
F	T
T	F

5.4. Simplifying Boolean Expressions

A set of rules for simplifying and rearranging expressions is called an algebra. For example, we are all familiar with school *algebra* rules, such as:

```
1 n * 0 == 0
```

Here we see a different algebra — the Boolean algebra — which provides rules for working with Boolean values.

First, the `and` operator:

```

1 x and False == False
2 False and x == False
3 y and x == x and y
4 x and True == x
5 True and x == x
6 x and x == x

```

Here are some corresponding rules for the or operator:

```

1 x or False == x
2 False or x == x
3 y or x == x or y
4 x or True == True
5 True or x == True
6 x or x == x

```

Two not operators cancel each other:

```

1 not (not x) == x

```

5.5. Conditional execution

In order to write useful programs, we almost always need the ability to check conditions and change the behavior of the program accordingly. **Conditional statements** give us this ability. The simplest form is the **if** statement:


```

1 if x % 2 == 0:
2     print(x, " is even.")
3     print("Did you know that 2 is the only even number that is prime?")
4 else:
5     print(x, " is odd.")
6     print("Did you know that multiplying two odd numbers " +
7           "always gives an odd result?")

```

The Boolean expression after the **if** statement is called the **condition**. If it is true, then all the indented statements get executed. If not, then all the statements indented under the **else** clause get executed.

Flowchart of an if statement with an else clause



Flowchart - if else

The syntax for an if statement looks like this:

```

1  if BOOLEAN_EXPRESSION:
2      STATEMENTS_1           # Executed if condition evaluates to True
3  else:
4      STATEMENTS_2           # Executed if condition evaluates to False
  
```

As with the function definition from the last chapter and other compound statements like `for`, the `if` statement consists of a header line and a body. The header line begins with the keyword `if` followed by a *Boolean expression* and ends with a colon (`:`).

The indented statements that follow are called a **block**. The first unindented statement marks the end of the block.


Each of the statements inside the first block of statements are executed in order if the Boolean expression evaluates to `True`. The entire first block of statements is skipped if the Boolean expression evaluates to `False`, and instead all the statements indented under the `else` clause are executed.

There is no limit on the number of statements that can appear under the two clauses of an `if` statement, but there has to be at least one statement in each block. Occasionally, it is useful to have a section with no statements (usually as a place keeper, or scaffolding, for code we haven't written yet). In that case, we can use the `pass` statement, which does nothing except act as a placeholder.

```
1 if True:           # This is always True,  
2     pass           # so this is always executed, but it does nothing  
3 else:  
4     pass
```

5.6. Omitting the else clause

Flowchart of an `if` statement with no `else` clause



Flowchart - if only

Another form of the `if` statement is one in which the `else` clause is omitted entirely. In this case, when the condition evaluates to `True`, the statements are executed, otherwise the flow of execution continues to the statement after the `if`.

```
1  if x < 0:
2      print("The negative number ", x, " is not valid here.")
3      x = 42
4      print("I've decided to use the number 42 instead.")
5
6  print("The square root of ", x, "is", math.sqrt(x))
```

In this case, the `print` function that outputs the square root is the one after the `if` — not because we left a blank line, but because of the way the code is indented. Note too that the function call `math.sqrt(x)` will give an error unless we have an `import math` statement, usually placed near the top of our script.

Python terminology

Python documentation sometimes uses the term **suite** of statements to mean what we have called a *block* here. They mean the same thing, and since most other languages and computer scientists use the word *block*, we'll stick with that.


Notice too that `else` is not a statement. The `if` statement has two clauses, one of which is the (optional) `else` clause.

5.7. Chained conditionals

Sometimes there are more than two possibilities and we need more than two branches. One way to express a computation like that is a **chained conditional**:

```
1  if x < y:
2      STATEMENTS_A
3  elif x > y:
4      STATEMENTS_B
5  else:
6      STATEMENTS_C
```

Flowchart of this chained conditional



Flowchart - chained conditional

`elif` is an abbreviation of `else if`. Again, exactly one branch will be executed. There is no limit of the number of `elif` statements but only a single (and optional) final `else` statement is allowed and it must be the last branch in the statement:


```
1 if choice == "a":
2     function_one()
3 elif choice == "b":
4     function_two()
5 elif choice == "c":
6     function_three()
7 else:
8     print("Invalid choice.")
```

Each condition is checked in order. If the first is false, the next is checked, and so on. If one of them is true, the corresponding branch executes, and the statement ends. Even if more than one condition is true, only the first true branch executes.

5.8. Nested conditionals

One conditional can also be **nested** within another. (It is the same theme of composability, again!) We could have written the previous example as follows:

Flowchart of this nested conditional



Flowchart - nested conditional

```
1 if x < y:
2     STATEMENTS_A
3 else:
4     if x > y:
5         STATEMENTS_B
6     else:
7         STATEMENTS_C
```

The outer conditional contains two branches. The second branch contains another `if` statement, which has two branches of its own. Those two branches could contain conditional statements as well.

Although the indentation of the statements makes the structure apparent, nested conditionals very quickly become difficult to read. In general, it is a good idea to avoid them when we can.

Logical operators often provide a way to simplify nested conditional statements. For example, we can rewrite the following code using a single conditional:

```
1  if 0 < x:                # Assume x is an int here
2      if x < 10:
3          print("x is a positive single digit.")
```

The `print` function is called only if we make it past both the conditionals, so instead of the above which uses two `if` statements each with a simple condition, we could make a more complex condition using the `and` operator. Now we only need a single `if` statement:

```
1  if 0 < x and x < 10:
2      print("x is a positive single digit.")
```

5.9. The return statement

The `return` statement, with or without a value, depending on whether the function is fruitful or void, allows us to terminate the execution of a function before (or when) we reach the end. One reason to use an *early return* is if we detect an error condition:

```
1  def print_square_root(x):
2      if x <= 0:
3          print("Positive numbers only, please.")
4          return
5
6      result = x**0.5
7      print("The square root of", x, "is", result)
```

The function `print_square_root` has a parameter named `x`. The first thing it does is check whether `x` is less than or equal to 0, in which case it displays an error message and then uses `return` to exit the function. The flow of execution immediately returns to the caller, and the remaining lines of the function are not executed.

5.10. Logical opposites

Each of the six relational operators has a logical opposite: for example, suppose we can get a driving licence when our age is greater or equal to 17, we can not get the driving licence when we are less than 17.

Notice that the opposite of `>=` is `<`.

operator	logical opposite
==	!=
!=	==
<	>=
<=	>
>	<=
>=	<

Understanding these logical opposites allows us to sometimes get rid of not operators. not operators are often quite difficult to read in computer code, and our intentions will usually be clearer if we can eliminate them.

For example, if we wrote this Python:

```
1 if not (age >= 17):
2     print("Hey, you're too young to get a driving licence!")
```

it would probably be clearer to use the simplification laws, and to write instead:

```
1 if age < 17:
2     print("Hey, you're too young to get a driving licence!")
```

Two powerful simplification laws (called de Morgan's laws) that are often helpful when dealing with complicated Boolean expressions are:

```
1 not (x and y) == (not x) or (not y)
2 not (x or y)  == (not x) and (not y)
```

For example, suppose we can slay the dragon only if our magic lightsabre sword is charged to 90% or higher, and we have 100 or more energy units in our protective shield. We find this fragment of Python code in the game:

```
1 if not ((sword_charge >= 0.90) and (shield_energy >= 100)):
2     print("Your attack has no effect, the dragon fries you to a crisp!")
3 else:
4     print("The dragon crumples in a heap. You rescue the gorgeous princess!")
```

de Morgan's laws together with the logical opposites would let us rework the condition in a (perhaps) easier to understand way like this:

```

1  if (sword_charge < 0.90) or (shield_energy < 100):
2      print("Your attack has no effect, the dragon fries you to a crisp!")
3  else:
4      print("The dragon crumples in a heap. You rescue the gorgeous princess!")

```

We could also get rid of the not by swapping around the then and else parts of the conditional. So here is a third version, also equivalent:

```

1  if (sword_charge >= 0.90) and (shield_energy >= 100):
2      print("The dragon crumples in a heap. You rescue the gorgeous princess!")
3  else:
4      print("Your attack has no effect, the dragon fries you to a crisp!")

```

This version is probably the best of the three, because it very closely matches the initial English statement. Clarity of our code (for other humans), and making it easy to see that the code does what was expected should always be a high priority.

As our programming skills develop we'll find we have more than one way to solve any problem. So good programs are *designed*. We make choices that favour clarity, simplicity, and elegance. The job title *software architect* says a lot about what we do — we are *architects* who engineer our products to balance beauty, functionality, simplicity and clarity in our creations.

Tip

Once our program works, we should play around a bit trying to polish it up. Write good comments. Think about whether the code would be clearer with different variable names. Could we have done it more elegantly? Should we rather use a function? Can we simplify the conditionals?

We think of our code as our creation, our work of art! We make it great.

5.11. Type conversion

We've had a first look at this in an earlier chapter. Seeing it again won't hurt!

Many Python types come with a built-in function that attempts to convert values of another type into its own type. The `int` function, for example, takes any value and converts it to an integer, if possible, or complains otherwise:

```

1  >>> int("32")
2  32
3  >>> int("Hello")
4  ValueError: invalid literal for int() with base 10: 'Hello'

```

`int` can also convert floating-point values to integers, but remember that it truncates the fractional part:


```
1 >>> int(-2.3)
2 -2
3 >>> int(3.99999)
4 3
5 >>> int("42")
6 42
7 >>> int(1.0)
8 1
```

The float function converts integers and strings to floating-point numbers:

```
1 >>> float(32)
2 32.0
3 >>> float("3.14159")
4 3.14159
5 >>> float(1)
6 1.0
```

It may seem odd that Python distinguishes the integer value 1 from the floating-point value 1.0. They may represent the same number, but they belong to different types. The reason is that they are represented differently inside the computer.

The str function converts any argument given to it to type string:

```
1 >>> str(32)
2 '32'
3 >>> str(3.14149)
4 '3.14149'
5 >>> str(True)
6 'True'
7 >>> str(true)
8 Traceback (most recent call last):
9   File "<interactive input>", line 1, in <module>
10 NameError: name 'true' is not defined
```

str will work with any value and convert it into a string. As mentioned earlier, True is a Boolean value; true is just an ordinary variable name, and is not defined here, so we get an error.

5.12. A Turtle Bar Chart

The turtle has a lot more power than we've seen so far. The full documentation can be found at <http://docs.python.org/py3k/library/turtle.html>.

Here are a couple of new tricks for our turtles:


- We can get a turtle to display text on the canvas at the turtle's current position. The method to do that is `alex.write("Hello")`.
- We can fill a shape (circle, semicircle, triangle, etc.) with a color. It is a two-step process. First we call the method `alex.begin_fill()`, then we draw the shape, then we call `alex.end_fill()`.
- We've previously set the color of our turtle — we can now also set its fill color, which need not be the same as the turtle and the pen color. We use `alex.color("blue", "red")` to set the turtle to draw in blue, and fill in red.

Ok, so can we get tess to draw a bar chart? Let us start with some data to be charted,

```
1 xs = [48, 117, 200, 240, 160, 260, 220]
```

Corresponding to each data measurement, we'll draw a simple rectangle of that height, with a fixed width.


```
1 def draw_bar(t, height):
2     """ Get turtle t to draw one bar, of height. """
3     t.left(90)
4     t.forward(height)    # Draw up the left side
5     t.right(90)
6     t.forward(40)        # Width of bar, along the top
7     t.right(90)
8     t.forward(height)    # And down again!
9     t.left(90)           # Put the turtle facing the way we found it.
10    t.forward(10)         # Leave small gap after each bar
11
12    ...
13    for v in xs:          # Assume xs and tess are ready
14        draw_bar(tess, v)
```



Simple bar chart

Ok, not fantastically impressive, but it is a nice start! The important thing here was the mental chunking, or how we broke the problem into smaller pieces. Our chunk is to draw one bar, and we wrote a function to do that. Then, for the whole chart, we repeatedly called our function.

Next, at the top of each bar, we'll print the value of the data. We'll do this in the body of `draw_bar`, by adding `t.write(' ' + str(height))` as the new third line of the body. We've put a little space in front of the number, and turned the number into a string. Without this extra space we tend to cramp our text awkwardly against the bar to the left. The result looks a lot better now:




Numbered bar chart

And now we'll add two lines to fill each bar. Our final program now looks like this:

```
1  import turtle
2
3  def draw_bar(t, height):
4      """ Get turtle t to draw one bar, of height. """
5      t.begin_fill()           # Added this line
6      t.left(90)
7      t.forward(height)
8      t.write("  "+ str(height))
9      t.right(90)
10     t.forward(40)
11     t.right(90)
12     t.forward(height)
13     t.left(90)
14     t.end_fill()             # Added this line
15     t.forward(10)
16
17 wn = turtle.Screen()         # Set up the window and its attributes
18 wn.bgcolor("lightgreen")
19
20 tess = turtle.Turtle()       # Create tess and set some attributes
21 tess.color("blue", "red")
22 tess.pensize(3)
23
24 xs = [48,117,200,240,160,260,220]
25
26 for a in xs:
27     draw_bar(tess, a)
28
29 wn.mainloop()
```

It produces the following, which is more satisfying:



Filled bar chart

Mmm. Perhaps the bars should not be joined to each other at the bottom. We'll need to pick up the pen while making the gap between the bars. We'll leave that (and a few more tweaks) as exercises for you!

5.13. Glossary

block

A group of consecutive statements with the same indentation.

body

The block of statements in a compound statement that follows the header.

Boolean algebra

Some rules for rearranging and reasoning about Boolean expressions.

Boolean expression

An expression that is either true or false.

Boolean value

There are exactly two Boolean values: `True` and `False`. Boolean values result when a Boolean expression is evaluated by the Python interpreter. They have type `bool`.

branch

One of the possible paths of the flow of execution determined by conditional execution.

chained conditional

A conditional branch with more than two possible flows of execution. In Python chained conditionals are written with `if ... elif ... else` statements.

comparison operator

One of the six operators that compares two values: `==`, `!=`, `>`, `<`, `>=`, and `<=`.

condition

The Boolean expression in a conditional statement that determines which branch is executed.

conditional statement

A statement that controls the flow of execution depending on some condition. In Python the keywords `if`, `elif`, and `else` are used for conditional statements.

logical operator

One of the operators that combines Boolean expressions: `and`, `or`, and `not`.

nesting

One program structure within another, such as a conditional statement inside a branch of another conditional statement.

prompt

A visual cue that tells the user that the system is ready to accept input data.

truth table

A concise table of Boolean values that can describe the semantics of an operator.

type conversion

An explicit function call that takes a value of one type and computes a corresponding value of another type.

wrapping code in a function

The process of adding a function header and parameters to a sequence of program statements is often referred to as “wrapping the code in a function”. This process is very useful whenever the program statements in question are going to be used multiple times. It is even more useful when it allows the programmer to express their mental chunking, and how they’ve broken a complex problem into pieces.

5.14. Exercises

1. Assume the days of the week are numbered 0, 1, 2, 3, 4, 5, 6 from Sunday to Saturday. Write a function which is given the day number, and it returns the day name (a string).

2. You go on a wonderful holiday (perhaps to jail, if you don't like happy exercises) leaving on day number 3 (a Wednesday). You return home after 137 sleeps. Write a general version of the program which asks for the starting day number, and the length of your stay, and it will tell you the name of day of the week you will return on.
3. Give the logical opposites of these conditions

```

1  a > b
2  a >= b
3  a >= 18 and day == 3
4  a >= 18 and day != 3

```

4. What do these expressions evaluate to?

```

1  3 == 3
2  3 != 3
3  3 >= 4
4  not (3 < 4)

```

5. Complete this truth table:

p	q	r	(not (p and q)) or r
F	F	F	?
F	F	T	?
F	T	F	?
F	T	T	?
T	F	F	?
T	F	T	?
T	T	F	?
T	T	T	?

6. Write a function which is given an exam mark, and it returns a string — the grade for that mark — according to this scheme:

Mark	Grade
>= 75	First
[70-75)	Upper Second
[60-70)	Second
[50-60)	Third
[45-50)	F1 Supp
[40-45)	F2
< 40	F3

The square and round brackets denote closed and open intervals. A closed interval includes the number, and open interval excludes it. So 39.99999 gets grade F3, but 40 gets grade F2. Assume

```

1  xs = [83, 75, 74.9, 70, 69.9, 65, 60, 59.9, 55, 50,
2         49.9, 45, 44.9, 40, 39.9, 2, 0]

```

Test your function by printing the mark and the grade for all the elements in this list.

7. Modify the turtle bar chart program so that the pen is up for the small gaps between each bar.
8. Modify the turtle bar chart program so that the bar for any value of 200 or more is filled with red, values between [100 and 200) are filled with yellow, and bars representing values less than 100 are filled with green.
9. In the turtle bar chart program, what do you expect to happen if one or more of the data values in the list is negative? Try it out. Change the program so that when it prints the text value for the negative bars, it puts the text below the bottom of the bar.
10. Write a function `find_hypot` which, given the length of two sides of a right-angled triangle, returns the length of the hypotenuse. (*Hint: $x ** 0.5$ will return the square root.*)
11. Write a function `is_rightangled` which, given the length of three sides of a triangle, will determine whether the triangle is right-angled. Assume that the third argument to the function is always the longest side. It will return `True` if the triangle is right-angled, or `False` otherwise.

Hint: Floating point arithmetic is not always exactly accurate, so it is not safe to test floating point numbers for equality. If a good programmer wants to know whether x is equal or close enough to y , they would probably code it up as:

```

1  if abs(x-y) < 0.000001:      # If x is approximately equal to y
2      ...

```

12. Extend the above program so that the sides can be given to the function in any order.
13. If you're intrigued by why floating point arithmetic is sometimes inaccurate, on a piece of paper, divide 10 by 3 and write down the decimal result. You'll find it does not terminate, so you'll need an infinitely long sheet of paper. The representation of numbers in computer memory or on your calculator has similar problems: memory is finite, and some digits may have to be discarded. So small inaccuracies creep in. Try this script:

```

1  import math
2  a = math.sqrt(2.0)
3  print(a, a*a)
4  print(a*a == 2.0)

```


Chapter 6: Fruitful functions

6.1. Return values

The built-in functions we have used, such as `abs`, `pow`, `int`, `max`, and `range`, have produced results. Calling each of these functions generates a value, which we usually assign to a variable or use as part of an expression.

```
1 biggest = max(3, 7, 2, 5)
2 x = abs(3 - 11) + 10
```

We also wrote our own function to return the final amount for a compound interest calculation.

In this chapter, we are going to write more functions that return values, which we will call *fruitful functions*, for want of a better name. The first example is `area`, which returns the area of a circle with the given radius:

```
1 def area(radius):
2     b = 3.14159 * radius**2
3     return b
```

We have seen the `return` statement before, but in a fruitful function the `return` statement includes a **return value**. This statement means: evaluate the return expression, and then return it immediately as the result (the fruit) of this function. The expression provided can be arbitrarily complicated, so we could have written this function like this:

```
1 def area(radius):
2     return 3.14159 * radius * radius
```

On the other hand, **temporary variables** like `b` above often make debugging easier.

Sometimes it is useful to have multiple `return` statements, one in each branch of a conditional. We have already seen the built-in `abs`, now we see how to write our own:

```
1 def absolute_value(x):
2     if x < 0:
3         return -x
4     else:
5         return x
```

Another way to write the above function is to leave out the `else` and just follow the `if` condition by the second `return` statement.

```
1 def absolute_value(x):
2     if x < 0:
3         return -x
4     return x
```

Think about this version and convince yourself it works the same as the first one.

Code that appears after a `return` statement, or any other place the flow of execution can never reach, is called **dead code**, or **unreachable code**.

In a fruitful function, it is a good idea to ensure that every possible path through the program hits a `return` statement. The following version of `absolute_value` fails to do this:

```
1 def bad_absolute_value(x):
2     if x < 0:
3         return -x
4     elif x > 0:
5         return x
```

This version is not correct because if `x` happens to be `0`, neither condition is true, and the function ends without hitting a `return` statement. In this case, the return value is a special value called **None**:

```
1 >>> print(bad_absolute_value(0))
2 None
```

All Python functions return `None` whenever they do not return another value.

It is also possible to use a `return` statement in the middle of a `for` loop, in which case control immediately returns from the function. Let us assume that we want a function which looks through a list of words. It should return the first 2-letter word. If there is not one, it should return the empty string:

```

1 def find_first_2_letter_word(xs):
2     for wd in xs:
3         if len(wd) == 2:
4             return wd
5     return ""

1 >>> find_first_2_letter_word(["This", "is", "a", "dead", "parrot"])
2 'is'
3 >>> find_first_2_letter_word(["I", "like", "cheese"])
4 ''

```

Single-step through this code and convince yourself that in the first test case that we've provided, the function returns while processing the second element in the list: it does not have to traverse the whole list.

6.2. Program development

At this point, you should be able to look at complete functions and tell what they do. Also, if you have been doing the exercises, you have written some small functions. As you write larger functions, you might start to have more difficulty, especially with runtime and semantic errors.

To deal with increasingly complex programs, we are going to suggest a technique called **incremental development**. The goal of incremental development is to avoid long debugging sessions by adding and testing only a small amount of code at a time.

As an example, suppose we want to find the distance between two points, given by the coordinates (x_1, y_1) and (x_2, y_2) . By the Pythagorean theorem, the distance is:

Distance formula

Distance formula

The first step is to consider what a distance function should look like in Python. In other words, what are the inputs (parameters) and what is the output (return value)?

In this case, the two points are the inputs, which we can represent using four parameters. The return value is the distance, which is a floating-point value.

Already we can write an outline of the function that captures our thinking so far:

```

1 def distance(x1, y1, x2, y2):
2     return 0.0

```

Obviously, this version of the function doesn't compute distances; it always returns zero. But it is syntactically correct, and it will run, which means that we can test it before we make it more complicated.

To test the new function, we call it with sample values:

```
1 >>> distance(1, 2, 4, 6)
2 0.0
```

We chose these values so that the horizontal distance equals 3 and the vertical distance equals 4; that way, the result is 5 (the hypotenuse of a 3-4-5 triangle). When testing a function, it is useful to know the right answer.

At this point we have confirmed that the function is syntactically correct, and we can start adding lines of code. After each incremental change, we test the function again. If an error occurs at any point, we know where it must be — in the last line we added.

A logical first step in the computation is to find the differences $x_2 - x_1$ and $y_2 - y_1$. We will refer to those values using temporary variables named `dx` and `dy`.

```
1 def distance(x1, y1, x2, y2):
2     dx = x2 - x1
3     dy = y2 - y1
4     return 0.0
```

If we call the function with the arguments shown above, when the flow of execution gets to the return statement, `dx` should be 3 and `dy` should be 4. We can check that this is the case in **PyScripter** by putting the cursor on the return statement, and running the program to break execution when it gets to the cursor (using the F4 key). Then we inspect the variables `dx` and `dy` by hovering the mouse above them, to confirm that the function is getting the right parameters and performing the first computation correctly. If not, there are only a few lines to check.

Next we compute the sum of squares of `dx` and `dy`:

```
1 def distance(x1, y1, x2, y2):
2     dx = x2 - x1
3     dy = y2 - y1
4     dsquared = dx*dx + dy*dy
5     return 0.0
```

Again, we could run the program at this stage and check the value of `dsquared` (which should be 25).

Finally, using the fractional exponent `0.5` to find the square root, we compute and return the result:

```
1 def distance(x1, y1, x2, y2):
2     dx = x2 - x1
3     dy = y2 - y1
4     dsquared = dx*dx + dy*dy
5     result = dsquared**0.5
6     return result
```

If that works correctly, you are done. Otherwise, you might want to inspect the value of `result` before the return statement.

When you start out, you might add only a line or two of code at a time. As you gain more experience, you might find yourself writing and debugging bigger conceptual chunks. Either way, stepping through your code one line at a time and verifying that each step matches your expectations can save you a lot of debugging time. As you improve your programming skills you should find yourself managing bigger and bigger chunks: this is very similar to the way we learned to read letters, syllables, words, phrases, sentences, paragraphs, etc., or the way we learn to chunk music — from individual notes to chords, bars, phrases, and so on.

The key aspects of the process are:

1. Start with a working skeleton program and make small incremental changes. At any point, if there is an error, you will know exactly where it is.
2. Use temporary variables to refer to intermediate values so that you can easily inspect and check them.
3. Once the program is working, relax, sit back, and play around with your options. (There is interesting research that links “playfulness” to better understanding, better learning, more enjoyment, and a more positive mindset about what you can achieve — so spend some time fiddling around!) You might want to consolidate multiple statements into one bigger compound expression, or rename the variables you’ve used, or see if you can make the function shorter. A good guideline is to aim for making code as easy as possible for others to read.

Here is another version of the function. It makes use of a square root function that is in the `math` module (we’ll learn about modules shortly). Which do you prefer? Which looks “closer” to the Pythagorean formula we started out with?

```
1 import math
2
3 def distance(x1, y1, x2, y2):
4     return math.sqrt( (x2-x1)**2 + (y2-y1)**2 )
```

```
1 >>> distance(1, 2, 4, 6)
2 5.0
```

6.3. Debugging with print

Another powerful technique for debugging (an alternative to single-stepping and inspection of program variables), is to **insert extra print functions in carefully selected places in your code**. Then, by inspecting the output of the program, you can check whether the algorithm is doing what you expect it to. Be clear about the following, however:

- You must have a clear solution to the problem, and must know what should happen before you can debug a program. Work on *solving* the problem on a piece of paper (perhaps using a flowchart to record the steps you take) *before* you concern yourself with writing code. Writing a program doesn't solve the problem — it simply *automates* the manual steps you would take. So first make sure you have a pen-and-paper manual solution that works. Programming then is about making those manual steps happen automatically.
- Do not write **chatterbox** functions. A chatterbox is a fruitful function that, in addition to its primary task, also asks the user for input, or prints output, when it would be more useful if it simply shut up and did its work quietly.

For example, we've seen built-in functions like `range`, `max` and `abs`. None of these would be useful building blocks for other programs if they prompted the user for input, or printed their results while they performed their tasks.

So a good tip is to **avoid calling print and input functions inside fruitful functions**, *unless the primary purpose of your function is to perform input and output*. The one exception to this rule might be to temporarily sprinkle some calls to `print` into your code to help debug and understand what is happening when the code runs, but these will then be removed once you get things working.

6.4. Composition

As you should expect by now, you can call one function from within another. This ability is called **composition**.

As an example, we'll write a function that takes two points, the center of the circle and a point on the perimeter, and computes the area of the circle.

Assume that the center point is stored in the variables `xc` and `yc`, and the perimeter point is in `xp` and `yp`. The first step is to find the radius of the circle, which is the distance between the two points. Fortunately, we've just written a function, `distance`, that does just that, so now all we have to do is use it:

```
1 radius = distance(xc, yc, xp, yp)
```

The second step is to find the area of a circle with that radius and return it. Again we will use one of our earlier functions:

```
1 result = area(radius)
2 return result
```

Wrapping that up in a function, we get:

```
1 def area2(xc, yc, xp, yp):
2     radius = distance(xc, yc, xp, yp)
3     result = area(radius)
4     return result
```

We called this function `area2` to distinguish it from the `area` function defined earlier.

The temporary variables `radius` and `result` are useful for development, debugging, and single-stepping through the code to inspect what is happening, but once the program is working, we can make it more concise by composing the function calls:

```
1 def area2(xc, yc, xp, yp):
2     return area(distance(xc, yc, xp, yp))
```

6.5. Boolean functions

Functions can return Boolean values, which is often convenient for hiding complicated tests inside functions. For example:

```
1 def is_divisible(x, y):
2     """ Test if x is exactly divisible by y """
3     if x % y == 0:
4         return True
5     else:
6         return False
```

It is common to give **Boolean functions** names that sound like yes/no questions. `is_divisible` returns either `True` or `False` to indicate whether the `x` is or is not divisible by `y`.

We can make the function more concise by taking advantage of the fact that the condition of the `if` statement is itself a Boolean expression. We can return it directly, avoiding the `if` statement altogether:

```
1 def is_divisible(x, y):  
2     return x % y == 0
```

This session shows the new function in action:

```
1 >>> is_divisible(6, 4)  
2 False  
3 >>> is_divisible(6, 3)  
4 True
```

Boolean functions are often used in conditional statements:

```
1 if is_divisible(x, y):  
2     ... # Do something ...  
3 else:  
4     ... # Do something else ...
```

It might be tempting to write something like:

```
1 if is_divisible(x, y) == True:
```

but the extra comparison is unnecessary.

6.6. Programming with style

Readability is very important to programmers, since in practice programs are read and modified far more often than they are written. But, like most rules, we occasionally break them. Most of the code examples in this book will be consistent with the *Python Enhancement Proposal 8* (PEP 8⁸), a style guide developed by the Python community.

We'll have more to say about style as our programs become more complex, but a few pointers will be helpful already:

- use 4 spaces (instead of tabs) for indentation
- limit line length to 78 characters
- when naming identifiers, use **CamelCase for classes** (we'll get to those) and **lowercase_with_underscores for functions and variables**
- place imports at the top of the file
- keep function definitions together
- use **docstrings** to document functions
- use two blank lines to separate function definitions from each other
- keep top level statements, including function calls, together at the bottom of the program

⁸<http://www.python.org/dev/peps/pep-0008/>

6.7. Unit testing

It is a common best practice in software development to include automatic **unit testing** of source code. Unit testing provides a way to automatically verify that individual pieces of code, such as functions, are working properly. This makes it possible to change the implementation of a function at a later time and quickly test that it still does what it was intended to do.

Some years back organizations had the view that their valuable asset was the program code and documentation. Organizations will now spend a large portion of their software budgets on crafting (and preserving) their tests.

Unit testing also forces the programmer to think about the different cases that the function needs to handle. You also only have to type the tests once into the script, rather than having to keep entering the same test data over and over as you develop your code.

Extra code in your program which is there because it makes debugging or testing easier is called **scaffolding**.

A collection of tests for some code is called its **test suite**.

There are a few different ways to do unit testing in Python — but at this stage we’re going to ignore what the Python community usually does, and we’re going to start with two functions that we’ll write ourselves. We’ll use these for writing our unit tests.

Let’s start with the `absolute_value` function that we wrote earlier in this chapter. Recall that we wrote a few different versions, the last of which was incorrect, and had a bug. Would tests have caught this bug?

First we plan our tests. We’d like to know if the function returns the correct value when its argument is negative, or when its argument is positive, or when its argument is zero. When planning your tests, you’ll always want to think carefully about the “edge” cases — here, an argument of 0 to `absolute_value` is on the edge of where the function behaviour changes, and as we saw at the beginning of the chapter, it is an easy spot for the programmer to make a mistake! So it is a good case to include in our test suite.

We’re going to write a helper function for checking the results of one test. It takes a boolean argument and will either print a message telling us that the test passed, or it will print a message to inform us that the test failed. The first line of the body (after the function’s docstring) magically determines the line number in the script where the call was made from. This allows us to print the line number of the test, which will help when we want to identify which tests have passed or failed.

```

1  import sys
2
3  def test(did_pass):
4      """ Print the result of a test. """
5      linenum = sys._getframe(1).f_lineno # Get the caller's line number.
6      if did_pass:
7          msg = "Test at line {0} ok.".format(linenum)
8      else:
9          msg = "Test at line {0} FAILED.".format(linenum)
10     print(msg)

```

There is also some slightly tricky string formatting using the format method which we will gloss over for the moment, and cover in detail in a future chapter. But with this function written, we can proceed to construct our test suite:

```

1  def test_suite():
2      """ Run the suite of tests for code in this module (this file). """
3
4      test(absolute_value(17) == 17)
5      test(absolute_value(-17) == 17)
6      test(absolute_value(0) == 0)
7      test(absolute_value(3.14) == 3.14)
8      test(absolute_value(-3.14) == 3.14)
9
10 test_suite() # Here is the call to run the tests

```

Here you'll see that we've constructed five tests in our test suite. We could run this against the first or second versions (the correct versions) of `absolute_value`, and we'd get output similar to the following:

```

1  Test at line 25 ok.
2  Test at line 26 ok.
3  Test at line 27 ok.
4  Test at line 28 ok.
5  Test at line 29 ok.

```

But let's say you change the function to an incorrect version like this:

```
1 def absolute_value(n):    # Buggy version
2     """ Compute the absolute value of n """
3     if n < 0:
4         return 1
5     elif n > 0:
6         return n
```

Can you find at least two mistakes in this code? Our test suite can! We get:

```
1 Test at line 25 ok.
2 Test at line 26 FAILED.
3 Test at line 27 FAILED.
4 Test at line 28 ok.
5 Test at line 29 FAILED.
```

These are three examples of *failing tests*.

There is a built-in Python statement called **assert** that does almost the same as our **test** function (except the program stops when the first assertion fails). You may want to read about it, and use it instead of our test function.

6.8. Glossary

Boolean function

A function that returns a Boolean value. The only possible values of the bool type are `False` and `True`.

chatterbox function

A function which interacts with the user (using `input` or `print`) when it should not. Silent functions that just convert their input arguments into their output results are usually the most useful ones.

composition (of functions)

Calling one function from within the body of another, or using the return value of one function as an argument to the call of another.

dead code

Part of a program that can never be executed, often because it appears after a `return` statement.

fruitful function

A function that yields a return value instead of `None`.

incremental development

A program development plan intended to simplify debugging by adding and testing only a small amount of code at a time.

None

A special Python value. One use in Python is that it is returned by functions that do not execute a return statement with a return argument.

return value

The value provided as the result of a function call.

scaffolding

Code that is used during program development to assist with development and debugging. The unit test code that we added in this chapter are examples of scaffolding.

temporary variable

A variable used to store an intermediate value in a complex calculation.

test suite

A collection of tests for some code you have written.

unit testing

An automatic procedure used to validate that individual units of code are working properly. Having a test suite is extremely useful when somebody modifies or extends the code: it provides a safety net against going backwards by putting new bugs into previously working code. The term *regression* testing is often used to capture this idea that we don't want to go backwards!

6.9. Exercises

All of the exercises below should be added to a single file. In that file, you should also add the test and test_suite scaffolding functions shown above, and then, as you work through the exercises, add the new tests to your test suite. (If you open the online version of the textbook, you can easily copy and paste the tests and the fragments of code into your Python editor.)

After completing each exercise, confirm that all the tests pass.

1. The four compass points can be abbreviated by single-letter strings as “N”, “E”, “S”, and “W”. Write a function `turn_clockwise` that takes one of these four compass points as its parameter, and returns the next compass point in the clockwise direction. Here are some tests that should pass:

```
1 test(turn_clockwise("N") == "E")
2 test(turn_clockwise("W") == "N")
```

You might ask “What if the argument to the function is some other value?” For all other cases, the function should return the value `None`:

```

1 test(turn_clockwise(42) == None)
2 test(turn_clockwise("rubbish") == None)

```

2. Write a function `day_name` that converts an integer number 0 to 6 into the name of a day. Assume day 0 is “Sunday”. Once again, return `None` if the arguments to the function are not valid. Here are some tests that should pass:

```

1 test(day_name(3) == "Wednesday")
2 test(day_name(6) == "Saturday")
3 test(day_name(42) == None)

```

3. Write the inverse function `day_num` which is given a day name, and returns its number:

```

1 test(day_num("Friday") == 5)
2 test(day_num("Sunday") == 0)
3 test(day_num(day_name(3)) == 3)
4 test(day_name(day_num("Thursday")) == "Thursday")

```

Once again, if this function is given an invalid argument, it should return `None`:

```

1 test(day_num("Halloween") == None)

```

4. Write a function that helps answer questions like “Today is Wednesday. I leave on holiday in 19 days time. What day will that be?” So the function must take a day name and a delta argument — the number of days to add — and should return the resulting day name:

```

1 test(day_add("Monday", 4) == "Friday")
2 test(day_add("Tuesday", 0) == "Tuesday")
3 test(day_add("Tuesday", 14) == "Tuesday")
4 test(day_add("Sunday", 100) == "Tuesday")

```

Hint: use the first two functions written above to help you write this one.

5. Can your `day_add` function already work with negative deltas? For example, -1 would be yesterday, or -7 would be a week ago:

```

1 test(day_add("Sunday", -1) == "Saturday")
2 test(day_add("Sunday", -7) == "Sunday")
3 test(day_add("Tuesday", -100) == "Sunday")

```

If your function already works, explain why. If it does not work, make it work.

Hint: Play with some cases of using the modulus function % (introduced at the beginning of the previous chapter). Specifically, explore what happens to $x \% 7$ when x is negative.

6. Write a function `days_in_month` which takes the name of a month, and returns the number of days in the month. Ignore leap years:

```

1 test(days_in_month("February") == 28)
2 test(days_in_month("December") == 31)

```

If the function is given invalid arguments, it should return `None`.

7. Write a function `to_secs` that converts hours, minutes and seconds to a total number of seconds. Here are some tests that should pass:

```

1 test(to_secs(2, 30, 10) == 9010)
2 test(to_secs(2, 0, 0) == 7200)
3 test(to_secs(0, 2, 0) == 120)
4 test(to_secs(0, 0, 42) == 42)
5 test(to_secs(0, -10, 10) == -590)

```

8. Extend `to_secs` so that it can cope with real values as inputs. It should always return an integer number of seconds (truncated towards zero):

```

1 test(to_secs(2.5, 0, 10.71) == 9010)
2 test(to_secs(2.433, 0, 0) == 8758)

```

9. Write three functions that are the “inverses” of `to_secs`:

1. `hours_in` returns the whole integer number of hours represented by a total number of seconds.
2. `minutes_in` returns the whole integer number of left over minutes in a total number of seconds, once the hours have been taken out.
3. `seconds_in` returns the left over seconds represented by a total number of seconds.

You may assume that the total number of seconds passed to these functions is an integer. Here are some test cases:

```

1 test(hours_in(9010) == 2)
2 test(minutes_in(9010) == 30)
3 test(seconds_in(9010) == 10)

```

It won't always be obvious what is wanted ...

In the third case above, the requirement seems quite ambiguous and fuzzy. But the test clarifies what we actually need to do.

Unit tests often have this secondary benefit of clarifying the specifications. If you write your own test suites, consider it part of the problem-solving process as you ask questions about what you really expect to happen, and whether you've considered all the possible cases.

Given our emphasis on *thinking like a computer scientist*, you might enjoy reading at least one reference about thinking, and about fun ideas like *fluid intelligence*, a key ingredient in problem solving. See, for example, <http://psychology.about.com/od/cognitivepsychology/a/fluid-crystal.htm>. Learning Computer Science requires a good mix of both fluid and crystallized kinds of intelligence.

10. Which of these tests fail? Explain why.

```

1 test(3 % 4 == 0)
2 test(3 % 4 == 3)
3 test(3 / 4 == 0)
4 test(3 // 4 == 0)
5 test(3+4 * 2 == 14)
6 test(4-2+2 == 0)
7 test(len("hello, world!") == 13)

```

11. Write a compare function that returns 1 if $a > b$, 0 if $a == b$, and -1 if $a < b$

```

1 test(compare(5, 4) == 1)
2 test(compare(7, 7) == 0)
3 test(compare(2, 3) == -1)
4 test(compare(42, 1) == 1)

```

12. Write a function called `hypotenuse` that returns the length of the hypotenuse of a right triangle given the lengths of the two legs as parameters:

```

1 test(hypotenuse(3, 4) == 5.0)
2 test(hypotenuse(12, 5) == 13.0)
3 test(hypotenuse(24, 7) == 25.0)
4 test(hypotenuse(9, 12) == 15.0)

```

13. Write a function `slope(x1, y1, x2, y2)` that returns the slope of the line through the points $(x1, y1)$ and $(x2, y2)$. Be sure your implementation of slope can pass the following tests:

```

1 test(slope(5, 3, 4, 2) == 1.0)
2 test(slope(1, 2, 3, 2) == 0.0)
3 test(slope(1, 2, 3, 3) == 0.5)
4 test(slope(2, 4, 1, 2) == 2.0)

```

Then use a call to `slope` in a new function named `intercept(x1, y1, x2, y2)` that returns the y-intercept of the line through the points $(x1, y1)$ and $(x2, y2)$

```

1 test(intercept(1, 6, 3, 12) == 3.0)
2 test(intercept(6, 1, 1, 6) == 7.0)
3 test(intercept(4, 6, 12, 8) == 5.0)

```

ini ngerjaiinnya gimana? TUOLONG
BANGET

14. Write a function called `is_even(n)` that takes an integer as an argument and returns `True` if the argument is an **even number** and `False` if it is **odd**.

Add your own tests to the test suite.

15. Now write the function `is_odd(n)` that returns `True` when n is odd and `False` otherwise. Include unit tests for this function too.

Finally, modify it so that it uses a call to `is_even` to determine if its argument is an odd integer, and ensure that its test still pass.

16. Write a function `is_factor(f, n)` that passes these tests:

```
1 test(is_factor(3, 12))
2 test(not is_factor(5, 12))
3 test(is_factor(7, 14))
4 test(not is_factor(7, 15))
5 test(is_factor(1, 15))
6 test(is_factor(15, 15))
7 test(not is_factor(25, 15))
```

An important role of unit tests is that they can also act as unambiguous “specifications” of what is expected. These test cases answer the question “Do we treat 1 and 15 as factors of 15”?

17. Write `is_multiple` to satisfy these unit tests:

```
1 test(is_multiple(12, 3))
2 test(is_multiple(12, 4))
3 test(not is_multiple(12, 5))
4 test(is_multiple(12, 6))
5 test(not is_multiple(12, 7))
```

Can you find a way to use `is_factor` in your definition of `is_multiple`?

18. Write the function `f2c(t)` designed to return the integer value of the nearest degree Celsius for given temperature in Fahrenheit. (*hint: you may want to make use of the built-in function, `round`. Try printing `round.__doc__` in a Python shell or looking up help for the `round` function, and experimenting with it until you are comfortable with how it works.*)

```
1 test(f2c(212) == 100)      # Boiling point of water
2 test(f2c(32) == 0)        # Freezing point of water
3 test(f2c(-40) == -40)     # Wow, what an interesting case!
4 test(f2c(36) == 2)
5 test(f2c(37) == 3)
6 test(f2c(38) == 3)
7 test(f2c(39) == 4)
```

19. Now do the opposite: write the function `c2f` which converts Celsius to Fahrenheit:

```
1 test(c2f(0) == 32)
2 test(c2f(100) == 212)
3 test(c2f(-40) == -40)
4 test(c2f(12) == 54)
5 test(c2f(18) == 64)
6 test(c2f(-48) == -54)
```


Chapter 7: Iteration

Computers are often used to automate repetitive tasks. Repeating identical or similar tasks without making errors is something that computers do well and people do poorly.

Repeated execution of a set of statements is called **iteration**. Because iteration is so common, Python provides several language features to make it easier. We've already seen the `for` statement in chapter 3. This the the form of iteration you'll likely be using most often. But in this chapter we've going to look at the `while` statement — another way to have your program do iteration, useful in slightly different circumstances.

Before we do that, let's just review a few ideas...

7.1. Assignment

As we have mentioned previously, it is legal to make more than one assignment to the same variable. A new assignment makes an existing variable refer to a new value (and stop referring to the old value).

```
1  airtime_remaining = 15
2  print(airtime_remaining)
3  airtime_remaining = 7
4  print(airtime_remaining)
```

The output of this program is:

```
1  15
2  7
```

because the first time `airtime_remaining` is printed, its value is 15, and the second time, its value is 7.

It is especially important to distinguish between an assignment statement and a Boolean expression that tests for equality. Because Python uses the equal token (`=`) for assignment, it is tempting to interpret a statement like `a = b` as a Boolean test. Unlike mathematics, it is not! Remember that the Python token for the equality operator is `==`.

Note too that an equality test is symmetric, but assignment is not. For example, if `a == 7` then `7 == a`. But in Python, the statement `a = 7` is legal and `7 = a` is not.

In Python, an assignment statement can make two variables equal, but because further assignments can change either of them, they don't have to stay that way:

```
1 a = 5
2 b = a    # After executing this line, a and b are now equal
3 a = 3    # After executing this line, a and b are no longer equal
```

The third line changes the value of `a` but does not change the value of `b`, so they are no longer equal. (In some programming languages, a different symbol is used for assignment, such as `<-` or `:=`, to avoid confusion. Some people also think that `variable` was an unfortunate word to choose, and instead we should have called them `assignables`. Python chooses to follow common terminology and token usage, also found in languages like C, C++, Java, and C#, so we use the tokens `=` for assignment, `==` for equality, and we talk of `variables`.

7.2. Updating variables

When an assignment statement is executed, the right-hand side expression (i.e. the expression that comes after the assignment token) is evaluated first. This produces a value. Then the assignment is made, so that the variable on the left-hand side now refers to the new value.

One of the most common forms of assignment is an update, where the new value of the variable depends on its old value. Deduct 40 cents from my airtime balance, or add one run to the scoreboard.

```
1 n = 5
2 n = 3 * n + 1
```

Line 2 means *get the current value of `n`, multiply it by three and add one, and assign the answer to `n`, thus making `n` refer to the value*. So after executing the two lines above, `n` will point/refer to the integer 16.

If you try to get the value of a variable that has never been assigned to, you'll get an error:

```
1 >>> w = x + 1
2 Traceback (most recent call last):
3   File "<interactive input>", line 1, in
4   NameError: name 'x' is not defined
```

Before you can update a variable, you have to **initialize** it to some starting value, usually with a simple assignment:

```
1 runs_scored = 0
2 ...
3 runs_scored = runs_scored + 1
```

Line 3 — updating a variable by adding 1 to it — is very common. It is called an **increment** of the variable; subtracting 1 is called a **decrement**. Sometimes programmers also talk about bumping a variable, which means the same as incrementing it by 1.

7.3. The `for` loop revisited

Recall that the `for` loop processes each item in a list. Each item in turn is (re-)assigned to the loop variable, and the body of the loop is executed. We saw this example in an earlier chapter:

```
1 for f in ["Joe", "Zoe", "Brad", "Angelina", "Zuki", "Thandi", "Paris"]:
2     invitation = "Hi " + f + ". Please come to my party on Saturday!"
3     print(invitation)
```

Running through all the items in a list is called **traversing** the list, or **traversal**.

Let us write a function now to sum up all the elements in a list of numbers. Do this by hand first, and try to isolate exactly what steps you take. You'll find you need to keep some "running total" of the sum so far, either on a piece of paper, in your head, or in your calculator. Remembering things from one step to the next is precisely why we have variables in a program: so we'll need some variable to remember the "running total". It should be initialized with a value of zero, and then we need to traverse the items in the list. For each item, we'll want to update the running total by adding the next number to it.

```
1 def mysum(xs):
2     """ Sum all the numbers in the list xs, and return the total. """
3     running_total = 0
4     for x in xs:
5         running_total = running_total + x
6     return running_total
7
8 # Add tests like these to your test suite ...
9 test(mysum([1, 2, 3, 4]) == 10)
10 test(mysum([1.25, 2.5, 1.75]) == 5.5)
11 test(mysum([1, -2, 3]) == 2)
12 test(mysum([ ]) == 0)
13 test(mysum(range(11)) == 55) # 11 is not included in the list.
```

7.4. The `while` statement

Here is a fragment of code that demonstrates the use of the `while` statement:

```

1  def sum_to(n):
2      """ Return the sum of 1+2+3 ... n """
3      ss = 0
4      v = 1
5      while v <= n:
6          ss = ss + v
7          v = v + 1
8      return ss
9
10 # For your test suite
11 test(sum_to(4) == 10)
12 test(sum_to(1000) == 500500)

```

You can almost read the `while` statement as if it were English. It means, while `v` is less than or equal to `n`, continue executing the body of the loop. Within the body, each time, increment `v`. When `v` passes `n`, return your accumulated sum.

More formally, here is precise flow of execution for a `while` statement:

- Evaluate the condition at line 5, yielding a value which is either `False` or `True`.
- If the value is `False`, exit the `while` statement and continue execution at the next statement (line 8 in this case).
- If the value is `True`, execute each of the statements in the body (lines 6 and 7) and then go back to the `while` statement at line 5.

The body consists of all of the statements indented below the `while` keyword.

Notice that if the loop condition is `False` the first time we get loop, the statements in the body of the loop are never executed.

The body of the loop should change the value of one or more variables so that eventually the condition becomes false and the loop terminates. Otherwise the loop will repeat forever, which is called an **infinite loop**. An endless source of amusement for computer scientists is the observation that the directions on shampoo, “lather, rinse, repeat”, are an infinite loop.

In the case here, we can prove that the loop terminates because we know that the value of `n` is finite, and we can see that the value of `v` increments each time through the loop, so eventually it will have to exceed `n`. In other cases, it is not so easy, even impossible in some cases, to tell if the loop will ever terminate.

What you will notice here is that the `while` loop is more work for you — the programmer — than the equivalent `for` loop. When using a `while` loop one has to manage the loop variable yourself: give it an initial value, test for completion, and then make sure you change something in the body so that the loop terminates. By comparison, here is an equivalent function that uses `for` instead:

```

1 def sum_to(n):
2     """ Return the sum of 1+2+3 ... n """
3     ss = 0
4     for v in range(n+1):
5         ss = ss + v
6     return ss

```

Notice the slightly tricky call to the `range` function — we had to add one onto `n`, because `range` generates its list up to but excluding the value you give it. It would be easy to make a programming mistake and overlook this, but because we’ve made the investment of writing some unit tests, our test suite would have caught our error.

So why have two kinds of loop if `for` looks easier? This next example shows a case where we need the extra power that we get from the `while` loop.

7.5. The Collatz $3n + 1$ sequence

Let’s look at a simple sequence that has fascinated and foxed mathematicians for many years. They still cannot answer even quite simple questions about this.

The “computational rule” for creating the sequence is to start from some given `n`, and to generate the next term of the sequence from `n`, either by halving `n`, (whenever `n` is even), or else by multiplying it by three and adding 1. The sequence terminates when `n` reaches 1.

This Python function captures that algorithm:

```

1 def seq3np1(n):
2     """ Print the 3n+1 sequence from n,
3     terminating when it reaches 1.
4     """
5     while n != 1:
6         print(n, end=", ")
7         if n % 2 == 0:           # n is even
8             n = n // 2
9         else:                   # n is odd
10            n = n * 3 + 1
11     print(n, end=".\n")

```

Notice first that the `print` function on line 6 has an extra argument `end=", "`. This tells the `print` function to follow the printed string with whatever the programmer chooses (in this case, a comma followed by a space), instead of ending the line. So each time something is printed in the loop, it is printed on the same output line, with the numbers separated by commas. The call to `print(n, end=".\n")` at line 11 after the loop terminates will then print the final value of `n` followed by a period and a newline character. (You’ll cover the `\n` (newline character) in the next chapter).

The condition for continuing with this loop is $n \neq 1$, so the loop will continue running until it reaches its termination condition, (i.e. $n == 1$).

Each time through the loop, the program outputs the value of n and then checks whether it is even or odd. If it is even, the value of n is divided by 2 using integer division. If it is odd, the value is replaced by $n * 3 + 1$. Here are some examples:

```

1 >>> seq3np1(3)
2 3, 10, 5, 16, 8, 4, 2, 1.
3 >>> seq3np1(19)
4 19, 58, 29, 88, 44, 22, 11, 34, 17, 52, 26, 13,
5         40, 20, 10, 5, 16, 8, 4, 2, 1.
6 >>> seq3np1(21)
7 21, 64, 32, 16, 8, 4, 2, 1.
8 >>> seq3np1(16)
9 16, 8, 4, 2, 1.
10 >>>

```

Since n sometimes increases and sometimes decreases, there is no obvious proof that n will ever reach 1, or that the program terminates. For some particular values of n , we can prove termination. For example, if the starting value is a power of two, then the value of n will be even each time through the loop until it reaches 1. The previous example ends with such a sequence, starting with 16.

See if you can find a small starting number that needs more than a hundred steps before it terminates.

Particular values aside, the interesting question was first posed by a German mathematician called Lothar Collatz: the *Collatz conjecture* (also known as the $3n + 1$ conjecture), is that this sequence terminates for all positive values of n . So far, no one has been able to prove it or disprove it! (A conjecture is a statement that might be true, but nobody knows for sure.)

Think carefully about what would be needed for a proof or disproof of the conjecture “All positive integers will eventually converge to 1 using the Collatz rules”. With fast computers we have been able to test every integer up to very large values, and so far, they have all eventually ended up at 1. But who knows? Perhaps there is some as-yet untested number which does not reduce to 1.

You’ll notice that if you don’t stop when you reach 1, the sequence gets into its own cyclic loop: 1, 4, 2, 1, 4, 2, 1, 4 ... So one possibility is that there might be other cycles that we just haven’t found yet.

Wikipedia has an informative article about the Collatz conjecture. The sequence also goes under other names (Hailstone sequence, Wonderous numbers, etc.), and you’ll find out just how many integers have already been tested by computer, and found to converge!

Choosing between for and while

Use a for loop if you know, before you start looping, the maximum number of times that you’ll need to execute the body. For example, if you’re traversing a list of elements, you know that the

maximum number of loop iterations you can possibly need is “all the elements in the list”. Or if you need to print the 12 times table, we know right away how many times the loop will need to run.

So any problem like “iterate this weather model for 1000 cycles”, or “search this list of words”, “find all prime numbers up to 10000” suggest that a `for` loop is best.

By contrast, if you are required to repeat some computation until some condition is met, and you cannot calculate in advance when (or if) this will happen, as we did in this $3n + 1$ problem, you’ll need a `while` loop.

We call the first case **definite iteration** — we know ahead of time some definite bounds for what is needed. The latter case is called **indefinite iteration** — we’re not sure how many iterations we’ll need — we cannot even establish an upper bound!

7.6. Tracing a program

To write effective computer programs, and to build a good conceptual model of program execution, a programmer needs to develop the ability to **trace** the execution of a computer program. Tracing involves becoming the computer and following the flow of execution through a sample program run, recording the state of all variables and any output the program generates after each instruction is executed.

To understand this process, let’s trace the call to `seq3np1(3)` from the previous section. At the start of the trace, we have a variable, `n` (the parameter), with an initial value of 3. Since 3 is not equal to 1, the `while` loop body is executed. 3 is printed and `3 % 2 == 0` is evaluated. Since it evaluates to `False`, the `else` branch is executed and `3 * 3 + 1` is evaluated and assigned to `n`.

To keep track of all this as you hand trace a program, make a column heading on a piece of paper for each variable created as the program runs and another one for output. Our trace so far would look something like this:

```

1  n                output printed so far
2  --                -----
3  3                3,
4  10
```

Since `10 != 1` evaluates to `True`, the loop body is again executed, and 10 is printed. `10 % 2 == 0` is `True`, so the `if` branch is executed and `n` becomes 5. By the end of the trace we have:

```

1  n          output printed so far
2  --          -----
3  3          3,
4  10         3, 10,
5  5          3, 10, 5,
6  16         3, 10, 5, 16,
7  8          3, 10, 5, 16, 8,
8  4          3, 10, 5, 16, 8, 4,
9  2          3, 10, 5, 16, 8, 4, 2,
10 1          3, 10, 5, 16, 8, 4, 2, 1.

```

Tracing can be a bit tedious and error prone (that's why we get computers to do this stuff in the first place!), but it is an essential skill for a programmer to have. From this trace we can learn a lot about the way our code works. We can observe that as soon as `n` becomes a power of 2, for example, the program will require $\log_2(n)$ executions of the loop body to complete. We can also see that the final 1 will not be printed as output within the body of the loop, which is why we put the special print function at the end.

Tracing a program is, of course, related to single-stepping through your code and being able to inspect the variables. Using the computer to **single-step** for you is less error prone and more convenient. Also, as your programs get more complex, they might execute many millions of steps before they get to the code that you're really interested in, so manual tracing becomes impossible. Being able to set a **breakpoint** where you need one is far more powerful. So we strongly encourage you to invest time in learning using to use your programming environment to full effect.

There are also some great visualization tools becoming available to help you trace and understand small fragments of Python code. The one we recommend is at <http://pythontutor.com/>

We've cautioned against chatterbox functions, but used them here. As we learn a bit more Python, we'll be able to show you how to generate a list of values to hold the sequence, rather than having the function print them. Doing this would remove the need to have all these pesky print functions in the middle of our logic, and will make the function more useful.

7.7. Counting digits

The following function counts the number of decimal digits in a positive integer:


```
1 def num_digits(n):
2     count = 0
3     while n != 0:
4         count = count + 1
5         n = n // 10
6     return count
```

A call to `print(num_digits(710))` will print 3. Trace the execution of this function call (perhaps using the single step function in PyScripter, or the Python visualizer, or on some paper) to convince yourself that it works.

This function demonstrates an important pattern of computation called a **counter**. The variable `count` is initialized to 0 and then incremented each time the loop body is executed. When the loop exits, `count` contains the result — the total number of times the loop body was executed, which is the same as the number of digits.

If we wanted to only count digits that are either 0 or 5, adding a conditional before incrementing the counter will do the trick:

```
1 def num_zero_and_five_digits(n):
2     count = 0
3     while n > 0:
4         digit = n % 10
5         if digit == 0 or digit == 5:
6             count = count + 1
7         n = n // 10
8     return count
```

Confirm that `test(num_zero_and_five_digits(1055030250) == 7)` passes.

Notice, however, that `test(num_digits(0) == 1)` fails. Explain why. Do you think this is a bug in the code, or a bug in the specifications, or our expectations, or the tests?

7.8. Abbreviated assignment

Incrementing a variable is so common that Python provides an abbreviated syntax for it:

```
1 >>> count = 0
2 >>> count += 1
3 >>> count
4 1
5 >>> count += 1
6 >>> count
7 2
```

`count += 1` is an abbreviation for `count = count + 1`. We pronounce the operator as “plus-equals”. The increment value does not have to be 1:


```
1 >>> n = 2
2 >>> n += 5
3 >>> n
4 7
```

There are similar abbreviations for `-=`, `*=`, `/=`, `//=` and `%=`:

```
1 >>> n = 2
2 >>> n *= 5
3 >>> n
4 10
5 >>> n -= 4
6 >>> n
7 6
8 >>> n //= 2
9 >>> n
10 3
11 >>> n %= 2
12 >>> n
13 1
```

7.9. Help and meta-notation

Python comes with extensive documentation for all its built-in functions, and its libraries. Different systems have different ways of accessing this help. In PyScripter, click on the Help menu item, and select Python Manuals. Then search for help on the built-in function `range`. You’ll get something like this:



Notice the square brackets in the description of the arguments. These are examples of **meta-notation** — notation that describes Python syntax, but is not part of it. The square brackets in this documentation mean that the argument is optional — the programmer can omit it. So what this first line of help tells us is that `range` must always have a `stop` argument, but it may have an optional `start` argument (which must be followed by a comma if it is present), and it can also have an optional `step` argument, preceded by a comma if it is present.

The examples from help show that `range` can have either 1, 2 or 3 arguments. The list can start at any starting value, and go up or down in increments other than 1. The documentation here also says that the arguments must be integers.

Other meta-notation you'll frequently encounter is the use of bold and italics. The bold means that these are tokens — keywords or symbols — typed into your Python code exactly as they are, whereas the italic terms stand for “something of this type”. So the syntax description

for *variable in list*:

means you can substitute any legal variable and any legal list when you write your Python code.

This (simplified) description of the `print` function, shows another example of meta-notation in which the ellipses (...) mean that you can have as many objects as you like (even zero), separated by commas:

print([*object*, ...])

Meta-notation gives us a concise and powerful way to describe the pattern of some syntax or feature.

7.10. Tables

One of the things loops are good for is generating tables. Before computers were readily available, people had to calculate logarithms, sines and cosines, and other mathematical functions by hand. To make that easier, mathematics books contained long tables listing the values of these functions. Creating the tables was slow and boring, and they tended to be full of errors.

When computers appeared on the scene, one of the initial reactions was, “*This is great! We can use the computers to generate the tables, so there will be no errors.*” That turned out to be true (mostly) but shortsighted. Soon thereafter, computers and calculators were so pervasive that the tables became obsolete.

Well, almost. For some operations, computers use tables of values to get an approximate answer and then perform computations to improve the approximation. In some cases, there have been errors in the underlying tables, most famously in the table the Intel Pentium processor chip used to perform floating-point division.

Although a log table is not as useful as it once was, it still makes a good example of iteration. The following program outputs a sequence of values in the left column and 2 raised to the power of that value in the right column:

```
1 for x in range(13):    # Generate numbers 0 to 12
2     print(x, "\t", 2**x)
```

The string “\t” represents a **tab character**. The backslash character in “\t” indicates the beginning of an **escape sequence**. Escape sequences are used to represent invisible characters like tabs and newlines. The sequence \n represents a **newline**.

An escape sequence can appear anywhere in a string; in this example, the tab escape sequence is the only thing in the string. How do you think you represent a backslash in a string?

As characters and strings are displayed on the screen, an invisible marker called the cursor keeps track of where the next character will go. After a `print` function, the cursor normally goes to the beginning of the next line.

The tab character shifts the cursor to the right until it reaches one of the tab stops. Tabs are useful for making columns of text line up, as in the output of the previous program:

1	0	1
2	1	2
3	2	4
4	3	8
5	4	16
6	5	32
7	6	64
8	7	128
9	8	256
10	9	512
11	10	1024
12	11	2048
13	12	4096

Because of the tab characters between the columns, the position of the second column does not depend on the number of digits in the first column.

7.11. Two-dimensional tables

A two-dimensional table is a table where you read the value at the intersection of a row and a column. A multiplication table is a good example. Let's say you want to print a multiplication table for the values from 1 to 6.

A good way to start is to write a loop that prints the multiples of 2, all on one line:

```
1 for i in range(1, 7):
2     print(2 * i, end=" ")
3 print()
```

Here we've used the `range` function, but made it start its sequence at 1. As the loop executes, the value of `i` changes from 1 to 6. When all the elements of the range have been assigned to `i`, the loop terminates. Each time through the loop, it displays the value of `2 * i`, followed by three spaces.

Again, the extra `end=" "` argument in the `print` function suppresses the newline, and uses three spaces instead. After the loop completes, the call to `print` at line 3 finishes the current line, and starts a new line.

The output of the program is:

```
1 2      4      6      8      10     12
```

So far, so good. The next step is to **encapsulate** and **generalize**.

7.12. Encapsulation and generalization

Encapsulation is the process of wrapping a piece of code in a function, allowing you to take advantage of all the things functions are good for. You have already seen some examples of encapsulation, including `is_divisible` in a previous chapter.

Generalization means taking something specific, such as printing the multiples of 2, and making it more general, such as printing the multiples of any integer.

This function encapsulates the previous loop and generalizes it to print multiples of `n`:

```
1 def print_multiples(n):
2     for i in range(1, 7):
3         print(n * i, end=" ")
4     print()
```

To encapsulate, all we had to do was add the first line, which declares the name of the function and the parameter list. To generalize, all we had to do was replace the value 2 with the parameter `n`.

If we call this function with the argument 2, we get the same output as before. With the argument 3, the output is:

```
1 3      6      9      12     15     18
```

With the argument 4, the output is:

```
1 4      8      12     16     20     24
```

By now you can probably guess how to print a multiplication table — by calling `print_multiples` repeatedly with different arguments. In fact, we can use another loop:

```
1 for i in range(1, 7):
2     print_multiples(i)
```

Notice how similar this loop is to the one inside `print_multiples`. All we did was replace the print function with a function call.

The output of this program is a multiplication table:

1	1	2	3	4	5	6
2	2	4	6	8	10	12
3	3	6	9	12	15	18
4	4	8	12	16	20	24
5	5	10	15	20	25	30
6	6	12	18	24	30	36

7.13. More encapsulation

To demonstrate encapsulation again, let's take the code from the last section and wrap it up in a function:

```
1 def print_mult_table():
2     for i in range(1, 7):
3         print_multiples(i)
```

This process is a common **development plan**. We develop code by writing lines of code outside any function, or typing them in to the interpreter. When we get the code working, we extract it and wrap it up in a function.

This development plan is particularly useful if you don't know how to divide the program into functions when you start writing. This approach lets you design as you go along.

7.14. Local variables



You might be wondering how we can use the same variable, `i`, in both `print_multiples` and `print_mult_table`. Doesn't it cause problems when one of the functions changes the value of the variable?

The answer is no, because the `i` in `print_multiples` and the `i` in `print_mult_table` are not the same variable.

Variables created inside a function definition are local; you can't access a local variable from outside its home function. **That means you are free to have multiple variables with the same name as long as they are not in the same function.**

Python examines all the statements in a function — if any of them assign a value to a variable, that is the clue that Python uses to make the variable a local variable.

The stack diagram for this program shows that the two variables named `i` are not the same variable. They can refer to different values, and changing one does not affect the other.

`print_mult_table``print_multiples`

Stack 2 diagram

The value of `i` in `print_mult_table` goes from 1 to 6. In the diagram it happens to be 3. The next time through the loop it will be 4. Each time through the loop, `print_mult_table` calls `print_multiples` with the current value of `i` as an argument. That value gets assigned to the parameter `n`.

Inside `print_multiples`, the value of `i` goes from 1 to 6. In the diagram, it happens to be 2. Changing this variable has no effect on the value of `i` in `print_mult_table`.

It is common and perfectly legal to have different local variables with the same name. In particular, names like `i` and `j` are used frequently as loop variables. If you avoid using them in one function just because you used them somewhere else, you will probably make the program harder to read.

The visualizer at <http://pythontutor.com/> shows very clearly how the two variables `i` are distinct variables, and how they have independent values.

7.15. The `break` statement

The `break` statement is used to immediately leave the body of its loop. The next statement to be executed is the first one after the body:


```

1  for i in [12, 16, 17, 24, 29]:
2      if i % 2 == 1: # If the number is odd
3          break      # ... immediately exit the loop
4      print(i)
5  print("done")

```

This prints:


```

1  12
2  16
3  done

```

The pre-test loop — standard loop behaviour

`for` and `while` loops do their tests at the start, before executing any part of the body. They're called **pre-test** loops, because the test happens before (pre) the body. `break` and `return` are our tools for adapting this standard behaviour.




7.16. Other flavours of loops

Sometimes we'd like to have the **middle-test** loop with the exit test in the middle of the body, rather than at the beginning or at the end. Or a **post-test** loop that puts its exit test as the last thing in the body. Other languages have different syntax and keywords for these different flavours, but Python just uses a combination of `while` and `if` condition: `break` to get the job done.

A typical example is a problem where the user has to input numbers to be summed. To indicate that there are no more inputs, the user enters a special value, often the value `-1`, or the empty string. This needs a middle-exit loop pattern: input the next number, then test whether to exit, or else process the number:

The middle-test loop flowchart



```

1 total = 0
2 while True:
3     response = input("Enter the next number. (Leave blank to end)")
4     if response == "":
5         break
6     total += int(response)
7 print("The total of the numbers you entered is ", total)

```

Convince yourself that this fits the middle-exit loop flowchart: line 3 does some useful work, lines 4 and 5 can exit the loop, and if they don't line 6 does more useful work before the next iteration starts.

The `while bool-expr:` uses the Boolean expression to determine whether to iterate again. `True` is a trivial Boolean expression, so `while True:` means always do the loop body again. This is a language idiom — a convention that most programmers will recognize immediately. Since the expression on line 2 will never terminate the loop, (it is a dummy test) the programmer must arrange to break (or return) out of the loop body elsewhere, in some other way (i.e. in lines 4 and 5 in this sample). A clever compiler or interpreter will understand that line 2 is a fake test that must always succeed, so it won't even generate a test, and our flowchart never even put the diamond-shape dummy test box at the top of the loop!

Similarly, by just moving the `if condition: break` to the end of the loop body we create a pattern for a post-test loop. Post-test loops are used when you want to be sure that the loop body always executes at least once (because the first test only happens at the end of the execution of the first loop body). This is useful, for example, if we want to play an interactive game against the user — we always want to play at least one game:

```

1 while True:
2     play_the_game_once()
3     response = input("Play again? (yes or no)")
4     if response != "yes":
5         break
6 print("Goodbye!")

```

Hint: Think about where you want the exit test to happen.

Once you've recognized that you need a loop to repeat something, think about its terminating condition — when will I want to stop iterating? Then figure out whether you need to do the test before starting the first (and every other) iteration, or at the end of the first (and every other) iteration, or perhaps in the middle of each iteration. Interactive programs that require input from the user or read from files often need to exit their loops in the middle or at the end of an iteration, when it becomes clear that there is no more data to process, or the user doesn't want to play our game anymore.

7.17. An example

The following program implements a simple guessing game:

```


1 import random                                # We cover random numbers in the
2 rng = random.Random()                        # modules chapter, so peek ahead.
3 number = rng.randrange(1, 1000) # Get random number between [1 and 1000).
4
5 guesses = 0
6 msg = ""
7
8 while True:
9     guess = int(input(msg + "\nGuess my number between 1 and 1000: "))
10    guesses += 1
11    if guess > number:
12        msg += str(guess) + " is too high.\n"
13    elif guess < number:
14        msg += str(guess) + " is too low.\n"
15    else:
16        break
17
18 input("\n\nGreat, you got it in {0} guesses!\n\n".format(guesses))

```

This program makes use of the mathematical law of **trichotomy** (given real numbers a and b , exactly one of these three must be true: $a > b$, $a < b$, or $a == b$).

At line 18 there is a call to the `input` function, but we don't do anything with the result, not even assign it to a variable. This is legal in Python. Here it has the effect of popping up the input dialog window and waiting for the user to respond before the program terminates. Programmers often use the trick of doing some extra input at the end of a script, just to keep the window open.

Also notice the use of the `msg` variable, initially an empty string, on lines 6, 12 and 14. Each time through the loop we extend the message being displayed: this allows us to display the program's feedback right at the same place as we're asking for the next guess.



7.18. The continue statement

This is a control flow statement that causes the program to immediately skip the processing of the rest of the body of the loop, for the current iteration. But the loop still carries on running for its remaining iterations:

```
1  for i in [12, 16, 17, 24, 29, 30]:
2      if i % 2 == 1:      # If the number is odd
3          continue      # Don't process it
4      print(i)
5  print("done")
```

This prints:

```
1  12
2  16
3  24
4  30
5  done
```

7.19. More generalization

As another example of generalization, imagine you wanted a program that would print a multiplication table of any size, not just the six-by-six table. You could add a parameter to `print_mult_table`:

```
1 def print_mult_table(high):
2     for i in range(1, high+1):
3         print_multiples(i)
```

We replaced the value 7 with the expression `high+1`. If we call `print_mult_table` with the argument 7, it displays:

```
1 1      2      3      4      5      6
2 2      4      6      8     10     12
3 3      6      9     12     15     18
4 4      8     12     16     20     24
5 5     10     15     20     25     30
6 6     12     18     24     30     36
7 7     14     21     28     35     42
```

This is fine, except that we probably want the table to be square — with the same number of rows and columns. To do that, we add another parameter to `print_multiples` to specify how many columns the table should have.

Just to be annoying, we call this parameter `high`, demonstrating that different functions can have parameters with the same name (just like local variables). Here's the whole program:

```
1 def print_multiples(n, high):
2     for i in range(1, high+1):
3         print(n * i, end=" ")
4     print()
5
6 def print_mult_table(high):
7     for i in range(1, high+1):
8         print_multiples(i, high)
```

Notice that when we added a new parameter, we had to change the first line of the function (the function heading), and we also had to change the place where the function is called in `print_mult_table`.

Now, when we call `print_mult_table(7)`:

1	1	2	3	4	5	6	7
2	2	4	6	8	10	12	14
3	3	6	9	12	15	18	21
4	4	8	12	16	20	24	28
5	5	10	15	20	25	30	35
6	6	12	18	24	30	36	42
7	7	14	21	28	35	42	49

When you generalize a function appropriately, you often get a program with capabilities you didn't plan. For example, you might notice that, because $ab = ba$, all the entries in the table appear twice. You could save ink by printing only half the table. To do that, you only have to change one line of `print_mult_table`. Change

```
1 print_multiples(i, high+1)
```

to

```
1 print_multiples(i, i+1)
```

and you get:

1	1						
2	2	4					
3	3	6	9				
4	4	8	12	16			
5	5	10	15	20	25		
6	6	12	18	24	30	36	
7	7	14	21	28	35	42	49

7.20. Functions

A few times now, we have mentioned all the things functions are good for. By now, you might be wondering what exactly those things are. Here are some of them:

1. Capturing your mental chunking. Breaking your complex tasks into sub-tasks, and giving the sub-tasks a meaningful name is a powerful mental technique. Look back at the example that illustrated the post-test loop: we assumed that we had a function called `play_the_game_once`. This chunking allowed us to put aside the details of the particular game — is it a card game, or noughts and crosses, or a role playing game — and simply focus on one isolated part of our program logic — letting the player choose whether they want to play again.

2. Dividing a long program into functions allows you to separate parts of the program, debug them in isolation, and then compose them into a whole.
3. Functions facilitate the use of iteration.
4. Well-designed functions are often useful for many programs. Once you write and debug one, you can reuse it.

7.21. Paired Data

We've already seen lists of names and lists of numbers in Python. We're going to peek ahead in the textbook a little, and show a more advanced way of representing our data. Making a pair of things in Python is as simple as putting them into parentheses, like this:

```
1 year_born = ("Paris Hilton", 1981)
```

We can put many pairs into a list of pairs:

```
1 celebs = [("Brad Pitt", 1963), ("Jack Nicholson", 1937),  
2          ("Justin Bieber", 1994)]
```

Here is a quick sample of things we can do with structured data like this. First, print all the celebs:

```
1 print(celebs)  
2 print(len(celebs))  
3 [("Brad Pitt", 1963), ("Jack Nicholson", 1937), ("Justin Bieber", 1994)]  
4 3
```

Notice that the celebs list has just 3 elements, each of them pairs.

Now we print the names of those celebrities born before 1980:

```
1 for (nm, yr) in celebs:  
2     if yr < 1980:  
3         print(nm)
```

```
1 Brad Pitt  
2 Jack Nicholson
```

This demonstrates something we have not seen yet in the `for` loop: instead of using a single loop control variable, we've used a pair of variable names, `(nm, yr)`, instead. The loop is executed three times — once for each pair in the list, and on each iteration both the variables are assigned values from the pair of data that is being handled.

7.22. Nested Loops for Nested Data

Now we'll come up with an even more adventurous list of structured data. In this case, we have a list of students. Each student has a name which is paired up with another list of subjects that they are enrolled for:

```
1 students = [  
2     ("John", ["CompSci", "Physics"]),  
3     ("Vusi", ["Maths", "CompSci", "Stats"]),  
4     ("Jess", ["CompSci", "Accounting", "Economics", "Management"]),  
5     ("Sarah", ["InfSys", "Accounting", "Economics", "CommLaw"]),  
6     ("Zuki", ["Sociology", "Economics", "Law", "Stats", "Music"])]
```

Here we've assigned a list of five elements to the variable `students`. Let's print out each student name, and the number of subjects they are enrolled for:

```
1 # Print all students with a count of their courses.  
2 for (name, subjects) in students:  
3     print(name, "takes", len(subjects), "courses")
```

Python agreeably responds with the following output:

```
1 John takes 2 courses  
2 Vusi takes 3 courses  
3 Jess takes 4 courses  
4 Sarah takes 4 courses  
5 Zuki takes 5 courses
```

Now we'd like to ask how many students are taking CompSci. This needs a counter, and for each student we need a second loop that tests each of the subjects in turn:

```
1 # Count how many students are taking CompSci  
2 counter = 0  
3 for (name, subjects) in students:  
4     for s in subjects: # A nested loop!  
5         if s == "CompSci":  
6             counter += 1  
7  
8 print("The number of students taking CompSci is", counter)
```



```
1 The number of students taking CompSci is 3
```

You should set up a list of your own data that interests you — perhaps a list of your CDs, each containing a list of song titles on the CD, or a list of movie titles, each with a list of movie stars who acted in the movie. You could then ask questions like “Which movies starred Angelina Jolie?”

7.23. Newton’s method for finding square roots

Loops are often used in programs that compute numerical results by starting with an approximate answer and iteratively improving it.

For example, before we had calculators or computers, people needed to calculate square roots manually. Newton used a particularly good method (there is some evidence that this method was known many years before). Suppose that you want to know the square root of n . If you start with almost any approximation, you can compute a better approximation (closer to the actual answer) with the following formula:

```
1 better = (approx + n/approx)/2
```

Repeat this calculation a few times using your calculator. Can you see why each iteration brings your estimate a little closer? One of the amazing properties of this particular algorithm is how quickly it converges to an accurate answer — a great advantage for doing it manually.

By using a loop and repeating this formula until the better approximation gets close enough to the previous one, we can write a function for computing the square root. (In fact, this is how your calculator finds square roots — it may have a slightly different formula and method, but it is also based on repeatedly improving its guesses.)

This is an example of an indefinite iteration problem: we cannot predict in advance how many times we’ll want to improve our guess — we just want to keep getting closer and closer. Our stopping condition for the loop will be when our old guess and our improved guess are “close enough” to each other.

Ideally, we’d like the old and new guess to be exactly equal to each other when we stop. But exact equality is a tricky notion in computer arithmetic when real numbers are involved. Because real numbers are not represented absolutely accurately (after all, a number like π or the square root of two has an infinite number of decimal places because it is irrational), we need to formulate the stopping test for the loop by asking “is a close enough to b”? This stopping condition can be coded like this:

```
1 if abs(a-b) < 0.001: # Make this smaller for better accuracy
2     break
```

Notice that we take the absolute value of the difference between a and b !

This problem is also a good example of when a middle-exit loop is appropriate:

```
1 def sqrt(n):
2     approx = n/2.0      # Start with some or other guess at the answer
3     while True:
4         better = (approx + n/approx)/2.0
5         if abs(approx - better) < 0.001:
6             return better
7         approx = better
8
9 # Test cases
10 print(sqrt(25.0))
11 print(sqrt(49.0))
12 print(sqrt(81.0))
```

The output is:

```
1 5.00000000002
2 7.0
3 9.0
```

See if you can improve the approximations by changing the stopping condition. Also, step through the algorithm (perhaps by hand, using your calculator) to see how many iterations were needed before it achieved this level of accuracy for `sqrt(25)`.

7.24. Algorithms

Newton's method is an example of an algorithm: it is a mechanical process for solving a category of problems (in this case, computing square roots).

Some kinds of knowledge are not algorithmic. For example, learning dates from history or your multiplication tables involves memorization of specific solutions.

But the techniques you learned for addition with carrying, subtraction with borrowing, and long division are all algorithms. Or if you are an avid Sudoku puzzle solver, you might have some specific set of steps that you always follow.

One of the characteristics of algorithms is that they do not require any intelligence to carry out. They are mechanical processes in which each step follows from the last according to a simple set of rules. And they're designed to solve a general class or category of problems, not just a single problem.

Understanding that hard problems can be solved by step-by-step algorithmic processes (and having technology to execute these algorithms for us) is one of the major breakthroughs that has had enormous benefits. So while the execution of the algorithm may be boring and may require no intelligence, algorithmic or computational thinking — i.e. using algorithms and automation as the basis for approaching problems — is rapidly transforming our society. Some claim that this shift

towards algorithmic thinking and processes is going to have even more impact on our society than the invention of the printing press. And the process of designing algorithms is interesting, intellectually challenging, and a central part of what we call programming.

Some of the things that people do naturally, without difficulty or conscious thought, are the hardest to express algorithmically. Understanding natural language is a good example. We all do it, but so far no one has been able to explain how we do it, at least not in the form of a step-by-step mechanical algorithm.

7.25. Glossary

algorithm

A step-by-step process for solving a category of problems.

body

The statements inside a loop.

breakpoint

A place in your program code where program execution will pause (or break), allowing you to inspect the state of the program's variables, or single-step through individual statements, executing them one at a time.

bump

Programmer slang. Synonym for increment.

continue statement

A statement that causes the remainder of the current iteration of a loop to be skipped. The flow of execution goes back to the top of the loop, evaluates the condition, and if this is true the next iteration of the loop will begin.

counter

A variable used to count something, usually initialized to zero and incremented in the body of a loop.

cursor

An invisible marker that keeps track of where the next character will be printed.

decrement

Decrease by 1.

definite iteration

A loop where we have an upper bound on the number of times the body will be executed. Definite iteration is usually best coded as a for loop.

development plan

A process for developing a program. In this chapter, we demonstrated a style of development based on developing code to do simple, specific things and then encapsulating and generalizing.

encapsulate

To divide a large complex program into components (like functions) and isolate the components from each other (by using local variables, for example).

escape sequence

An escape character, `\`, followed by one or more printable characters used to designate a non printable character.

generalize

To replace something unnecessarily specific (like a constant value) with something appropriately general (like a variable or parameter). Generalization makes code more versatile, more likely to be reused, and sometimes even easier to write.

increment

Both as a noun and as a verb, increment means to increase by 1.

infinite loop

A loop in which the terminating condition is never satisfied.

indefinite iteration

A loop where we just need to keep going until some condition is met. A `while` statement is used for this case.

initialization (of a variable)

To initialize a variable is to give it an initial value. Since in Python, variables don't exist until they are assigned values, they are initialized when they are created. In other programming languages this is not the case, and variables can be created without being initialized, in which case they have either default or garbage values.

iteration

Repeated execution of a set of programming statements.

loop

The construct that allows us to repeatedly execute a statement or a group of statements until a terminating condition is satisfied.

loop variable

A variable used as part of the terminating condition of a loop.

meta-notation

Extra symbols or notation that helps describe other notation. Here we introduced square brackets, ellipses, italics, and bold as meta-notation to help describe optional, repeatable, substitutable and fixed parts of the Python syntax.

middle-test loop

A loop that executes some of the body, then tests for the exit condition, and then may execute some more of the body. We don't have a special Python construct for this case, but can use `while` and `break` together.

nested loop

A loop inside the body of another loop.

newline

A special character that causes the cursor to move to the beginning of the next line.

post-test loop

A loop that executes the body, then tests for the exit condition. We don't have a special Python construct for this, but can use `while` and `break` together.

pre-test loop

A loop that tests before deciding whether to execute its body. `for` and `while` are both pre-test loops.

single-step

A mode of interpreter execution where you are able to execute your program one step at a time, and inspect the consequences of that step. Useful for debugging and building your internal mental model of what is going on.

tab

A special character that causes the cursor to move to the next tab stop on the current line.

trichotomy

Given any real numbers a and b , exactly one of the following relations holds: $a < b$, $a > b$, or $a == b$. Thus when you can establish that two of the relations are false, you can assume the remaining one is true.

trace

To follow the flow of execution of a program by hand, recording the change of state of the variables and any output produced.

7.26. Exercises

This chapter showed us how to sum a list of items, and how to count items. The counting example also had an `if` statement that let us only count some selected items. In the previous chapter we also

showed a function `find_first_2_letter_word` that allowed us an “early exit” from inside a loop by using `return` when some condition occurred. We now also have `break` to exit a loop but not the enclosing function, and `continue` to abandon the current iteration of the loop without ending the loop.

Composition of list traversal, summing, counting, testing conditions and early exit is a rich collection of building blocks that can be combined in powerful ways to create many functions that are all slightly different.

The first six questions are typical functions you should be able to write using only these building blocks.

1. Write a function to count how many odd numbers are in a list.
2. Sum up all the even numbers in a list.
3. Sum up all the negative numbers in a list.
4. Count how many words in a list have length 5.
5. Sum all the elements in a list up to but not including the first even number. (Write your unit tests. What if there is no even number?)
6. Count how many words occur in a list up to and including the first occurrence of the word “sam”. (Write your unit tests for this case too. What if “sam” does not occur?)
7. Add a print function to Newton’s `sqrt` function that prints out better each time it is calculated. Call your modified function with 25 as an argument and record the results.
8. Trace the execution of the last version of `print_mult_table` and figure out how it works.
9. Write a function `print_triangular_numbers(n)` that prints out the first `n` triangular numbers. A call to `print_triangular_numbers(5)` would produce the following output:

```

1  1      1
2  2      3
3  3      6
4  4     10
5  5     15

```

(hint: use a web search to find out what a triangular number is.)

10. Write a function, `is_prime`, which takes a single integer argument and returns `True` when the argument is a prime number and `False` otherwise. Add tests for cases like this:

```

1  test(is_prime(11))
2  test(not is_prime(35))
3  test(is_prime(19911121))

```

The last case could represent your birth date. Were you born on a prime day? In a class of 100 students, how many do you think would have prime birth dates?

11. Revisit the drunk pirate problem from the exercises in chapter 3. This time, the drunk pirate makes a turn, and then takes some steps forward, and repeats this. Our social science student now records pairs of data: the angle of each turn, and the number of steps taken after the turn. Her experimental data is [(160, 20), (-43, 10), (270, 8), (-43, 12)]. Use a turtle to draw the path taken by our drunk friend.
12. Many interesting shapes can be drawn by the turtle by giving a list of pairs like we did above, where the first item of the pair is the angle to turn, and the second item is the distance to move forward. Set up a list of pairs so that the turtle draws a house with a cross through the centre, as show here. This should be done without going over any of the lines / edges more than once, and without lifting your pen.



13. Not all shapes like the one above can be drawn without lifting your pen, or going over an edge more than once. Which of these can be drawn?



Now read Wikipedia's article (http://en.wikipedia.org/wiki/Eulerian_path) about Eulerian paths. Learn how to tell immediately by inspection whether it is possible to find a solution or not. If the path is possible, you'll also know where to put your pen to start drawing, and where you should end up!

14. What will `num_digits(0)` return? Modify it to return 1 for this case. Why does a call to `num_digits(-24)` result in an infinite loop? (hint: `-1//10` evaluates to `-1`) Modify `num_digits` so that it works correctly with any integer value. Add these tests:


```
1 test(num_digits(0) == 1)
2 test(num_digits(-12345) == 5)
```
15. Write a function `num_even_digits(n)` that counts the number of even digits in `n`. These tests should pass:

```

1 test(num_even_digits(123456) == 3)
2 test(num_even_digits(2468) == 4)
3 test(num_even_digits(1357) == 0)
4 test(num_even_digits(0) == 1)

```

16. Write a function `sum_of_squares(xs)` that computes the sum of the squares of the numbers in the list `xs`. For example, `sum_of_squares([2, 3, 4])` should return `4+9+16` which is `29`:

```

1 test(sum_of_squares([2, 3, 4]) == 29)
2 test(sum_of_squares([ ]) == 0)
3 test(sum_of_squares([2, -3, 4]) == 29)

```

17. You and your friend are in a team to write a two-player game, human against computer, such as Tic-Tac-Toe / Noughts and Crosses. Your friend will write the logic to play one round of the game, while you will write the logic to allow many rounds of play, keep score, decide who plays, first, etc. The two of you negotiate on how the two parts of the program will fit together, and you come up with this simple scaffolding (which your friend will improve later):

```

1 # Your friend will complete this function
2 def play_once(human_plays_first):
3     """
4     Must play one round of the game. If the parameter
5     is True, the human gets to play first, else the
6     computer gets to play first. When the round ends,
7     the return value of the function is one of
8     -1 (human wins), 0 (game drawn), 1 (computer wins).
9     """
10    # This is all dummy scaffolding code right at the moment...
11    import random # See Modules chapter ...
12    rng = random.Random()
13    # Pick a random result between -1 and 1.
14    result = rng.randrange(-1,2)
15    print("Human plays first={0}, winner={1} "
16          .format(human_plays_first, result))
17    return result

```

- Write the main program which repeatedly calls this function to play the game, and after each round it announces the outcome as “I win!”, “You win!”, or “Game drawn!”. It then asks the player “Do you want to play again?” and either plays again, or says “Goodbye”, and terminates.
- Keep score of how many wins each player has had, and how many draws there have been. After each round of play, also announce the scores.
- Add logic so that the players take turns to play first.
- Compute the percentage of wins for the human, out of all games played. Also announce this at the end of each round.

- e. Draw a flowchart of your logic.

Chapter 8: Strings

8.1. A compound data type

So far we have seen built-in types like `int`, `float`, `bool`, `str` and we've seen lists and pairs. Strings, lists, and pairs are qualitatively different from the others because they are made up of smaller pieces. In the case of strings, they're made up of smaller strings each containing one **character**

Types that comprise smaller pieces are called **compound data types**. Depending on what we are doing, we may want to treat a compound data type as a single thing, or we may want to access its parts. This ambiguity is useful.

8.2. Working with strings as single things

We previously saw that each turtle instance has its own attributes and a number of methods that can be applied to the instance. For example, we could set the turtle's color, and we wrote `tess.turn(90)`.

Just like a turtle, a string is also an object. So each string instance has its own attributes and methods.

For example:


```
1 >>> ss = "Hello, World!"
2 >>> tt = ss.upper()
3 >>> tt
4 'HELLO, WORLD!'
```

`upper` is a method that can be invoked on any string object to create a new string, in which all the characters are in uppercase. (The original string `ss` remains unchanged.)

There are also methods such as `lower`, `capitalize`, and `swapcase` that do other interesting stuff.

To learn what methods are available, you can consult the Help documentation, look for string methods, and read the documentation. Or, if you're a bit lazier, simply type the following into a PyScripter script:

When you type the period to select one of the methods of `ss`, PyScripter will pop up a selection window showing all the methods (there are around 70 of them — thank goodness we'll only use a few of those!) that could be used on your string.



When you type the name of the method, some further help about its parameter and return type, and its docstring, will be displayed. This is a good example of a tool — PyScripter — using the meta-information — the docstrings — provided by the module programmers.

```
greet = "Hello, World"
xx= greet.swapcase()
print(xx)
```

**** No/Unknown parameters ****
S.swapcase() -> str

Return a copy of S with uppercase characters converted to lowercase and vice versa.

8.3. Working with the parts of a string

The **indexing operator** (Python uses square brackets to enclose the index) selects a single character substring from a string:

```
1 >>> fruit = "banana"
2 >>> m = fruit[1]
3 >>> print(m)
```

The expression `fruit[1]` selects character number 1 from `fruit`, and creates a new string containing just this one character. The variable `m` refers to the result. When we display `m`, we could get a surprise:

```
1 a
```

Computer scientists always start counting from zero! The letter at subscript position zero of "banana" is b. So at position `[1]` we have the letter a.

If we want to access the zero-eth letter of a string, we just place 0, or any expression that evaluates to 0, inbetween the brackets:

```
1 >>> m = fruit[0]
2 >>> print(m)
3 b
```

The expression in brackets is called an **index**. An index specifies a member of an ordered collection, in this case the collection of characters in the string. The index *indicates* which one you want, hence the name. It can be any integer expression.

We can use `enumerate` to visualize the indices:

```
1 >>> fruit = "banana"
2 >>> list(enumerate(fruit))
3 [(0, 'b'), (1, 'a'), (2, 'n'), (3, 'a'), (4, 'n'), (5, 'a')]
```

Do not worry about `enumerate` at this point, we will see more of it in the chapter on lists.

Note that indexing returns a *string* — Python has no special type for a single character. It is just a string of length 1.

We've also seen lists previously. The same indexing notation works to extract elements from a list:

```
1 >>> prime_nums = [2, 3, 5, 7, 11, 13, 17, 19, 23, 29, 31]
2 >>> prime_nums[4]
3 11
4 >>> friends = ["Joe", "Zoe", "Brad", "Angelina", "Zuki", "Thandi", "Paris"]
5 >>> friends[3]
6 'Angelina'
```

8.4. Length

The `len` function, when applied to a string, returns the number of characters in a string:

```
1 >>> fruit = "banana"
2 >>> len(fruit)
3 6
```

To get the last letter of a string, you might be tempted to try something like this:

That won't work. It causes the runtime error `IndexError: string index out of range`. The reason is that there is no character at index position 6 in "banana". Because we start counting at zero, the six indexes are numbered 0 to 5. To get the last character, we have to subtract 1 from the length of `fruit`:

Alternatively, we can use negative indices, which count backward from the end of the string. The expression `fruit[-1]` yields the last letter, `fruit[-2]` yields the second to last, and so on.

As you might have guessed, indexing with a negative index also works like this for lists.

We won't use negative indexes in the rest of these notes — not many computer languages use this idiom, and you'll probably be better off avoiding it. But there is plenty of Python code out on the Internet that will use this trick, so it is best to know that it exists.

8.5. Traversal and the `for` loop

A lot of computations involve processing a string one character at a time. Often they start at the beginning, select each character in turn, do something to it, and continue until the end. This pattern of processing is called a **traversal**. One way to encode a traversal is with a `while` statement:

This loop traverses the string and displays each letter on a line by itself. The loop condition is `ix < len(fruit)`, so when `ix` is equal to the length of the string, the condition is false, and the body of the loop is not executed. The last character accessed is the one with the index `len(fruit)-1`, which is the last character in the string.

But we've previously seen how the `for` loop can easily iterate over the elements in a list and it can do so for strings as well:

Each time through the loop, the next character in the string is assigned to the variable `c`. The loop continues until no characters are left. Here we can see the expressive power the `for` loop gives us compared to the `while` loop when traversing a string.

The following example shows how to use concatenation and a `for` loop to generate an abecedarian series. Abecedarian refers to a series or list in which the elements appear in alphabetical order. For example, in Robert McCloskey's book *Make Way for Ducklings*, the names of the ducklings are Jack, Kack, Lack, Mack, Nack, Ouack, Pack, and Quack. This loop outputs these names in order:

The output of this program is:

```
1 Jack
2 Kack
3 Lack
4 Mack
5 Nack
6 Oack
7 Pack
8 Qack
```


Of course, that's not quite right because Ouack and Quack are misspelled. You'll fix this as an exercise below.

8.6. Slices

A *substring* of a string is obtained by taking a **slice**. Similarly, we can slice a list to refer to some sublist of the items in the list:

```
1 >>> s = "Pirates of the Caribbean"
2 >>> print(s[0:7])
3 Pirates
4 >>> print(s[11:14])
5 the
6 >>> print(s[15:24])
7 Caribbean
8 >>> friends = ["Joe", "Zoe", "Brad", "Angelina", "Zuki", "Thandi", "Paris"]
9 >>> print(friends[2:4])
10 ['Brad', 'Angelina']
```

The operator `[n:m]` returns the part of the string from the `n`'th character to the `m`'th character, including the first but excluding the last. This behavior makes sense if you imagine the indices pointing *between* the characters, as in the following diagram:



If you imagine this as a piece of paper, the slice operator `[n:m]` copies out the part of the paper between the `n` and `m` positions. Provided `m` and `n` are both within the bounds of the string, your result will be of length `(m-n)`.

Three tricks are added to this: if you omit the first index (before the colon), the slice starts at the beginning of the string (or list). If you omit the second index, the slice extends to the end of the string (or list). Similarly, if you provide value for `n` that is bigger than the length of the string (or list), the slice will take all the values up to the end. (It won't give an "out of range" error like the normal indexing operation does.) Thus:

```

1 >>> fruit = "banana"
2 >>> fruit[:3]
3 'ban'
4 >>> fruit[3:]
5 'ana'
6 >>> fruit[3:999]
7 'ana'

```

What do you think `s[:]` means? What about `friends[4:]`?

8.7. String comparison

The comparison operators work on strings. To see if two strings are equal:

Other comparison operations are useful for putting words in lexicographical order:

This is similar to the alphabetical order you would use with a dictionary, except that all the uppercase letters come before all the lowercase letters. As a result:

```
1 Your word, Zebra, comes before banana.
```

A common way to address this problem is to convert strings to a standard format, such as all lowercase, before performing the comparison. A more difficult problem is making the program realize that zebras are not fruit.

8.8. Strings are immutable

It is tempting to use the `[]` operator on the left side of an assignment, with the intention of changing a character in a string. For example:

Instead of producing the output `Jello, world!`, this code produces the runtime error `TypeError: 'str' object does not support item assignment`.

Strings are **immutable**, which means you can't change an existing string. The best you can do is create a new string that is a variation on the original:

The solution here is to concatenate a new first letter onto a slice of `greeting`. This operation has no effect on the original string.

8.9. The `in` and `not in` operators

The `in` operator tests for membership. When both of the arguments to `in` are strings, `in` checks whether the left argument is a substring of the right argument.

```
1 >>> "p" in "apple"
2 True
3 >>> "i" in "apple"
4 False
5 >>> "ap" in "apple"
6 True
7 >>> "pa" in "apple"
8 False
```

Note that a string is a substring of itself, and the empty string is a substring of any other string. (Also note that computer scientists like to think about these edge cases quite carefully!)


```
1 >>> "a" in "a"
2 True
3 >>> "apple" in "apple"
4 True
5 >>> "" in "a"
6 True
7 >>> "" in "apple"
8 True
```

The `not in` operator returns the logical opposite results of `in`:

```
1 >>> "x" not in "apple"
2 True
```

Combining the `in` operator with string concatenation using `+`, we can write a function that removes all the vowels from a string:

```
1 def remove_vowels(s):
2     vowels = "aeiouAEIOU"
3     s_sans_vowels = ""
4     for x in s:
5         if x not in vowels:
6             s_sans_vowels += x
7     return s_sans_vowels
8
9 test(remove_vowels("compsci") == "cmpsc")
10 test(remove_vowels("aAbEefIijOopUus") == "bfjps")
```

8.10. A `find` function

What does the following function do?

```
1 def find(strng, ch):
2     """
3     Find and return the index of ch in strng.
4     Return -1 if ch does not occur in strng.
5     """
6     ix = 0
7     while ix < len(strng):
8         if strng[ix] == ch:
9             return ix
```

```

10         ix += 1
11     return -1
12
13 test(find("CompSci", "p") == 3)
14 test(find("CompSci", "C") == 0)
15 test(find("CompSci", "i") == 6)
16 test(find("CompSci", "x") == -1)

```

In a sense, `find` is the opposite of the indexing operator. Instead of taking an index and extracting the corresponding character, it takes a character and finds the index where that character appears. If the character is not found, the function returns `-1`.

This is another example where we see a `return` statement inside a loop. If `strng[ix] == ch`, the function returns immediately, breaking out of the loop prematurely.

If the character doesn't appear in the string, then the program exits the loop normally and returns `-1`.

This pattern of computation is sometimes called a **eureka traversal** or **short-circuit evaluation**, because as soon as we find what we are looking for, we can cry “Eureka!”, take the short-circuit, and stop looking.

8.11. Looping and counting

The following program counts the number of times the letter `a` appears in a string, and is another example of the counter pattern introduced in counting.

```

1 def count_a(text):
2     count = 0
3     for c in text:
4         if c == "a":
5             count += 1
6     return(count)
7
8 test(count_a("banana") == 3)

```

8.12. Optional parameters

To find the locations of the second or third occurrence of a character in a string, we can modify the `find` function, adding a third parameter for the starting position in the search string:

```

1 def find2(strng, ch, start):
2     ix = start
3     while ix < len(strng):
4         if strng[ix] == ch:
5             return ix
6         ix += 1
7     return -1
8
9 test(find2("banana", "a", 2) == 3)

```

The call `find2("banana", "a", 2)` now returns 3, the index of the first occurrence of “a” in “banana” starting the search at index 2. What does `find2("banana", "n", 3)` return? If you said, 4, there is a good chance you understand how `find2` works.

Better still, we can combine `find` and `find2` using an **optional parameter**:

```

1 def find(strng, ch, start=0):
2     ix = start
3     while ix < len(strng):
4         if strng[ix] == ch:
5             return ix
6         ix += 1
7     return -1

```

When a function has an optional parameter, the caller may provide a matching argument. If the third argument is provided to `find`, it gets assigned to `start`. But if the caller leaves the argument out, then `start` is given a default value indicated by the assignment `start=0` in the function definition.

So the call `find("banana", "a", 2)` to this version of `find` behaves just like `find2`, while in the call `find("banana", "a")`, `start` will be set to the **default value** of 0.

Adding another optional parameter to `find` makes it search from a starting position, up to but not including the end position:

```

1 def find(strng, ch, start=0, end=None):
2     ix = start
3     if end is None:
4         end = len(strng)
5     while ix < end:
6         if strng[ix] == ch:
7             return ix
8         ix += 1
9     return -1

```

The optional value for `end` is interesting: we give it a default value `None` if the caller does not supply any argument. In the body of the function we test what `end` is, and if the caller did not supply any argument, we reassign `end` to be the length of the string. If the caller has supplied an argument for `end`, however, the caller's value will be used in the loop.

The semantics of `start` and `end` in this function are precisely the same as they are in the `range` function.

Here are some test cases that should pass:

```
1 ss = "Python strings have some interesting methods."
2 test(find(ss, "s") == 7)
3 test(find(ss, "s", 7) == 7)
4 test(find(ss, "s", 8) == 13)
5 test(find(ss, "s", 8, 13) == -1)
6 test(find(ss, ".") == len(ss)-1)
```

8.13. The built-in `find` method

Now that we've done all this work to write a powerful `find` function, we can reveal that strings already have their own built-in `find` method. It can do everything that our code can do, and more!

The built-in `find` method is more general than our version. It can find substrings, not just single characters:

```
1 >>> "banana".find("nan")
2
3 >>> "banana".find("na", 3)
4 4
```

Usually we'd prefer to use the methods that Python provides rather than reinvent our own equivalents. But many of the built-in functions and methods make good teaching exercises, and the underlying techniques you learn are your building blocks to becoming a proficient programmer.

8.14. The `split` method

One of the most useful methods on strings is the `split` method: it splits a single multi-word string into a list of individual words, removing all the whitespace between them. (Whitespace means any tabs, newlines, or spaces.) This allows us to read input as a single string, and split it into words.

```

1 >>> ss = "Well I never did said Alice"
2 >>> wds = ss.split()
3 >>> wds
4 ['Well', 'I', 'never', 'did', 'said', 'Alice']

```

8.15. Cleaning up your strings

We'll often work with strings that contain punctuation, or tab and newline characters, especially, as we'll see in a future chapter, when we read our text from files or from the Internet. But if we're writing a program, say, to count word frequencies or check the spelling of each word, we'd prefer to strip off these unwanted characters.

We'll show just one example of how to strip punctuation from a string. Remember that strings are immutable, so we cannot change the string with the punctuation — we need to traverse the original string and create a new string, omitting any punctuation:

```

1 punctuation = "!\"#$%&'()*+,-./:;<=>?@[\\]^_`{|}~"
2
3 def remove_punctuation(s):
4     s_sans_punct = ""
5     for letter in s:
6         if letter not in punctuation:
7             s_sans_punct += letter
8     return s_sans_punct

```

Setting up that first assignment is messy and error-prone. Fortunately, the Python string module already does it for us. So we will make a slight improvement to this program — we'll import the string module and use its definition:

```

1 import string
2
3 def remove_punctuation(s):
4     s_without_punct = ""
5     for letter in s:
6         if letter not in string.punctuation:
7             s_without_punct += letter
8     return s_without_punct
9
10 test(remove_punctuation('Well, I never did!', said Alice.') ==
11      "Well I never did said Alice")
12 test(remove_punctuation("Are you very, very, sure?") ==
13      "Are you very very sure")

```

Composing together this function and the `split` method from the previous section makes a useful combination — we'll clean out the punctuation, and `split` will clean out the newlines and tabs while turning the string into a list of words:

```

1 my_story = """
2 Pythons are constrictors, which means that they will 'squeeze' the life
3 out of their prey. They coil themselves around their prey and with
4 each breath the creature takes the snake will squeeze a little tighter
5 until they stop breathing completely. Once the heart stops the prey
6 is swallowed whole. The entire animal is digested in the snake's
7 stomach except for fur or feathers. What do you think happens to the fur,
8 feathers, beaks, and eggshells? The 'extra stuff' gets passed out as ---
9 you guessed it --- snake POOP! """
10
11 wds = remove_punctuation(my_story).split()
12 print(wds)

```

The output:

```

1 ['Pythons', 'are', 'constrictors', ... , 'it', 'snake', 'POOP']

```

There are other useful string methods, but this book isn't intended to be a reference manual. On the other hand, the *Python Library Reference* is. Along with a wealth of other documentation, it is available at the [Python website](https://www.python.org/)⁹.

8.16. The string format method

The easiest and most powerful way to format a string in Python 3 is to use the `format` method. To see how this works, let's start with a few examples:

```

1 s1 = "His name is {0}!".format("Arthur")
2 print(s1)
3
4 name = "Alice"
5 age = 10
6 s2 = "I am {1} and I am {0} years old.".format(age, name)
7 print(s2)
8
9 n1 = 4
10 n2 = 5
11 s3 = "2**10 = {0} and {1} * {2} = {3:f}".format(2**10, n1, n2, n1 * n2)
12 print(s3)

```

⁹<https://www.python.org/>

Running the script produces:

```
1 His name is Arthur!
2 I am Alice and I am 10 years old.
3 2**10 = 1024 and 4 * 5 = 20.000000
```

The template string contains place holders, ... {0} ... {1} ... {2} ... etc. The format method substitutes its arguments into the place holders. The numbers in the place holders are indexes that determine which argument gets substituted — make sure you understand line 6 above!

But there's more! Each of the replacement fields can also contain a **format specification** — it is always introduced by the : symbol (Line 11 above uses one.) This modifies how the substitutions are made into the template, and can control things like:

- whether the field is aligned to the left <, center ^, or right >
- the width allocated to the field within the result string (a number like 10)
- the type of conversion (we'll initially only force conversion to float, f, as we did in line 11 of the code above, or perhaps we'll ask integer numbers to be converted to hexadecimal using x)
- if the type conversion is a float, you can also specify how many decimal places are wanted (typically, .2f is useful for working with currencies to two decimal places.)

Let's do a few simple and common examples that should be enough for most needs. If you need to do anything more esoteric, use help and read all the powerful, gory details.

```
1 n1 = "Paris"
2 n2 = "Whitney"
3 n3 = "Hilton"
4
5 print("Pi to three decimal places is {0:.3f}".format(3.1415926))
6 print("123456789 123456789 123456789 123456789 123456789 123456789")
7 print("|||{0:<15}|||{1:^15}|||{2:>15}|||Born in {3}|||")
8     .format(n1,n2,n3,1981))
9 print("The decimal value {0} converts to hex value {0:x}"
10     .format(123456))
```

This script produces the output:

```
1 Pi to three decimal places is 3.142
2 123456789 123456789 123456789 123456789 123456789 123456789
3 |||Paris          |||   Whitney   |||           Hilton|||Born in 1981|||
4 The decimal value 123456 converts to hex value 1e240
```

You can have multiple placeholders indexing the same argument, or perhaps even have extra arguments that are not referenced at all:

```

1 letter = """
2 Dear {0} {2}.
3 {0}, I have an interesting money-making proposition for you!
4 If you deposit $10 million into my bank account, I can
5 double your money ...
6 """
7
8 print(letter.format("Paris", "Whitney", "Hilton"))
9 print(letter.format("Bill", "Henry", "Gates"))

```

This produces the following:

```

1 Dear Paris Hilton.
2 Paris, I have an interesting money-making proposition for you!
3 If you deposit $10 million into my bank account, I can
4 double your money ...
5
6
7 Dear Bill Gates.
8 Bill, I have an interesting money-making proposition for you!
9 If you deposit $10 million into my bank account I can
10 double your money ...

```

As you might expect, you'll get an index error if your placeholders refer to arguments that you do not provide:

```

1 >>> "hello {3}".format("Dave")
2 Traceback (most recent call last):
3   File "<interactive input>", line 1, in <module>
4   IndexError: tuple index out of range

```

The following example illustrates the real utility of string formatting. First, we'll try to print a table without using string formatting:

```

1 print("i\ti**2\ti**3\ti**5\ti**10\ti**20")
2 for i in range(1, 11):
3     print(i, "\t", i**2, "\t", i**3, "\t", i**5, "\t",
4           i**10, "\t", i**20)

```

This program prints out a table of various powers of the numbers from 1 to 10. (This assumes that the tab width is 8. You might see something even worse than this if you tab width is set to 4.) In its current form it relies on the tab character (\t) to align the columns of values, but this breaks down when the values in the table get larger than the tab width:


```

1  i      i**2    i**3    i**5    i**10   i**20
2  1      1      1      1      1      1
3  2      4      8      32     1024    1048576
4  3      9      27     243    59049   3486784401
5  4      16     64     1024   1048576    1099511627776
6  5      25     125    3125   9765625    95367431640625
7  6      36     216    7776   60466176   3656158440062976
8  7      49     343   16807  282475249  79792266297612001
9  8      64     512   32768  1073741824 1152921504606846976
10 9      81     729   59049  3486784401 12157665459056928801
11 10     100    1000  100000 10000000000 10000000000000000000

```

One possible solution would be to change the tab width, but the first column already has more space than it needs. The best solution would be to set the width of each column independently. As you may have guessed by now, string formatting provides a much nicer solution. We can also right-justify each field:

```

1  layout = "{0:>4}{1:>6}{2:>6}{3:>8}{4:>13}{5:>24}"
2
3  print(layout.format("i", "i**2", "i**3", "i**5", "i**10", "i**20"))
4  for i in range(1, 11):
5      print(layout.format(i, i**2, i**3, i**5, i**10, i**20))

```

Running this version produces the following (much more satisfying) output:

```

1  i      i**2    i**3    i**5    i**10   i**20
2  1      1      1      1      1      1
3  2      4      8      32     1024    1048576
4  3      9      27     243    59049   3486784401
5  4      16     64     1024   1048576    1099511627776
6  5      25     125    3125   9765625    95367431640625
7  6      36     216    7776   60466176   3656158440062976
8  7      49     343   16807  282475249  79792266297612001
9  8      64     512   32768  1073741824 1152921504606846976
10 9      81     729   59049  3486784401 12157665459056928801
11 10     100    1000  100000 10000000000 10000000000000000000

```

8.17. Summary

This chapter introduced a lot of new ideas. The following summary may prove helpful in remembering what you learned.

indexing ([])

Access a single character in a string using its position (starting from 0). Example: `"This"[2]` evaluates to `"i"`.

length function (len)

Returns the number of characters in a string. Example:
`len("happy")` evaluates to 5.

for loop traversal (for)

Traversing a string means accessing each character in the string, one at a time. For example, the following for loop:

```
1 for ch in "Example":
2     ...
```

executes the body of the loop 7 times with different values of `ch` each time.

slicing ([:])

A *slice* is a substring of a string. Example: `'bananas and cream'[3:6]` evaluates to `ana` (so does `'bananas and cream'[1:4]`).

string comparison (>, <, >=, <=, ==, !=)

The six common comparison operators work with strings, evaluating according to lexicographical order. Examples:

`"apple" < "banana"` evaluates to `True`. `"Zeta" < "Apricot"` evaluates to `False`. `"Zebra" <= "aardvark"` evaluates to `True` because all upper case letters precede lower case letters.

in and not in operator (in, not in)

The `in` operator tests for membership. In the case of strings, it tests whether one string is contained inside another string. Examples: `"heck" in "I'll be checking for you."` evaluates to `True`. `"cheese" in "I'll be checking for you."` evaluates to `False`.

8.18. Glossary

compound data type

A data type in which the values are made up of components, or elements, that are themselves values.

default value

The value given to an optional parameter if no argument for it is provided in the function call.

docstring

A string constant on the first line of a function or module definition (and as we will see later, in class and method definitions as well).

Docstrings provide a convenient way to associate documentation with code. Docstrings are also used by programming tools to provide interactive help.

dot notation

Use of the **dot operator**, `.`, to access methods and attributes of an object.

immutable data value

A data value which cannot be modified. Assignments to elements or slices (sub-parts) of immutable values cause a runtime error.

index

A variable or value used to select a member of an ordered collection, such as a character from a string, or an element from a list.

mutable data value

A data value which can be modified. The types of all mutable values are compound types. Lists and dictionaries are mutable; strings and tuples are not.

optional parameter

A parameter written in a function header with an assignment to a default value which it will receive if no corresponding argument is given for it in the function call.

short-circuit evaluation

A style of programming that shortcuts extra work as soon as the outcome is known with certainty. In this chapter our `find` function returned as soon as it found what it was looking for; it didn't traverse all the rest of the items in the string.

slice

A part of a string (substring) specified by a range of indices. More generally, a subsequence of any sequence type in Python can be created using the slice operator (`sequence[start:stop]`).

traverse

To iterate through the elements of a collection, performing a similar operation on each.

whitespace

Any of the characters that move the cursor without printing visible characters. The constant `string.whitespace` contains all the white-space characters.

8.19. Exercises

We suggest you create a single file containing the test scaffolding from our previous chapters, and put all functions that require tests into that file.

1. What is the result of each of the following:

```

1 >>> "Python"[1]
2 >>> "Strings are sequences of characters."[5]
3 >>> len("wonderful")
4 >>> "Mystery"[:4]
5 >>> "p" in "Pineapple"
6 >>> "apple" in "Pineapple"
7 >>> "pear" not in "Pineapple"
8 >>> "apple" > "pineapple"
9 >>> "pineapple" < "Peach"

```

2. Modify:

```

1 prefixes = "JKLMNOPQ"
2 suffix = "ack"
3
4 for letter in prefixes:
5     print(letter + suffix)

```

so that Ouack and Quack are spelled correctly.

3. Encapsulate

```

1 fruit = "banana"
2 count = 0
3 for char in fruit:
4     if char == "a":
5         count += 1
6 print(count)

```

in a function named `count_letters`, and generalize it so that it accepts the string and the letter as arguments. Make the function return the number of characters, rather than print the answer. The caller should do the printing.

4. Now rewrite the `count_letters` function so that instead of traversing the string, it repeatedly calls the `find` method, with the optional third parameter to locate new occurrences of the letter being counted.
5. Assign to a variable in your program a triple-quoted string that contains your favourite paragraph of text — perhaps a poem, a speech, instructions to bake a cake, some inspirational verses, etc.

Write a function which removes all punctuation from the string, breaks the string into a list of words, and counts the number of words in your text that contain the letter “e”. Your program should print an analysis of the text like this:

1 Your text contains 243 words, of which 109 (44.8%) contain an "e".

6. Print a neat looking multiplication table like this:

```

1          1  2  3  4  5  6  7  8  9 10 11 12
2      :-----
3      1:    1  2  3  4  5  6  7  8  9 10 11 12
4      2:    2  4  6  8 10 12 14 16 18 20 22 24
5      3:    3  6  9 12 15 18 21 24 27 30 33 36
6      4:    4  8 12 16 20 24 28 32 36 40 44 48
7      5:    5 10 15 20 25 30 35 40 45 50 55 60
8      6:    6 12 18 24 30 36 42 48 54 60 66 72
9      7:    7 14 21 28 35 42 49 56 63 70 77 84
10     8:    8 16 24 32 40 48 56 64 72 80 88 96
11     9:    9 18 27 36 45 54 63 72 81 90 99 108
12    10:   10 20 30 40 50 60 70 80 90 100 110 120
13    11:   11 22 33 44 55 66 77 88 99 110 121 132
14    12:   12 24 36 48 60 72 84 96 108 120 132 144

```

7. Write a function that reverses its string argument, and satisfies these tests:

```

1 test(reverse("happy") == "yppah")
2 test(reverse("Python") == "nohtyP")
3 test(reverse("") == "")
4 test(reverse("a") == "a")

```

8. Write a function that mirrors its argument:

```

1 test(mirror("good") == "gooddoog")
2 test(mirror("Python") == "PythonnohtyP")
3 test(mirror("") == "")
4 test(mirror("a") == "aa")

```

9. Write a function that removes all occurrences of a given letter from a string:

```
1 test(remove_letter("a", "apple") == "pple")
2 test(remove_letter("a", "banana") == "bnn")
3 test(remove_letter("z", "banana") == "banana")
4 test(remove_letter("i", "Mississippi") == "Msssspp")
5 test(remove_letter("b", "") == "")
6 test(remove_letter("b", "c") == "c")
```

10. Write a function that recognizes palindromes. (Hint: use your reverse function to make this easy!):

```
1 test(is_palindrome("abba"))
2 test(not is_palindrome("abab"))
3 test(is_palindrome("tenet"))
4 test(not is_palindrome("banana"))
5 test(is_palindrome("straw warts"))
6 test(is_palindrome("a"))
7 # test(is_palindrome(""))    # Is an empty string a palindrome?
```

11. Write a function that counts how many times a substring occurs in a string:

```
1 test(count("is", "Mississippi") == 2)
2 test(count("an", "banana") == 2)
3 test(count("ana", "banana") == 2)
4 test(count("nana", "banana") == 1)
5 test(count("nanan", "banana") == 0)
6 test(count("aaa", "aaaaaa") == 4)
```

12. Write a function that removes the first occurrence of a string from another string:

```
1 test(remove("an", "banana") == "bana")
2 test(remove("cyc", "bicycle") == "bile")
3 test(remove("iss", "Mississippi") == "Missippi")
4 test(remove("eggs", "bicycle") == "bicycle")
```

13. Write a function that removes all occurrences of a string from another string:

```
1 test(remove_all("an", "banana") == "ba")
2 test(remove_all("cyc", "bicycle") == "bile")
3 test(remove_all("iss", "Mississippi") == "Mippi")
4 test(remove_all("eggs", "bicycle") == "bicycle")
```

Chapter 9: Tuples

9.1. Tuples are used for grouping data

We saw earlier that we could group together pairs of values by surrounding with parentheses. Recall this example:

```
1 >>> year_born = ("Paris Hilton", 1981)
```

This is an example of a **data structure** - a mechanism for grouping and organizing data to make it easier to use.

The pair is an example of a **tuple**. Generalizing this, a tuple can be used to group any number of items into a single compound value. Syntactically, a tuple is a comma-separated sequence of values. Although it is not necessary, it is conventional to enclose tuples in parentheses:

```
1 >>> julia = ("Julia", "Roberts", 1967, "Duplicity", 2009, "Actress", "Atlanta, Georg\
2 ia")
```

Tuples are useful for representing what other languages often call *records* - some related information that belongs together, like your student record. There is no description of what each of these fields means, but we can guess. A tuple lets us “chunk” together related information and use it as a single thing.

Tuples support the same sequence operations as strings. The index operator selects an element from a tuple.

```
1 >>> julia[2]
2 1967
```

But if we try to use item assignment to modify one of the elements of the tuple, we get an error:

```
1 >>> julia[0] = "X"
2 TypeError: 'tuple' object does not support item assignment
```

So like strings, tuples are immutable. Once Python has created a tuple in memory, it cannot be changed.

Of course, even if we can't modify the elements of a tuple, we can always make the `julia` variable reference a new tuple holding different information. To construct the new tuple, it is convenient that we can slice parts of the old tuple and join up the bits to make the new tuple. So if `julia` has a new recent film, we could change her variable to reference a new tuple that used some information from the old one:


```
1 >>> julia = julia[:3] + ("Eat Pray Love", 2010) + julia[5:]
2 >>> julia
3 ("Julia", "Roberts", 1967, "Eat Pray Love", 2010, "Actress", "Atlanta, Georgia")
```

To create a tuple with a single element (but you're probably not likely to do that too often), we have to include the final comma, because without the final comma, Python treats the (5) below as an integer in parentheses:

```
1 >>> tup = (5,)
2 >>> type(tup)
3 <class 'tuple'>
4 >>> x = (5)
5 >>> type(x)
6 <class 'int'>
```

9.2. Tuple assignment

Python has a very powerful **tuple assignment** feature that allows a tuple of variables on the left of an assignment to be assigned values from a tuple on the right of the assignment. (We already saw this used for pairs, but it generalizes.)

```
1 (name, surname, b_year, movie, m_year, profession, b_place) = julia
```

This does the equivalent of seven assignment statements, all on one easy line. One requirement is that the number of variables on the left must match the number of elements in the tuple.

One way to think of tuple assignment is as tuple packing/unpacking.

In tuple packing, the values on the left are 'packed' together in a tuple:

```
1 >>> b = ("Bob", 19, "CS")      # tuple packing
```

In tuple unpacking, the values in a tuple on the right are 'unpacked' into the variables/names on the left:

```
1 >>> b = ("Bob", 19, "CS")
2 >>> (name, age, studies) = b      # tuple unpacking
3 >>> name
4 'Bob'
5 >>> age
6 19
7 >>> studies
8 'CS'
```

Once in a while, it is useful to swap the values of two variables. With conventional assignment statements, we have to use a temporary variable. For example, to swap *a* and *b*:

```
1 temp = a
2 a = b
3 b = temp
```

Tuple assignment solves this problem neatly:

```
1 (a, b) = (b, a)
```

The left side is a tuple of variables; the right side is a tuple of values. Each value is assigned to its respective variable. All the expressions on the right side are evaluated before any of the assignments. This feature makes tuple assignment quite versatile.

Naturally, the number of variables on the left and the number of values on the right have to be the same:

```
1 >>> (a, b, c, d) = (1, 2, 3)
2 ValueError: need more than 3 values to unpack
```

9.3. Tuples as return values

Functions can always only return a single value, but by making that value a tuple, we can effectively group together as many values as we like, and return them together. This is very useful - we often want to know some batsman's highest and lowest score, or we want to find the mean and the standard deviation, or we want to know the year, the month, and the day, or if we're doing some ecological modelling we may want to know the number of rabbits and the number of wolves on an island at a given time.

For example, we could write a function that returns both the area and the circumference of a circle of radius *r*:

```

1 def f(r):
2     """ Return (circumference, area) of a circle of radius r """
3     c = 2 * math.pi * r
4     a = math.pi * r * r
5     return (c, a)

```

9.4. Composability of Data Structures

We saw in an earlier chapter that we could make a list of pairs, and we had an example where one of the items in the tuple was itself a list:

```

1 students = [
2     ("John", ["CompSci", "Physics"]),
3     ("Vusi", ["Maths", "CompSci", "Stats"]),
4     ("Jess", ["CompSci", "Accounting", "Economics", "Management"]),
5     ("Sarah", ["InfSys", "Accounting", "Economics", "CommLaw"]),
6     ("Zuki", ["Sociology", "Economics", "Law", "Stats", "Music"])]

```

Tuples items can themselves be other tuples. For example, we could improve the information about our movie stars to hold the full date of birth rather than just the year, and we could have a list of some of her movies and dates that they were made, and so on:

```

1 julia_more_info = ( ("Julia", "Roberts"), (8, "October", 1967),
2                     "Actress", ("Atlanta", "Georgia"),
3                     [ ("Duplicity", 2009),
4                       ("Notting Hill", 1999),
5                       ("Pretty Woman", 1990),
6                       ("Erin Brockovich", 2000),
7                       ("Eat Pray Love", 2010),
8                       ("Mona Lisa Smile", 2003),
9                       ("Oceans Twelve", 2004) ])

```

Notice in this case that the tuple has just five elements - but each of those in turn can be another tuple, a list, a string, or any other kind of Python value. This property is known as being **heterogeneous**, meaning that it can be composed of elements of different types.

9.5. Glossary

data structure

An organization of data for the purpose of making it easier to use.

immutable data value

A data value which cannot be modified. Assignments to elements or slices (sub-parts) of immutable values cause a runtime error.

mutable data value

A data value which can be modified. The types of all mutable values are compound types. Lists and dictionaries are mutable; strings and tuples are not.

tuple

An immutable data value that contains related elements. Tuples are used to group together related data, such as a person's name, their age, and their gender.

tuple assignment

An assignment to all of the elements in a tuple using a single assignment statement. Tuple assignment occurs *simultaneously* rather than in sequence, making it useful for swapping values.

9.6. Exercises

1. We've said nothing in this chapter about whether you can pass tuples as arguments to a function. Construct a small Python example to test whether this is possible, and write up your findings.
2. Is a pair a generalization of a tuple, or is a tuple a generalization of a pair?
3. Is a pair a kind of tuple, or is a tuple a kind of pair?

Chapter 10: Event handling

10.1. Event-driven programming

Most programs and devices like a cellphone respond to *events* – things that happen. For example, you might move your mouse, and the computer responds. Or you click a button, and the program does something interesting. In this chapter we'll touch very briefly on how event-driven programming works.

10.2. Keypress events

Here's a program with some new features. Copy it into your workspace, run it. When the turtle window opens, press the arrow keys and make tess move about!

```
1  import turtle
2
3  turtle.setup(400,500)           # Determine the window size
4  wn = turtle.Screen()           # Get a reference to the window
5  wn.title("Handling keypresses!") # Change the window title
6  wn.bgcolor("lightgreen")        # Set the background color
7  tess = turtle.Turtle()         # Create our favorite turtle
8
9  # The next four functions are our "event handlers".
10 def h1():
11     tess.forward(30)
12
13 def h2():
14     tess.left(45)
15
16 def h3():
17     tess.right(45)
18
19 def h4():
20     wn.bye()                    # Close down the turtle window
21
22 # These lines "wire up" keypresses to the handlers we've defined.
23 wn.onkey(h1, "Up")
```

```

24 wn.onkey(h2, "Left")
25 wn.onkey(h3, "Right")
26 wn.onkey(h4, "q")
27
28 # Now we need to tell the window to start listening for events,
29 # If any of the keys that we're monitoring is pressed, its
30 # handler will be called.
31 wn.listen()
32 wn.mainloop()

```

Here are some points to note:

- We need the call to the window's `listen` method at line 31, otherwise it won't notice our keypresses.
- We named our handler functions `h1`, `h2` and so on, but we can choose better names. The handlers can be arbitrarily complex functions that call other functions, etc.
- Pressing the `q` key on the keyboard calls function `h4` (because we bound the `q` key to `h4` on line 26). While executing `h4`, the window's `bye` method (line 20) closes the turtle window, which causes the window's `mainloop` call (line 31) to end its execution. Since we did not write any more statements after line 32, this means that our program has completed everything, so it too will terminate.
- We can refer to keys on the keyboard by their character code (as we did in line 26), or by their symbolic names. Some of the symbolic names to try are `Cancel` (the Break key), `BackSpace`, `Tab`, `Return` (the Enter key), `Shift_L` (any Shift key), `Control_L` (any Control key), `Alt_L` (any Alt key), `Pause`, `Caps_Lock`, `Escape`, `Prior` (Page Up), `Next` (Page Down), `End`, `Home`, `Left`, `Up`, `Right`, `Down`, `Print`, `Insert`, `Delete`, `F1`, `F2`, `F3`, `F4`, `F5`, `F6`, `F7`, `F8`, `F9`, `F10`, `F11`, `F12`, `Num_Lock`, and `Scroll_Lock`.

10.3. Mouse events

A mouse event is a bit different from a keypress event because its handler needs two parameters to receive `x,y` coordinate information telling us where the mouse was when the event occurred.

```

1  import turtle
2
3  turtle.setup(400,500)
4  wn = turtle.Screen()
5  wn.title("How to handle mouse clicks on the window!")
6  wn.bgcolor("lightgreen")
7
8  tess = turtle.Turtle()
9  tess.color("purple")
10 tess.pensize(3)
11 tess.shape("circle")
12

```

```

13 def h1(x, y):
14     tess.goto(x, y)
15
16 wn.onclick(h1) # Wire up a click on the window.
17 wn.mainloop()

```

There is a new turtle method used at line 14 – this allows us to move the turtle to an *absolute* coordinate position. (Most of the examples that we’ve seen so far move the turtle *relative* to where it currently is). So what this program does is move the turtle (and draw a line) to wherever the mouse is clicked. Try it out!

If we add this line before line 14, we’ll learn a useful debugging trick too:

```

1 wn.title("Got click at coords {0}, {1}".format(x, y))

```

Because we can easily change the text in the window’s title bar, it is a useful place to display occasional debugging or status information. (Of course, this is not the real purpose of the window title!)

But there is more!

Not only can the window receive mouse events: individual turtles can also have their own handlers for mouse clicks. The turtle that “receives” the click event will be the one under the mouse. So we’ll create two turtles. Each will bind a handler to its own `onclick` event. And the two handlers can do different things for their turtles.

```

1 import turtle
2
3 turtle.setup(400,500)           # Determine the window size
4 wn = turtle.Screen()           # Get a reference to the window
5 wn.title("Handling mouse clicks!") # Change the window title
6 wn.bgcolor("lightgreen")       # Set the background color
7 tess = turtle.Turtle()         # Create two turtles
8 tess.color("purple")
9 alex = turtle.Turtle()         # Move them apart
10 alex.color("blue")
11 alex.forward(100)
12
13 def handler_for_tess(x, y):
14     wn.title("Tess clicked at {0}, {1}".format(x, y))
15     tess.left(42)
16     tess.forward(30)
17
18 def handler_for_alex(x, y):

```

```
19     wn.title("Alex clicked at {0}, {1}".format(x, y))
20     alex.right(84)
21     alex.forward(50)
22
23 tess.onclick(handler_for_tess)
24 alex.onclick(handler_for_alex)
25
26 wn.mainloop()
```

Run this, click on the turtles, see what happens!

10.4. Automatic events from a timer

Alarm clocks, kitchen timers, and thermonuclear bombs in James Bond movies are set to create an “automatic” event after a certain interval. The turtle module in Python has a timer that can cause an event when its time is up.

```
1  import turtle
2
3  turtle.setup(400,500)
4  wn = turtle.Screen()
5  wn.title("Using a timer")
6  wn.bgcolor("lightgreen")
7
8  tess = turtle.Turtle()
9  tess.color("purple")
10 tess.pensize(3)
11
12 def h1():
13     tess.forward(100)
14     tess.left(56)
15
16 wn.ontimer(h1, 2000)
17 wn.mainloop()
```

On line 16 the timer is started and set to explode in 2000 milliseconds (2 seconds). When the event does occur, the handler is called, and tess springs into action.

Unfortunately, when one sets a timer, it only goes off once. So a common idiom, or style, is to restart the timer inside the handler. In this way the timer will keep on giving new events. Try this program:



```
1  import turtle
2
3  turtle.setup(400,500)
4  wn = turtle.Screen()
5  wn.title("Using a timer to get events!")
6  wn.bgcolor("lightgreen")
7
8  tess = turtle.Turtle()
9  tess.color("purple")
10
11 def h1():
12     tess.forward(100)
13     tess.left(56)
14     wn.ontimer(h1, 60)
15
16 h1()
17 wn.mainloop()
```

10.5. An example: state machines

A state machine is a system that can be in one of a few different states. We draw a state diagram to represent the machine, where each state is drawn as a circle or an ellipse. Certain events occur which cause the system to leave one state and transition into a different state. These state transitions are usually drawn as an arrow on the diagram.

This idea is not new: when first turning on a cellphone, it goes into a state which we could call “Awaiting PIN”. When the correct PIN is entered, it transitions into a different state – say “Ready”. Then we could lock the phone, and it would enter a “Locked” state, and so on.

A simple state machine that we encounter often is a traffic light. Here is a state diagram which shows that the machine continually cycles through three different states, which we’ve numbered 0, 1 and 2.



We're going to build a program that uses a turtle to simulate the traffic lights. There are three lessons here. The first shows off some different ways to use our turtles. The second demonstrates how we would program a state machine in Python, by using a variable to keep track of the current state, and a number of different `if` statements to inspect the current state, and take the actions as we change to a different state. The third lesson is to use events from the keyboard to trigger the state changes.

Copy and run this program. Make sure you understand what each line does, consulting the documentation as you need to.

```

1  import turtle                # Tess becomes a traffic light.
2
3  turtle.setup(400,500)
4  wn = turtle.Screen()
5  wn.title("Tess becomes a traffic light!")
6  wn.bgcolor("lightgreen")
7  tess = turtle.Turtle()
8
9
10 def draw_housing():
11     """ Draw a nice housing to hold the traffic lights """
12     tess.pensize(3)
13     tess.color("black", "darkgrey")
14     tess.begin_fill()
```

```
15     tess.forward(80)
16     tess.left(90)
17     tess.forward(200)
18     tess.circle(40, 180)
19     tess.forward(200)
20     tess.left(90)
21     tess.end_fill()
22
23
24 draw_housing()
25
26 tess.penup()
27 # Position tess onto the place where the green light should be
28 tess.forward(40)
29 tess.left(90)
30 tess.forward(50)
31 # Turn tess into a big green circle
32 tess.shape("circle")
33 tess.shapesize(3)
34 tess.fillcolor("green")
35
36 # A traffic light is a kind of state machine with three states,
37 # Green, Orange, Red. We number these states 0, 1, 2
38 # When the machine changes state, we change tess' position and
39 # her fillcolor.
40
41 # This variable holds the current state of the machine
42 state_num = 0
43
44
45 def advance_state_machine():
46     global state_num
47     if state_num == 0:          # Transition from state 0 to state 1
48         tess.forward(70)
49         tess.fillcolor("orange")
50         state_num = 1
51     elif state_num == 1:       # Transition from state 1 to state 2
52         tess.forward(70)
53         tess.fillcolor("red")
54         state_num = 2
55     else:                      # Transition from state 2 to state 0
56         tess.back(140)
57         tess.fillcolor("green")
```

```

58         state_num = 0
59
60     # Bind the event handler to the space key.
61     wn.onkey(advance_state_machine, "space")
62
63     wn.listen()                # Listen for events
64     wn.mainloop()

```

The new Python statement is at line 46. The `global` keyword tells Python not to create a new local variable for `state_num` (in spite of the fact that the function assigns to this variable at lines 50, 54, and 58). Instead, in this function, `state_num` always refers to the variable that was created at line 42.

What the code in `advance_state_machine` does is advance from whatever the current state is, to the next state. On the state change we move tess to her new position, change her color, and, of course, we assign to `state_num` the number of the new state we've just entered.

Each time the space bar is pressed, the event handler causes the traffic light machine to move to its new state.

10.6. Glossary

bind

We bind a function (or associate it) with an event, meaning that when the event occurs, the function is called to handle it.

event

Something that happens “outside” the normal control flow of our program, usually from some user action. Typical events are mouse operations and keypresses. We’ve also seen that a timer can be primed to create an event.

handler


A function that is called in response to an event.

10.7. Exercises

1. Add some new key bindings to the first sample program:

- Pressing keys R, G or B should change tess’s color to Red, Green or Blue.
- Pressing keys + or - should increase or decrease the width of tess’s pen. Ensure that the pen size stays between 1 and 20 (inclusive).
- Handle some other keys to change some attributes of tess, or attributes of the window, or to give her new behaviour that can be controlled from the keyboard.

2. Change the traffic light program so that changes occur automatically, driven by a timer.
3. In an earlier chapter we saw two turtle methods, `hideturtle` and `showturtle` that can hide or show a turtle. This suggests that we could take a different approach to the traffic lights program. Add to your program above as follows: draw a second housing for another set of traffic lights. Create three separate turtles to represent each of the green, orange and red lights, and position them appropriately within your new housing. As your state changes occur, just make one of the three turtles visible at any time. Once you've made the changes, sit back and ponder some deep thoughts: you've now got two different ways to use turtles to simulate the traffic lights, and both seem to work. Is one approach somehow preferable to the other? Which one more closely resembles reality – i.e. the traffic lights in your town?
4. Now that you've got a traffic light program with different turtles for each light, perhaps the visibility / invisibility trick wasn't such a great idea. If we watch traffic lights, they turn on and off – but when they're off they are still there, perhaps just a darker color. Modify the program now so that the lights don't disappear: they are either on, or off. But when they're off, they're still visible.
5. Your traffic light controller program has been patented, and you're about to become seriously rich. But your new client needs a change. They want four states in their state machine: Green, then Green and Orange together, then Orange only, and then Red. Additionally, they want different times spent in each state. The machine should spend 3 seconds in the Green state, followed by one second in the Green+Orange state, then one second in the Orange state, and then 2 seconds in the Red state. Change the logic in the state machine.
6. If you don't know how tennis scoring works, ask a friend or consult Wikipedia. A single game in tennis between player A and player B always has a score. We want to think about the “state of the score” as a state machine. The game starts in state (0, 0), meaning neither player has any score yet. We'll assume the first element in this pair is the score for player A. If player A wins the first point, the score becomes (15, 0). If B wins the first point, the state becomes (0, 15). Below are the first few states and transitions for a state diagram. In this diagram, each state has two possible outcomes (A wins the next point, or B does), and the uppermost arrow is always the transition that happens when A wins the point. Complete the diagram, showing all transitions and all states. (Hint: there are twenty states, if you include the duece state, the advantage states, and the “A wins” and “B wins” states in your diagram.)



Chapter 11: Lists

A **list** is an ordered collection of values. The values that make up a list are called its **elements**, or its **items**. We will use the term element or item to mean the same thing. Lists are similar to strings, which are ordered collections of characters, except that the elements of a list can be of any type. Lists and strings — and other collections that maintain the order of their items — are called **sequences**.

11.1. List values

There are several ways to create a new list; the simplest is to enclose the elements in square brackets ([and]):

```
1 ps = [10, 20, 30, 40]
2 qs = ["spam", "bungee", "swallow"]
```

The first example is a list of four integers. The second is a list of three strings. The elements of a list don't have to be the same type. The following list contains a string, a float, an integer, and (amazingly) another list:

```
1 zs = ["hello", 2.0, 5, [10, 20]]
```

A list within another list is said to be **nested**.

Finally, a list with no elements is called an empty list, and is denoted [].

We have already seen that we can assign list values to variables or pass lists as parameters to functions:

```
1 >>> vocabulary = ["apple", "cheese", "dog"]
2 >>> numbers = [17, 123]
3 >>> an_empty_list = []
4 >>> print(vocabulary, numbers, an_empty_list)
5 ["apple", "cheese", "dog"] [17, 123] []
```

11.2. Accessing elements

The syntax for accessing the elements of a list is the same as the syntax for accessing the characters of a string — the index operator: [] (not to be confused with an empty list). The expression inside the brackets specifies the index. Remember that the indices start at 0:

```

1 >>> numbers[0]
2 17

```

Any expression evaluating to an integer can be used as an index:

```

1 >>> numbers[9-8]
2 5
3 >>> numbers[1.0]
4 Traceback (most recent call last):
5   File "<interactive input>", line 1, in <module>
6   TypeError: list indices must be integers, not float

```

If you try to access or assign to an element that does not exist, you get a runtime error:

```

1 >>> numbers[2]
2 Traceback (most recent call last):
3   File "<interactive input>", line 1, in <module>
4   IndexError: list index out of range

```

It is common to use a loop variable as a list index.

```

1 horsemen = ["war", "famine", "pestilence", "death"]
2
3 for i in [0, 1, 2, 3]:
4     print(horsemen[i])

```

Each time through the loop, the variable `i` is used as an index into the list, printing the `i`'th element. This pattern of computation is called a **list traversal**.

The above sample doesn't need or use the index `i` for anything besides getting the items from the list, so this more direct version — where the `for` loop gets the items — might be preferred:

```

1 horsemen = ["war", "famine", "pestilence", "death"]
2
3 for h in horsemen:
4     print(h)

```

11.3. List length

The function `len` returns the length of a list, which is equal to the number of its elements. If you are going to use an integer index to access the list, it is a good idea to use this value as the upper bound of a loop instead of a constant. That way, if the size of the list changes, you won't have to go through the program changing all the loops; they will work correctly for any size list:


```

1 horsemen = ["war", "famine", "pestilence", "death"]
2
3 for i in range(len(horsemen)):
4     print(horsemen[i])

```

The last time the body of the loop is executed, `i` is `len(horsemen) - 1`, which is the index of the last element. (But the version without the index looks even better now!)

Although a list can contain another list, the nested list still counts as a single element in its parent list. The length of this list is 4:

```

1 >>> len(["car makers", 1, ["Ford", "Toyota", "BMW"], [1, 2, 3]])
2 4

```

11.4. List membership

`in` and `not in` are Boolean operators that test membership in a sequence. We used them previously with strings, but they also work with lists and other sequences:

```

1 >>> horsemen = ["war", "famine", "pestilence", "death"]
2 >>> "pestilence" in horsemen
3 True
4 >>> "debauchery" in horsemen
5 False
6 >>> "debauchery" not in horsemen
7 True

```

Using this produces a more elegant version of the nested loop program we previously used to count the number of students doing Computer Science in the section `nested_data`:

```

1 students = [
2     ("John", ["CompSci", "Physics"]),
3     ("Vusi", ["Maths", "CompSci", "Stats"]),
4     ("Jess", ["CompSci", "Accounting", "Economics", "Management"]),
5     ("Sarah", ["InfSys", "Accounting", "Economics", "CommLaw"]),
6     ("Zuki", ["Sociology", "Economics", "Law", "Stats", "Music"])
7
8     # Count how many students are taking CompSci
9     counter = 0
10    for (name, subjects) in students:
11        if "CompSci" in subjects:
12            counter += 1
13
14    print("The number of students taking CompSci is", counter)

```

11.5. List operations

The + operator concatenates lists:

```
1 >>> a = [1, 2, 3]
2 >>> b = [4, 5, 6]
3 >>> c = a + b
4 >>> c
5 [1, 2, 3, 4, 5, 6]
```

Similarly, the * operator repeats a list a given number of times:

```
1 >>> [0] * 4
2 [0, 0, 0, 0]
3 >>> [1, 2, 3] * 3
4 [1, 2, 3, 1, 2, 3, 1, 2, 3]
```

The first example repeats [0] four times. The second example repeats the list [1, 2, 3] three times.

11.6. List slices

The slice operations we saw previously with strings let us work with sublists:

```
1 >>> a_list = ["a", "b", "c", "d", "e", "f"]
2 >>> a_list[1:3]
3 ['b', 'c']
4 >>> a_list[:4]
5 ['a', 'b', 'c', 'd']
6 >>> a_list[3:]
7 ['d', 'e', 'f']
8 >>> a_list[:]
9 ['a', 'b', 'c', 'd', 'e', 'f']
```

11.7. Lists are mutable

Unlike strings, lists are **mutable**, which means we can change their elements. Using the index operator on the left side of an assignment, we can update one of the elements:

```
1 >>> fruit = ["banana", "apple", "quince"]
2 >>> fruit[0] = "pear"
3 >>> fruit[2] = "orange"
4 >>> fruit
5 ['pear', 'apple', 'orange']
```

The bracket operator applied to a list can appear anywhere in an expression. When it appears on the left side of an assignment, it changes one of the elements in the list, so the first element of `fruit` has been changed from "banana" to "pear", and the last from "quince" to "orange". An assignment to an element of a list is called **item assignment**. Item assignment does not work for strings:

```
1 >>> my_string = "TEST"
2 >>> my_string[2] = "X"
3 Traceback (most recent call last):
4   File "<interactive input>", line 1, in <module>
5   TypeError: 'str' object does not support item assignment
```

but it does for lists:

```
1 >>> my_list = ["T", "E", "S", "T"]
2 >>> my_list[2] = "X"
3 >>> my_list
4 ['T', 'E', 'X', 'T']
```

With the slice operator we can update a whole sublist at once:

```
1 >>> a_list = ["a", "b", "c", "d", "e", "f"]
2 >>> a_list[1:3] = ["x", "y"]
3 >>> a_list
4 ['a', 'x', 'y', 'd', 'e', 'f']
```

We can also remove elements from a list by assigning an empty list to them:

```
1 >>> a_list = ["a", "b", "c", "d", "e", "f"]
2 >>> a_list[1:3] = []
3 >>> a_list
4 ['a', 'd', 'e', 'f']
```

And we can add elements to a list by squeezing them into an empty slice at the desired location:

```
1 >>> a_list = ["a", "d", "f"]
2 >>> a_list[1:1] = ["b", "c"]
3 >>> a_list
4 ['a', 'b', 'c', 'd', 'f']
5 >>> a_list[4:4] = ["e"]
6 >>> a_list
7 ['a', 'b', 'c', 'd', 'e', 'f']
```

11.8. List deletion

Using slices to delete list elements can be error-prone. Python provides an alternative that is more readable. The `del` statement removes an element from a list:

```
1 >>> a = ["one", "two", "three"]
2 >>> del a[1]
3 >>> a
4 ['one', 'three']
```

As you might expect, `del` causes a runtime error if the index is out of range.

You can also use `del` with a slice to delete a sublist:

```
1 >>> a_list = ["a", "b", "c", "d", "e", "f"]
2 >>> del a_list[1:5]
3 >>> a_list
4 ['a', 'f']
```

As usual, the sublist selected by slice contains all the elements up to, but not including, the second index.

11.9. Objects and references

After we execute these assignment statements

```
1 a = "banana"
2 b = "banana"
```

we know that `a` and `b` will refer to a string object with the letters "banana". But we don't know yet whether they point to the *same* string object.

There are two possible ways the Python interpreter could arrange its memory:



In one case, `a` and `b` refer to two different objects that have the same value. In the second case, they refer to the same object.

We can test whether two names refer to the same object using the `is` operator:

```
1 >>> a is b
2 True
```


This tells us that both `a` and `b` refer to the same object, and that it is the second of the two state snapshots that accurately describes the relationship.

Since strings are *immutable*, Python optimizes resources by making two names that refer to the same string value refer to the same object.

This is not the case with lists:

```
1 >>> a = [1, 2, 3]
2 >>> b = [1, 2, 3]
3 >>> a == b
4 True
5 >>> a is b
6 False
```

The state snapshot here looks like this:




`a` and `b` have the same value but do not refer to the same object.

11.10. Aliasing

Since variables refer to objects, if we assign one variable to another, both variables refer to the same object:

```
1 >>> a = [1, 2, 3]
2 >>> b = a
3 >>> a is b
4 True
```

In this case, the state snapshot looks like this:



Because the same list has two different names, `a` and `b`, we say that it is **aliased**. Changes made with one alias affect the other:

```
1 >>> b[0] = 5
2 >>> a
3 [5, 2, 3]
```

Although this behavior can be useful, it is sometimes unexpected or undesirable. In general, it is safer to avoid aliasing when you are working with mutable objects (i.e. lists at this point in our textbook, but we'll meet more mutable objects as we cover classes and objects, dictionaries and sets). Of course, for immutable objects (i.e. strings, tuples), there's no problem — it is just not possible to change something and get a surprise when you access an alias name. That's why Python is free to alias strings (and any other immutable kinds of data) when it sees an opportunity to economize.


11.11. Cloning lists

If we want to modify a list and also keep a copy of the original, we need to be able to make a copy of the list itself, not just the reference. This process is sometimes called **cloning**, to avoid the ambiguity of the word copy.

The easiest way to clone a list is to use the slice operator:

```
1 >>> a = [1, 2, 3]
2 >>> b = a[:]
3 >>> b
4 [1, 2, 3]
```

Taking any slice of `a` creates a new list. In this case the slice happens to consist of the whole list. So now the relationship is like this:



Now we are free to make changes to `b` without worrying that we'll inadvertently be changing `a`:

```
1 >>> b[0] = 5
2 >>> a
3 [1, 2, 3]
```

11.12. Lists and `for` loops

The `for` loop also works with lists, as we've already seen. The generalized syntax of a `for` loop is:

```
1 for VARIABLE in LIST:
2     BODY
```

So, as we've seen

```
1 friends = ["Joe", "Zoe", "Brad", "Angelina", "Zuki", "Thandi", "Paris"]
2 for friend in friends:
3     print(friend)
```

It almost reads like English: For (every) friend in (the list of) friends, print (the name of the) friend.

Any list expression can be used in a `for` loop:

```
1 for number in range(20):
2     if number % 3 == 0:
3         print(number)
4
5 for fruit in ["banana", "apple", "quince"]:
6     print("I like to eat " + fruit + "s!")
```

The first example prints all the multiples of 3 between 0 and 19. The second example expresses enthusiasm for various fruits.

Since lists are mutable, we often want to traverse a list, changing each of its elements. The following squares all the numbers in the list `xs`:

```

1 xs = [1, 2, 3, 4, 5]
2
3 for i in range(len(xs)):
4     xs[i] = xs[i]**2

```

Take a moment to think about `range(len(xs))` until you understand how it works.

In this example we are interested in both the *value* of an item, (we want to square that value), and its *index* (so that we can assign the new value to that position). This pattern is common enough that Python

provides a nicer way to implement it:

```

1 xs = [1, 2, 3, 4, 5]
2
3 for (i, val) in enumerate(xs):
4     xs[i] = val**2

```

`enumerate` generates pairs of both (index, value) during the list traversal. Try this next example to see more clearly how `enumerate` works:

```

1 for (i, v) in enumerate(["banana", "apple", "pear", "lemon"]):
2     print(i, v)

```

```

1 0 banana
2 1 apple
3 2 pear
4 3 lemon

```

11.13. List parameters

Passing a list as an argument actually passes a reference to the list, not a copy or clone of the list. So parameter passing creates an alias for you: the caller has one variable referencing the list, and the called function has an alias, but there is only one underlying list object. For example, the function below takes a list as an argument and multiplies each element in the list by 2:

```

1 def double_stuff(a_list):
2     """ Overwrite each element in a_list with double its value. """
3     for (idx, val) in enumerate(a_list):
4         a_list[idx] = 2 * val

```


If we add the following onto our script:


```
1 things = [2, 5, 9]
2 double_stuff(things)
3 print(things)
```

When we run it we'll get:

```
1 [4, 10, 18]
```

In the function above, the parameter `a_list` and the variable `things` are aliases for the same object. So before any changes to the elements in the list, the state snapshot looks like this:



Since the list object is shared by two frames, we drew it between them.

If a function modifies the items of a list parameter, the caller sees the change.

Use the Python visualizer!

We've already mentioned the Python visualizer at <http://pythontutor.com>. It is a very useful tool for building a good understanding of references, aliases, assignments, and passing arguments to functions. Pay special attention to cases where you clone a list or have two separate lists, and cases where there is only one underlying list, but more than one variable is aliased to reference the list.

11.14. List methods

The dot operator can also be used to access built-in methods of list objects. We'll start with the most useful method for adding something onto the end of an existing list:

```
1 >>> mylist = []
2 >>> mylist.append(5)
3 >>> mylist.append(27)
4 >>> mylist.append(3)
5 >>> mylist.append(12)
6 >>> mylist
7 [5, 27, 3, 12]
```

`append` is a list method which adds the argument passed to it to the end of the list. We'll use it heavily when we're creating new lists. Continuing with this example, we show several other list methods:

```
1 >>> mylist.insert(1, 12)  # Insert 12 at pos 1, shift other items up
2 >>> mylist
3 [5, 12, 27, 3, 12]
4 >>> mylist.count(12)      # How many times is 12 in mylist?
5 2
6 >>> mylist.extend([5, 9, 5, 11])  # Put whole list onto end of mylist
7 >>> mylist
8 [5, 12, 27, 3, 12, 5, 9, 5, 11]
9 >>> mylist.index(9)        # Find index of first 9 in mylist
10 6
11 >>> mylist.reverse()
12 >>> mylist
13 [11, 5, 9, 5, 12, 3, 27, 12, 5]
14 >>> mylist.sort()
15 >>> mylist
16 [3, 5, 5, 5, 9, 11, 12, 12, 27]
17 >>> mylist.remove(12)      # Remove the first 12 in the list
18 >>> mylist
19 [3, 5, 5, 5, 9, 11, 12, 27]
```

Experiment and play with the list methods shown here, and read their documentation until you feel confident that you understand how they work.

11.15. Pure functions and modifiers

Functions which take lists as arguments and change them during execution are called **modifiers** and the changes they make are called **side effects**.

A **pure function** does not produce side effects. It communicates with the calling program only through parameters, which it does not modify, and a return value. Here is `double_stuff` written as a pure function:

```

1  def double_stuff(a_list):
2      """ Return a new list which contains
3          doubles of the elements in a_list.
4      """
5      new_list = []
6      for value in a_list:
7          new_elem = 2 * value
8          new_list.append(new_elem)
9
10     return new_list

```

This version of `double_stuff` does not change its arguments:

```

1  >>> things = [2, 5, 9]
2  >>> xs = double_stuff(things)
3  >>> things
4  [2, 5, 9]
5  >>> xs
6  [4, 10, 18]

```

An early rule we saw for assignment said “first evaluate the right hand side, then assign the resulting value to the variable”. So it is quite safe to assign the function result to the same variable that was passed to the function:

```

1  >>> things = [2, 5, 9]
2  >>> things = double_stuff(things)
3  >>> things
4  [4, 10, 18]

```

Which style is better?

Anything that can be done with modifiers can also be done with pure functions. In fact, some programming languages only allow pure functions. There is some evidence that programs that use pure functions are faster to develop and less error-prone than programs that use modifiers. Nevertheless, modifiers are convenient at times, and in some cases, functional programs are less efficient.

In general, we recommend that you write pure functions whenever it is reasonable to do so and resort to modifiers only if there is a compelling advantage. This approach might be called a *functional programming style*.

11.16. Functions that produce lists

The pure version of `double_stuff` above made use of an important **pattern** for your toolbox. Whenever you need to write a function that creates and returns a list, the pattern is usually:

```

1 initialize a result variable to be an empty list
2 loop
3     create a new element
4     append it to result
5 return the result

```

Let us show another use of this pattern. Assume you already have a function `is_prime(x)` that can test if `x` is prime. Write a function to return a list of all prime numbers less than `n`:

```

1 def primes_less_than(n):
2     """ Return a list of all prime numbers less than n. """
3     result = []
4     for i in range(2, n):
5         if is_prime(i):
6             result.append(i)
7     return result

```

11.17. Strings and lists

Two of the most useful methods on strings involve conversion to and from lists of substrings. The `split` method (which we've already seen) breaks a string into a list of words. By default, any number of whitespace characters is considered a word boundary:

```

1 >>> song = "The rain in Spain..."
2 >>> wds = song.split()
3 >>> wds
4 ['The', 'rain', 'in', 'Spain...']

```

An optional argument called a **delimiter** can be used to specify which string to use as the boundary marker between substrings. The following example uses the string `ai` as the delimiter:

```

1 >>> song.split("ai")
2 ['The r', 'n in Sp', 'n...']

```

Notice that the delimiter doesn't appear in the result.

The inverse of the `split` method is `join`. You choose a desired **separator** string, (often called the *glue*) and join the list with the glue between each of the elements:

```

1 >>> glue = ";"
2 >>> s = glue.join(wds)
3 >>> s
4 'The;rain;in;Spain...'

```

The list that you glue together (`wds` in this example) is not modified. Also, as these next examples show, you can use empty glue or multi-character strings as glue:

```

1 >>> " --- ".join(wds)
2 'The --- rain --- in --- Spain...'
3 >>> "".join(wds)
4 'TheraininSpain...'

```

11.18. list and range

Python has a built-in type conversion function called `list` that tries to turn whatever you give it into a list.

```

1 >>> xs = list("Crunchy Frog")
2 >>> xs
3 ['C', 'r', 'u', 'n', 'c', 'h', 'y', ' ', 'F', 'r', 'o', 'g']
4 >>> "".join(xs)
5 'Crunchy Frog'

```

One particular feature of `range` is that it doesn't instantly compute all its values: it “puts off” the computation, and does it on demand, or “lazily”. We'll say that it gives a **promise** to produce the values

when they are needed. This is very convenient if your computation short-circuits a search and returns early, as in this case:

```

1 def f(n):
2     """ Find the first positive integer between 101 and less
3     than n that is divisible by 21
4     """
5     for i in range(101, n):
6         if (i % 21 == 0):
7             return i
8
9
10 test(f(110) == 105)
11 test(f(1000000000) == 105)

```

In the second test, if `range` were to eagerly go about building a list with all those elements, you would soon exhaust your computer's available memory and crash the program. But it is cleverer than that! This computation works just fine, because the `range` object is just a promise to produce the elements if and when they are needed. Once the condition in the `if` becomes true, no further elements are generated, and the function returns. (Note: Before Python 3, `range` was not lazy. If you use an earlier versions of Python, YMMV!)

YMMV: Your Mileage May Vary

The acronym YMMV stands for *your mileage may vary*. American car advertisements often quoted fuel consumption figures for cars, e.g. that they would get 28 miles per gallon. But this always had to be accompanied by legal small-print warning the reader that they might not get the same. The term YMMV is now used idiomatically to mean “your results may differ”, e.g. *The battery life on this phone is 3 days, but YMMV*.

You'll sometimes find the lazy `range` wrapped in a call to `list`. This forces Python to turn the lazy promise into an actual list:

```
1 >>> range(10)           # Create a lazy promise
2 range(0, 10)
3 >>> list(range(10))      # Call in the promise, to produce a list.
4 [0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
```

11.19. Nested lists

A nested list is a list that appears as an element in another list. In this list, the element with index 3 is a nested list:

```
1 >>> nested = ["hello", 2.0, 5, [10, 20]]
```

If we output the element at index 3, we get:

```
1 >>> print(nested[3])
2 [10, 20]
```

To extract an element from the nested list, we can proceed in two steps:

```
1 >>> elem = nested[3]
2 >>> elem[0]
3 10
```

Or we can combine them:

```
1 >>> nested[3][1]
2 20
```

Bracket operators evaluate from left to right, so this expression gets the 3'th element of `nested` and extracts the 1'th element from it.

11.20. Matrices

Nested lists are often used to represent matrices. For example, the matrix:

$$\begin{bmatrix} 1 & 2 & 3 \\ 4 & 5 & 6 \\ 7 & 8 & 9 \end{bmatrix}$$

might be represented as:

```
1 >>> mx = [[1, 2, 3], [4, 5, 6], [7, 8, 9]]
```

`mx` is a list with three elements, where each element is a row of the matrix. We can select an entire row from the matrix in the usual way:

```
1 >>> mx[1]
2 [4, 5, 6]
```

Or we can extract a single element from the matrix using the double-index form:

```
1 >>> mx[1][2]
2 6
```

The first index selects the row, and the second index selects the column. Although this way of representing matrices is common, it is not the only possibility. A small variation is to use a list of columns instead of a list of rows. Later we will see a more radical alternative using a dictionary.

11.21. Glossary

aliases

Multiple variables that contain references to the same object.

clone

To create a new object that has the same value as an existing object.

Copying a reference to an object creates an alias but doesn't clone the object.

delimiter

A character or string used to indicate where a string should be split.

element

One of the values in a list (or other sequence). The bracket operator selects elements of a list. Also called *item*.

immutable data value

A data value which cannot be modified. Assignments to elements or slices (sub-parts) of immutable values cause a runtime error.

index

An integer value that indicates the position of an item in a list. Indexes start from 0.

item

See *element*.

list

A collection of values, each in a fixed position within the list. Like other types `str`, `int`, `float`, etc. there is also a `list` type-converter function that tries to turn whatever argument you give it into a list.

list traversal

The sequential accessing of each element in a list.

modifier

A function which changes its arguments inside the function body. Only mutable types can be changed by modifiers.

mutable data value

A data value which can be modified. The types of all mutable values are compound types. Lists and dictionaries are mutable; strings and tuples are not.

nested list

A list that is an element of another list.

object

A thing to which a variable can refer.

pattern

A sequence of statements, or a style of coding something that has general applicability in a number of different situations. Part of becoming a mature Computer Scientist is to learn and establish the

patterns and algorithms that form your toolkit. Patterns often correspond to your “mental chunking”.

promise

An object that promises to do some work or deliver some values if they’re eventually needed, but it lazily puts off doing the work immediately. Calling `range` produces a promise.

pure function

A function which has no side effects. Pure functions only make changes to the calling program through their return values.

sequence

Any of the data types that consist of an ordered collection of elements, with each element identified by an index.

side effect

A change in the state of a program made by calling a function. Side effects can only be produced by modifiers.

step size

The interval between successive elements of a linear sequence. The third (and optional argument) to the `range` function is called the step size. If not specified, it defaults to 1.

11.22. Exercises

1. What is the Python interpreter’s response to the following?

```
1 >>> list(range(10, 0, -2))
```

The three arguments to the `range` function are *start*, *stop*, and *step*, respectively. In this example, *start* is greater than *stop*. What happens if *start* < *stop* and *step* < 0? Write a rule for the relationships among *start*, *stop*, and *step*.

2. Consider this fragment of code:

```
1 import turtle
2
3 tess = turtle.Turtle()
4 alex = tess
5 alex.color("hotpink")
```

Does this fragment create one or two turtle instances? Does setting the color of alex also change the color of tess? Explain in detail.

3. Draw a state snapshot for a and b before and after the third line of the following Python code is executed:

```
1 a = [1, 2, 3]
2 b = a[:]
3 b[0] = 5
```

4. What will be the output of the following program?

```
1 this = ["I", "am", "not", "a", "crook"]
2 that = ["I", "am", "not", "a", "crook"]
3 print("Test 1: {0}".format(this is that))
4 that = this
5 print("Test 2: {0}".format(this is that))
```

Provide a *detailed* explanation of the results.

5. Lists can be used to represent mathematical *vectors*. In this exercise and several that follow you will

write functions to perform standard operations on vectors. Create a script named `vectors.py` and write Python code to pass the tests in each case.

Write a function `add_vectors(u, v)` that takes two lists of numbers of the same length, and returns a new list containing the sums of the corresponding elements of each:

```
1 test(add_vectors([1, 1], [1, 1]) == [2, 2])
2 test(add_vectors([1, 2], [1, 4]) == [2, 6])
3 test(add_vectors([1, 2, 1], [1, 4, 3]) == [2, 6, 4])
```

6. Write a function `scalar_mult(s, v)` that takes a number, `s`, and a list, `v` and returns the **scalar multiple**¹⁰ of `v` by `s`:

¹⁰http://en.wikipedia.org/wiki/Scalar_multiple

```

1 test(scalar_mult(5, [1, 2]) == [5, 10])
2 test(scalar_mult(3, [1, 0, -1]) == [3, 0, -3])
3 test(scalar_mult(7, [3, 0, 5, 11, 2]) == [21, 0, 35, 77, 14])

```

7. Write a function `dot_product(u, v)` that takes two lists of numbers of the same length, and returns the sum of the products of the corresponding elements of each (the [dot_product](#)¹¹).

```

1 test(dot_product([1, 1], [1, 1]) == 2)
2 test(dot_product([1, 2], [1, 4]) == 9)
3 test(dot_product([1, 2, 1], [1, 4, 3]) == 12)

```

8. **Extra challenge for the mathematically inclined:** Write a function `cross_product(u, v)` that takes two

lists of numbers of length 3 and returns their [cross product](#)¹². You should write your own tests.

9. Describe the relationship between `" ".join(song.split())` and `song` in the fragment of code below. Are

they the same for all strings assigned to `song`? When would they be different?

```

1 song = "The rain in Spain..."

```

10. Write a function `replace(s, old, new)` that replaces all occurrences of `old` with `new` in a string `s`:

```

1 test(replace("Mississippi", "i", "I") == "MIssIssIppI")
2
3 s = "I love spom! Spom is my favorite food. Spom, spom, yum!"
4 test(replace(s, "om", "am") ==
5       "I love spam! Spam is my favorite food. Spam, spam, yum!")
6
7 test(replace(s, "o", "a") ==
8       "I lave spam! Spam is my favarite faad. Spam, spam, yum!")

```

¹¹http://en.wikipedia.org/wiki/Dot_product

¹²http://en.wikipedia.org/wiki/Cross_product

Hint: use the `split` and `join` methods.

11. Suppose you want to swap around the values in two variables. You decide to factor this out into a

reusable function, and write this code:

```
1  def swap(x, y):          # Incorrect version
2      print("before swap statement: x:", x, "y:", y)
3      (x, y) = (y, x)
4      print("after swap statement: x:", x, "y:", y)
5
6  a = ["This", "is", "fun"]
7  b = [2,3,4]
8  print("before swap function call: a:", a, "b:", b)
9  swap(a, b)
10 print("after swap function call: a:", a, "b:", b)
```

Run this program and describe the results. Oops! So it didn't do what you intended! Explain why not. Using a Python visualizer like the one at <http://pythontutor.com> may help you build a good conceptual model of what is going on. What will be the values of `a` and `b` after the call to `swap`?

Chapter 12: Modules

A **module** is a file containing Python definitions and statements intended for use in other Python programs. There are many Python modules that come with Python as part of the **standard library**. We have seen at least two of these already, the `turtle` module and the `string` module.

We have also shown you how to access help. The help system contains a listing of all the standard modules that are available with Python. Play with help!

12.1. Random numbers

We often want to use random numbers in programs, here are a few typical uses:

- To play a game of chance where the computer needs to throw some dice, pick a number, or flip a coin
- To shuffle a deck of playing cards randomly,
- To allow/make an enemy spaceship appear at a random location and start shooting at the player
- To simulate possible rainfall when we make a computerized model for estimating the environmental impact of building a dam,
- For encrypting banking sessions on the Internet.

Python provides a module `random` that helps with tasks like this. You can look it up using help, but here are the key things we'll do with it:

```
1 import random
2
3 # Create a black box object that generates random numbers
4 rng = random.Random()
5
6 dice_throw = rng.randrange(1,7)    # Return an int, one of 1,2,3,4,5,6
7 delay_in_seconds = rng.random() * 5.0
```

The `randrange` method call generates an integer between its lower and upper argument, using the same semantics as `range` — so the lower bound is included, but the upper bound is excluded. All the values have

an equal probability of occurring (i.e. the results are *uniformly* distributed). Like `range`, `randrange` can also take an optional step argument. So let's assume we needed a random odd number less than 100, we could say:

```
1 r_odd = rng.randrange(1, 100, 2)
```

Other methods can also generate other distributions e.g. a bell-shaped, or “normal” distribution might be more appropriate for estimating seasonal rainfall, or the concentration of a compound in the body after taking a dose of medicine.

The `random` method returns a floating point number in the interval $[0.0, 1.0)$ — the square bracket means “closed interval on the left” and the round parenthesis means “open interval on the right”. In other words, 0.0 is possible, but all returned numbers will be strictly less than 1.0. It is usual to *scale* the results after calling this method, to get them into an interval suitable for your application. In the case shown here, we’ve converted the result of the method call to a number in the interval $[0.0, 5.0)$. Once more, these are uniformly distributed numbers — numbers close to 0 are just as likely to occur as numbers close to 0.5, or numbers close to 1.0.

This example shows how to shuffle a list. (`shuffle` cannot work directly with a lazy promise, so notice that we had to convert the range object using the `list` type converter first.)

```
1 cards = list(range(52)) # Generate ints [0 .. 51]
2                               # representing a pack of cards.
3 rng.shuffle(cards)      # Shuffle the pack
```

12.1.1. Repeatability and Testing

Random number generators are based on a **deterministic** algorithm — repeatable and predictable. So they’re called **pseudo-random** generators — they are not genuinely random. They start with a *seed* value. Each time you ask for another random number, you’ll get one based on the current seed attribute, and the state of the seed (which is one of the attributes of the generator) will be updated.

For debugging and for writing unit tests, it is convenient to have repeatability — programs that do the same thing every time they are run. We can arrange this by forcing the random number generator to be initialized with a known seed every time. (Often this is only wanted during testing — playing a game of cards where the shuffled deck was always in the same order as last time you played would get boring very rapidly!)

```
1 drng = random.Random(123) # Create generator with known starting state
```

This alternative way of creating a random number generator gives an explicit seed value to the object. Without this argument, the system probably uses something based on the time. So grabbing some random numbers from `drng` today will give you precisely the same random sequence as it will tomorrow!

12.1.2. Picking balls from bags, throwing dice, shuffling a pack of cards

Here is an example to generate a list containing `n` random ints between a lower and an upper bound:

```

1  import random
2
3  def make_random_ints(num, lower_bound, upper_bound):
4      """
5          Generate a list containing num random ints between lower_bound
6          and upper_bound. upper_bound is an open bound.
7      """
8      rng = random.Random() # Create a random number generator
9      result = []
10     for i in range(num):
11         result.append(rng.randrange(lower_bound, upper_bound))
12     return result

```

```

1  >>> make_random_ints(5, 1, 13) # Pick 5 random month numbers
2  [8, 1, 8, 5, 6]

```

Notice that we got a duplicate in the result. Often this is wanted, e.g. if we throw a die five times, we would expect some duplicates.

But what if you don't want duplicates? If you wanted 5 distinct months, then this algorithm is wrong. In this case a good algorithm is to generate the list of possibilities, shuffle it, and slice off the number of elements you want:

```

1  xs = list(range(1,13)) # Make list 1..12 (there are no duplicates)
2  rng = random.Random() # Make a random number generator
3  rng.shuffle(xs)        # Shuffle the list
4  result = xs[:5]        # Take the first five elements

```

In statistics courses, the first case — allowing duplicates — is usually described as pulling balls out of a bag *with replacement* — you put the drawn ball back in each time, so it can occur again. The latter case, with no duplicates, is usually described as pulling balls out of the bag *without replacement*. Once the ball is drawn, it doesn't go back to be drawn again. TV lotto games work like this.

The second “shuffle and slice” algorithm would not be so great if you only wanted a few elements, but from a very large domain. Suppose I wanted five numbers between one and ten million, without duplicates. Generating a list of ten million items, shuffling it, and then slicing off the first five would be a performance disaster! So let us have another try:

```

1  import random
2
3  def make_random_ints_no_dups(num, lower_bound, upper_bound):
4      """
5          Generate a list containing num random ints between
6          lower_bound and upper_bound. upper_bound is an open bound.
7          The result list cannot contain duplicates.
8      """
9      result = []
10     rng = random.Random()
11     for i in range(num):
12         while True:
13             candidate = rng.randrange(lower_bound, upper_bound)
14             if candidate not in result:
15                 break
16             result.append(candidate)
17     return result
18
19 xs = make_random_ints_no_dups(5, 1, 10000000)
20 print(xs)

```

This agreeably produces 5 random numbers, without duplicates:

```
1 [3344629, 1735163, 9433892, 1081511, 4923270]
```

Even this function has its pitfalls. Can you spot what is going to happen in this case?

```
1 xs = make_random_ints_no_dups(10, 1, 6)
```

12.2. The `time` module

As we start to work with more sophisticated algorithms and bigger programs, a natural concern is “*is our code efficient?*” One way to experiment is to time how long various operations take. The `time` module has a function called `process_time` that is recommended for this purpose. Whenever `process_time` is called, it returns a floating point number representing how many seconds have elapsed since your program started running.

The way to use it is to call `process_time` assign the result to a variable, say `t0`, just before you start executing the code you want to measure. Then after execution, call `process_time` again, (this time we’ll save

the result in variable `t1`). The difference `t1 - t0` is the time elapsed, and is a measure of how fast your program is running.

Let's try a small example. Python has a built-in `sum` function that can sum the elements in a list. We can also write our own. How do we think they would compare for speed? We'll try to do the summation of a list

`[0, 1, 2 ...]` in both cases, and compare the results:

```

1  import time
2
3  def do_my_sum(xs):
4      sum = 0
5      for v in xs:
6          sum += v
7      return sum
8
9  sz = 10000000          # Lets have 10 million elements in the list
10 testdata = range(sz)
11
12 t0 = time.process_time()
13 my_result = do_my_sum(testdata)
14 t1 = time.process_time()
15 print("my_result    = {0} (time taken = {1:.4f} seconds)"
16       .format(my_result, t1-t0))
17
18 t2 = time.process_time()
19 their_result = sum(testdata)
20 t3 = time.process_time()
21 print("their_result = {0} (time taken = {1:.4f} seconds)"
22       .format(their_result, t3-t2))

```

On a reasonably modest laptop, we get these results:

```

1  my_sum    = 49999995000000 (time taken = 1.5567 seconds)
2  their_sum = 49999995000000 (time taken = 0.9897 seconds)

```

So our function runs about 57% slower than the built-in one. Generating and summing up ten million elements in under a second is not too shabby!

12.3. The `math` module

The `math` module contains the kinds of mathematical functions you'd typically find on your calculator (`sin`, `cos`, `sqrt`, `asin`, `log`, `log10`) and some mathematical constants like `pi` and `e`:

```

1 >>> import math
2 >>> math.pi           # Constant pi
3 3.141592653589793
4 >>> math.e             # Constant natural log base
5 2.718281828459045
6 >>> math.sqrt(2.0)     # Square root function
7 1.4142135623730951
8 >>> math.radians(90)   # Convert 90 degrees to radians
9 1.5707963267948966
10 >>> math.sin(math.radians(90)) # Find sin of 90 degrees
11 1.0
12 >>> math.asin(1.0) * 2 # Double the arcsin of 1.0 to get pi
13 3.141592653589793

```

Like almost all other programming languages, angles are expressed in *radians* rather than degrees. There are two functions `radians` and `degrees` to convert between these two popular ways of measuring angles.

Notice another difference between this module and our use of `random` and `turtle`: in `random` and `turtle` we create objects and we call methods on the object. This is because objects have *state* — a `turtle` has a color, a position, a heading, etc., and every random number generator has a seed value that determines its next result.

Mathematical functions are “pure” and don’t have any state — calculating the square root of 2.0 doesn’t depend on any kind of state or history about what happened in the past. So the functions are not methods of an object — they are simply functions that are grouped together in a module called `math`.

12.4. Creating your own modules

All we need to do to create our own modules is to save our script as a file with a `.py` extension. Suppose, for example, this script is saved as a file named `seqtools.py`:

```

1 def remove_at(pos, seq):
2     return seq[:pos] + seq[pos+1:]

```

We can now use our module, both in scripts we write, or in the interactive Python interpreter. To do so, we must first `import` the module.

```
1 >>> import seqtools
2 >>> s = "A string!"
3 >>> seqtools.remove_at(4, s)
4 'A sting!'
```

We do not include the `.py` file extension when importing. Python expects the file names of Python modules to end in `.py`, so the file extension is not included in the **import statement**.

The use of modules makes it possible to break up very large programs into manageable sized parts, and to keep related parts together.

12.5. Namespaces

A **namespace** is a collection of identifiers that belong to a module, or to a function, (and as we will see soon, in classes too). Generally, we like a namespace to hold “related” things, e.g. all the math functions, or all the typical things we’d do with random numbers.

Each module has its own namespace, so we can use the same identifier name in multiple modules without causing an identification problem.

```
1 # Module1.py
2
3 question = "What is the meaning of Life, the Universe, and Everything?"
4 answer = 42

1 # Module2.py
2
3 question = "What is your quest?"
4 answer = "To seek the holy grail."
```

We can now import both modules and access `question` and `answer` in each:

```
1 import module1
2 import module2
3
4 print(module1.question)
5 print(module2.question)
6 print(module1.answer)
7 print(module2.answer)
```

will output the following:

```
1 What is the meaning of Life, the Universe, and Everything?  
2 What is your quest?  
3 42  
4 To seek the holy grail.
```

Functions also have their own namespaces:

```
1 def f():  
2     n = 7  
3     print("printing n inside of f:", n)  
4  
5 def g():  
6     n = 42  
7     print("printing n inside of g:", n)  
8  
9 n = 11  
10 print("printing n before calling f:", n)  
11 f()  
12 print("printing n after calling f:", n)  
13 g()  
14 print("printing n after calling g:", n)
```

Running this program produces the following output:

```
1 printing n before calling f: 11  
2 printing n inside of f: 7  
3 printing n after calling f: 11  
4 printing n inside of g: 42  
5 printing n after calling g: 11
```

The three `n`'s here do not collide since they are each in a different namespace — they are three names for three different variables, just like there might be three different instances of people, all called “Bruce”.

Namespaces permit several programmers to work on the same project without having naming collisions.

How are namespaces, files and modules related?

Python has a convenient and simplifying one-to-one mapping, one module per file, giving rise to one namespace. Also, Python takes the module name from the file name, and this becomes the name of the namespace.

`math.py` is a filename, the module is called `math`, and its namespace is `math`. So in Python the concepts are more or less interchangeable.

But you will encounter other languages (e.g. C#), that allow one module to span multiple files, or one file to have multiple namespaces, or many files to all share the same namespace. So the name of the file doesn't need to be the same as the namespace.

So a good idea is to try to keep the concepts distinct in your mind.

Files and directories organize *where* things are stored in our computer. On the other hand, namespaces and modules are a programming concept: they help us organize how we want to group related functions and attributes. They are not about “where” to store things, and should not have to coincide with the file and directory structures.

So in Python, if you rename the file `math.py`, its module name also changes, your `import` statements would need to change, and your code that refers to functions or attributes inside that namespace would also need to change.

In other languages this is not necessarily the case. So don't blur the concepts, just because Python blurs them!

12.6. Scope and lookup rules

The **scope** of an identifier is the region of program code in which the identifier can be accessed, or used.

There are three important scopes in Python:

- **Local scope** refers to identifiers declared within a function. These identifiers are kept in the namespace that belongs to the function, and each function has its own namespace.
- **Global scope** refers to all the identifiers declared within the current module, or file.
- **Built-in scope** refers to all the identifiers built into Python — those like `range` and `min` that can be used without having to import anything, and are (almost) always available.

Python (like most other computer languages) uses precedence rules: the same name could occur in more than one of these scopes, but the innermost, or local scope, will always take precedence over the global scope, and the global scope always gets used in preference to the built-in scope. Let's start with a simple example:

```
1 def range(n):
2     return 123*n
3
4 print(range(10))
```

What gets printed? We've defined our own function called `range`, so there is now a potential ambiguity. When we use `range`, do we mean our own one, or the built-in one? Using the scope

lookup rules determines this: our own `range` function, not the built-in one, is called, because our function `range` is in the global namespace, which takes precedence over the built-in names.

So although names like `range` and `min` are built-in, they can be “hidden” from your use if you choose to define your own variables or functions that reuse those names. (It is a confusing practice to redefine built-in names — so to be a good programmer you need to understand the scope rules and understand that you can do nasty things that will cause confusion, and then you avoid doing them!)

Now, a slightly more complex example:

```
1 n = 10
2 m = 3
3 def f(n):
4     m = 7
5     return 2*n+m
6
7 print(f(5), n, m)
```

This prints `17 10 3`. The reason is that the two variables `m` and `n` in lines 1 and 2 are outside the function in the global namespace. Inside the function, new variables called `n` and `m` are created *just for the duration of the execution of `f`*. These are created in the local namespace of function `f`. Within the body of `f`, the scope lookup rules determine that we use the local variables `m` and `n`. By contrast, after we’ve returned from `f`, the `n` and `m` arguments to the `print` function refer to the original variables on lines 1 and 2, and these have not been changed in any way by executing function `f`.

Notice too that the `def` puts name `f` into the global namespace here. So it can be called on line 7.

What is the scope of the variable `n` on line 1? Its scope — the region in which it is visible — is lines 1, 2, 6, 7. It is hidden from view in lines 3, 4, 5 because of the local variable `n`.

12.7. Attributes and the dot operator

Variables defined inside a module are called **attributes** of the module. We’ve seen that objects have attributes too: for example, most objects have a `__doc__` attribute, some functions have a `__annotations__` attribute. Attributes are accessed using the **dot operator** (`.`). The `question` attribute of `module1` and `module2` is accessed using `module1.question` and `module2.question`.

Modules contain functions as well as attributes, and the dot operator is used to access them in the same way. `seqtools.remove_at` refers to the `remove_at` function in the `seqtools` module.

When we use a dotted name, we often refer to it as a **fully qualified name**, because we’re saying exactly which `question` attribute we mean.

12.8. Three `import` statement variants

Here are three different ways to import names into the current namespace, and to use them:

```
1 import math
2 x = math.sqrt(10)
```

Here just the single identifier `math` is added to the current namespace. If you want to access one of the functions in the module, you need to use the dot notation to get to it.

Here is a different arrangement:

```
1 from math import cos, sin, sqrt
2 x = sqrt(10)
```

The names are added directly to the current namespace, and can be used without qualification. The name `math` is not itself imported, so trying to use the qualified form `math.sqrt` would give an error.

Then we have a convenient shorthand:

```
1 from math import *    # Import all the identifiers from math,
2                       #   adding them to the current namespace.
3 x = sqrt(10)          # Use them without qualification.
```

Of these three, the first method is generally preferred, even though it means a little more typing each time. Although, we can make things shorter by importing a module under a different name:

```
1 >>> import math as m
2 >>> m.pi
3 3.141592653589793
```

But hey, with nice editors that do auto-completion, and fast fingers, that's a small price!

Finally, observe this case:

```
1 def area(radius):
2     import math
3     return math.pi * radius * radius
4
5 x = math.sqrt(10)    # This gives an error
```

Here we imported `math`, but we imported it into the local namespace of `area`. So the name is usable within the function body, but not in the enclosing script, because it is not in the global namespace.

12.9. Turn your unit tester into a module

Near the end of Chapter 6 (Fruitful functions) we introduced unit testing, and our own `test` function, and you've had to copy this into each module for which you wrote tests. Now we can put that definition into a module of its own, say `unit_tester.py`, and simply use one line in each new script instead:

```
1 from unit_tester import test
```

12.10. Glossary

attribute

A variable defined inside a module (or class or instance – as we will see later). Module attributes are accessed by using the **dot operator** (`.`).

dot operator

The dot operator (`.`) permits access to attributes and functions of a module (or attributes and methods of a class or instance – as we have seen elsewhere).

fully qualified name

A name that is prefixed by some namespace identifier and the dot operator, or by an instance object, e.g. `math.sqrt` or `tess.forward(10)`.

import statement

A statement which makes the objects contained in a module available for use within another module. There are two forms for the import statement. Using hypothetical modules named `mymod1` and `mymod2` each containing functions `f1` and `f2`, and variables `v1` and `v2`, examples of these two forms include:

```
1 import mymod1
2 from mymod2 import f1, f2, v1, v2
```

The second form brings the imported objects into the namespace of the importing module, while the first form preserves a separate namespace for the imported module, requiring `mymod1.v1` to access the `v1` variable from that module.

method

Function-like attribute of an object. Methods are *invoked* (called) on an object using the dot operator. For example:


```
1 >>> s = "this is a string."  
2 >>> s.upper()  
3 'THIS IS A STRING.'  
4 >>>
```

We say that the method, `upper` is invoked on the string, `s`. `s` is implicitly the first argument to `upper`.

module

A file containing Python definitions and statements intended for use in other Python programs. The contents of a module are made available to the other program by using the `import` statement.

namespace

A syntactic container providing a context for names so that the same name can reside in different namespaces without ambiguity. In Python, modules, classes, functions and methods all form namespaces.

naming collision

A situation in which two or more names in a given namespace cannot be unambiguously resolved. Using

```
1 import string
```

instead of

```
1 from string import *
```

prevents naming collisions.

standard library

A library is a collection of software used as tools in the development of other software. The standard library of a programming language is the set of such tools that are distributed with the core programming language. Python comes with an extensive standard library.

12.11. Exercises

1. Open help for the `calendar` module.
1. Try the following:

```

1  import calendar
2  cal = calendar.TextCalendar()      # Create an instance
3  cal.pryear(2012)                  # What happens here?

```

2. Observe that the week starts on Monday. An adventurous CompSci student believes that it is better

mental chunking to have his week start on Thursday, because then there are only two working days to the weekend, and every week has a break in the middle. Read the documentation for `TextCalendar`, and see how you can help him print a calendar that suits his needs.

3. Find a function to print just the month in which your birthday occurs this year.

4. Try this:

```

1  d = calendar.LocaleTextCalendar(6, "SPANISH")
2  d.pryear(2012)
3
4  Try a few other languages, including one that doesn't work, and see what happens.

```

5. Experiment with `calendar.isleap`. What does it expect as an argument? What does it return as a result? What kind of a function is this?

Make detailed notes about what you learned from these exercises.

2. Open help for the `math` module.

1. How many functions are in the `math` module?

2. What does `math.ceil` do? What about `math.floor`? (*hint: both `floor` and `ceil` expect floating point arguments.*)

3. Describe how we have been computing the same value as `math.sqrt` without using the `math` module.

4. What are the two data constants in the `math` module?

Record detailed notes of your investigation in this exercise.

3. Investigate the `copy` module. What does `deepcopy` do? In which exercises from last chapter would `deepcopy` have come in handy?

4. Create a module named `mymodule1.py`. Add attributes `myage` set to your current age, and `year` set to

the current year. Create another module named `mymodule2.py`. Add attributes `myage` set to 0, and `year` set to the year you were born. Now create a file named `namespace_test.py`. Import both of

the modules above and write the following statement:

```
1     print( (mymodule2.myage - mymodule1.myage) ==
2             (mymodule2.year - mymodule1.year) )
```

When you will run `namespace_test.py` you will see either `True` or `False` as output depending on whether or not you've already had your birthday this year.

What this example illustrates is that out different modules can both have attributes named `myage` and `year`. Because they're in different namespaces, they don't clash with one another. When we write `namespace_test.py`, we fully qualify exactly which variable `year` or `myage` we are referring to.

5. Add the following statement to `mymodule1.py`, `mymodule2.py`, and `namespace_test.py` from the previous exercise:

```
1     print("My name is", __name__)
```

Run `namespace_test.py`. What happens? Why? Now add the following to the bottom of `mymodule1.py`:

```
1     if __name__ == "__main__":
2         print("This won't run if I'm imported.")
```

Run `mymodule1.py` and `namespace_test.py` again. In which case do you see the new print statement?

6. In a Python shell / interactive interpreter, try the following:

```
1     >>> import this
```

What does Tim Peters have to say about namespaces?

7. Give the Python interpreter's response to each of the following from a continuous interpreter session:

```

1     >>> s = "If we took the bones out, it wouldn't be crunchy, would it?"
2     >>> s.split()
3     >>> type(s.split())
4     >>> s.split("o")
5     >>> s.split("i")
6     >>> "0".join(s.split("o"))

```

Be sure you understand why you get each result. Then apply what you have learned to fill in the body of the function below using the `split` and `join` methods of `str` objects:

```

1     def myreplace(old, new, s):
2         """ Replace all occurrences of old with new in s. """
3         ...
4
5
6     test(myreplace(",", ";", "this, that, and some other thing") ==
7          "this; that; and some other thing")
8     test(myreplace(" ", "**",
9                   "Words will now      be separated by stars.") ==
10          "Words**will**now**be**separated**by**stars.")

```

Your solution should pass the tests.

8. Create a module named `wordtools.py` with our test scaffolding in place.

Now add functions to these tests pass:

```

1  test(cleanword("what?") == "what")
2  test(cleanword("'now!'") == "now")
3  test(cleanword("?+='w-o-r-d!,@$()'") == "word")
4
5  test(has_dashdash("distance--but"))
6  test(not has_dashdash("several"))
7  test(has_dashdash("spoke--"))
8  test(has_dashdash("distance--but"))
9  test(not has_dashdash("-yo-yo-"))
10
11 test(extract_words("Now is the time! 'Now', is the time? Yes, now.") == ['now', 'is',
12 , 'the', 'time', 'now', 'is', 'the', 'time', 'yes', 'now'])
13 test(extract_words("she tried to curtsey as she spoke--fancy") == ['she', 'tried', 'to',
14 , 'curtsey', 'as', 'she', 'spoke', 'fancy'])

```

```
15
16 test(wordcount("now", ["now", "is", "time", "is", "now", "is", "is"])) == 2)
17 test(wordcount("is", ["now", "is", "time", "is", "now", "the", "is"])) == 3)
18 test(wordcount("time", ["now", "is", "time", "is", "now", "is", "is"])) == 1)
19 test(wordcount("frog", ["now", "is", "time", "is", "now", "is", "is"])) == 0)
20
21 test(wordset(["now", "is", "time", "is", "now", "is", "is"])) == ["is", "now", "time" \
22 ]
23 test(wordset(["I", "a", "a", "is", "a", "is", "I", "am"])) == ["I", "a", "am", "is"])
24 test(wordset(["or", "a", "am", "is", "are", "be", "but", "am"])) == ["a", "am", "are" \
25 , "be", "but", "is", "or"])
26
27 test(longestword(["a", "apple", "pear", "grape"])) == 5)
28 test(longestword(["a", "am", "I", "be"])) == 2)
29 test(longestword(["this", "supercalifragilisticexpialidocious"])) == 34)
30 test(longestword([ ]) == 0)
```

Save this module so you can use the tools it contains in future programs.

Chapter 13: Files

13.1. About files

While a program is running, its data is stored in *random access memory* (RAM). RAM is fast and inexpensive, but it is also **volatile**, which means that when the program ends, or the computer shuts down, data in

RAM disappears. To make data available the next time the computer is turned on and the program is started, it has to be written to a **non-volatile** storage medium, such a hard drive, usb drive, or CD-RW.

Data on non-volatile storage media is stored in named locations on the media called **files**. By reading and writing files, programs can save information between program runs.

Working with files is a lot like working with a notebook. To use a notebook, it has to be opened. When done, it has to be closed. While the notebook is open, it can either be read from or written to. In either case, the notebook holder knows where they are. They can read the whole notebook in its natural order or they can skip around.

All of this applies to files as well. To open a file, we specify its name and indicate whether we want to read or write.

13.2. Writing our first file

Let's begin with a simple program that writes three lines of text into a file:

```
1 myfile = open("test.txt", "w")
2 myfile.write("My first file written from Python\n")
3 myfile.write("-----\n")
4 myfile.write("Hello, world!\n")
5 myfile.close()
```

Opening a file creates what we call a file **handle**. In this example, the variable `myfile` refers to the new handle object. Our program calls methods on the handle, and this makes changes to the actual file which is usually located on our disk.

On line 1, the `open` function takes two arguments. The first is the name of the file, and the second is the **mode**. Mode `"w"` means that we are opening the file for writing.

With mode "w", if there is no file named `test.txt` on the disk, it will be created. If there already is one, it will be replaced by the file we are writing.

To put data in the file we invoke the `write` method on the handle, shown in lines 2, 3 and 4 above. In bigger programs, lines 2–4 will usually be replaced by a loop that writes many more lines into the file.

Closing the file handle (line 5) tells the system that we are done writing and makes the disk file available for reading by other programs (or by our own program).

A handle is somewhat like a TV remote control

We're all familiar with a remote control for a TV. We perform operations on the remote control — switch channels, change the volume, etc. But the real action happens on the TV. So, by simple analogy, we'd call the remote control our handle to the underlying TV.

Sometimes we want to emphasize the difference — the file handle is not the same as the file, and the remote control is not the same as the TV. But at other times we prefer to treat them as a single mental chunk, or abstraction, and we'll just say "close the file", or "flip the TV channel".

13.3. Reading a file line-at-a-time

Now that the file exists on our disk, we can open it, this time for reading, and read all the lines in the file, one at a time. This time, the mode argument is "r" for reading:

```

1 mynewhandle = open("test.txt", "r")
2 while True:                                # Keep reading forever
3     theline = mynewhandle.readline()        # Try to read next line
4     if len(theline) == 0:                    # If there are no more lines
5         break                                # leave the loop
6
7     # Now process the line we've just read
8     print(theline, end="")
9
10 mynewhandle.close()
```

This is a handy pattern for our toolbox. In bigger programs, we'd squeeze more extensive logic into the body of the loop at line 8 —for example, if each line of the file contained the name and email address of one of our friends, perhaps we'd split the line into some pieces and call a function to send the friend a party invitation.

On line 8 we suppress the newline character that `print` usually appends to our strings. Why? This is because the string already has its own newline: the `readline` method in line 3 returns everything up to *and including* the newline character. This also explains the end-of-file detection logic: when

there are no more lines to be read from the file, `readline` returns an empty string — one that does not even have a newline at the end, hence its length is 0.

Fail first ...

In our sample case here, we have three lines in the file, yet we enter the loop *four* times. In Python, you only learn that the file has no more lines by failure to read another line. In some other programming languages (e.g. Pascal), things are different: there you read three lines, but you have what is called *look ahead* — after reading the third line you already know that there are no more lines in the file. You're not even allowed to try to read the fourth line.

So the templates for working line-at-a-time in Pascal and Python are subtly different!

When you transfer your Python skills to your next computer language, be sure to ask how you'll know when the file has ended: is the style in the language “try, and after you fail you'll know”, or is it “look ahead”?

If we try to open a file that doesn't exist, we get an error:

```
1 >>> mynewhandle = open("wharrah.txt", "r")
2 IOError: [Errno 2] No such file or directory: "wharrah.txt"
```

13.4. Turning a file into a list of lines

It is often useful to fetch data from a disk file and turn it into a list of lines. Suppose we have a file containing our friends and their email addresses, one per line in the file. But we'd like the lines sorted into alphabetical order. A good plan is to read everything into a list of lines, then sort the list, and then write the sorted list back to another file:

```
1 f = open("friends.txt", "r")
2 xs = f.readlines()
3 f.close()
4
5 xs.sort()
6
7 g = open("sortedfriends.txt", "w")
8 for v in xs:
9     g.write(v)
10 g.close()
```

The `readlines` method in line 2 reads all the lines and returns a list of the strings.

We could have used the template from the previous section to read each line one-at-a-time, and to build up the list ourselves, but it is a lot easier to use the method that the Python implementors gave us!

13.5. Reading the whole file at once

Another way of working with text files is to read the complete contents of the file into a string, and then to use our string-processing skills to work with the contents.

We'd normally use this method of processing files if we were not interested in the line structure of the file. For example, we've seen the `split` method on strings which can break a string into words. So here is how we might count the number of words in a file:

```
1 f = open("somefile.txt")
2 content = f.read()
3 f.close()
4
5 words = content.split()
6 print("There are {0} words in the file.".format(len(words)))
```

Notice here that we left out the "r" mode in line 1. By default, if we don't supply the mode, Python opens the file for reading.

Your file paths may need to be explicitly named.

In the above example, we're assuming that the file `somefile.txt` is in the same directory as your Python source code. If this is not the case, you may need to provide a full or a relative path to the file. On Windows, a full path could look like `"C:\\temp\\somefile.txt"`, while on a Unix system the full path could be `"/home/jimmy/somefile.txt"`.

We'll return to this later in this chapter.

13.6. Working with binary files

Files that hold photographs, videos, zip files, executable programs, etc. are called **binary** files: they're not organized into lines, and cannot be opened with a normal text editor. Python works just as easily with binary files, but when we read from the file we're going to get bytes back rather than a string. Here we'll copy one binary file to another:

```
1 f = open("somefile.zip", "rb")
2 g = open("thecopy.zip", "wb")
3
4 while True:
5     buf = f.read(1024)
6     if len(buf) == 0:
7         break
8     g.write(buf)
9
10 f.close()
11 g.close()
```

There are a few new things here. In lines 1 and 2 we added a "b" to the mode to tell Python that the files are binary rather than text files. In line 5, we see `read` can take an argument which tells it how many bytes to attempt to read from the file. Here we chose to read and write up to 1024 bytes on each iteration of the loop. When we get back an empty buffer from our attempt to read, we know we can break out of the loop and close both the files.

If we set a breakpoint at line 6, (or `print type(buf)` there) we'll see that the type of `buf` is `bytes`. We don't do any detailed work with bytes objects in this textbook.

13.7. An example

Many useful line-processing programs will read a text file line-at-a-time and do some minor processing as they write the lines to an output file. They might number the lines in the output file, or insert extra blank lines after every 60 lines to make it convenient for printing on sheets of paper, or extract some specific columns only from each line in the source file, or only print lines that contain a specific substring. We call this kind of program a **filter**.

Here is a filter that copies one file to another, omitting any lines that begin with #:

```
1 def filter(oldfile, newfile):
2     infile = open(oldfile, "r")
3     outfile = open(newfile, "w")
4     while True:
5         text = infile.readline()
6         if len(text) == 0:
7             break
8         if text[0] == "#":
9             continue
10
11         # Put any more processing logic here
12         outfile.write(text)
```

```

13
14     infile.close()
15     outfile.close()

```

The `continue` statement at line 9 skips over the remaining lines in the current iteration of the loop, but the loop will still iterate. This style looks a bit contrived here, but it is often useful to say “*get the lines we’re not concerned with out of the way early, so that we have cleaner more focused logic in the meaty part of the loop that might be written around line 11.*”

Thus, if `text` is the empty string, the loop exits. If the first character of `text` is a hash mark, the flow of execution goes to the top of the loop, ready to start processing the next line. Only if both conditions fail do we fall through to do the processing at line 11, in this example, writing the line into the new file.

Let’s consider one more case: suppose our original file contained empty lines. At line 6 above, would this program find the first empty line in the file, and terminate immediately? No! Recall that `readline` always includes the newline character in the string it returns. It is only when we try to read *beyond* the end of the file that we get back the empty string of length 0.

13.8. Directories

Files on non-volatile storage media are organized by a set of rules known as a **file system**. File systems are made up of files and **directories**, which are containers for both files and other directories.

When we create a new file by opening it and writing, the new file goes in the current directory (wherever we were when we ran the program). Similarly, when we open a file for reading, Python looks for it in the current directory.

If we want to open a file somewhere else, we have to specify the **path** to the file, which is the name of the directory (or folder) where the file is located:

```

1  >>> wordsfile = open("/usr/share/dict/words", "r")
2  >>> wordlist = wordsfile.readlines()
3  >>> print(wordlist[:6])
4  ['\n', 'A\n', 'A's\n', 'AOL\n', 'AOL's\n', 'Aachen\n']

```

This (Unix) example opens a file named `words` that resides in a directory named `dict`, which resides in `share`, which resides in `usr`, which resides in the top-level directory of the system, called `/`. It then reads in each line into a list using `readlines`, and prints out the first 5 elements from that list.

A Windows path might be `"c:/temp/words.txt"` or `"c:\\temp\\words.txt"`. Because backslashes are used to escape things like newlines and tabs, we need to write two backslashes in a literal string to get one! So the length of these two strings is the same!

We cannot use / or \ as part of a filename; they are reserved as a **delimiter** between directory and filenames.

The file `/usr/share/dict/words` should exist on Unix-based systems, and contains a list of words in alphabetical order.

13.9. What about fetching something from the web?

The Python libraries are pretty messy in places. But here is a very simple example that copies the contents at some web URL to a local file.

```
1 import urllib.request
2
3 url = "https://www.ietf.org/rfc/rfc793.txt"
4 destination_filename = "rfc793.txt"
5
6 urllib.request.urlretrieve(url, destination_filename)
```

The `urlretrieve` function — just one call — could be used to download any kind of content from the Internet.

We'll need to get a few things right before this works:

- The resource we're trying to fetch must exist! Check this using a browser.
- We'll need permission to write to the destination filename, and the file will be created in the “current directory” - i.e. the same folder that the Python program is saved in.
- If we are behind a proxy server that requires authentication, (as some students are), this may require some more special handling to work around our proxy. Use a local resource for the purpose of this demonstration!

Here is a slightly different example. Rather than save the web resource to our local disk, we read it directly into a string, and return it:

```
1 import urllib.request
2
3 def retrieve_page(url):
4     """ Retrieve the contents of a web page.
5         The contents is converted to a string before returning it.
6     """
7     my_socket = urllib.request.urlopen(url)
8     data = str(my_socket.read())
9     my_socket.close()
```

```
10     return dta
11
12 the_text = retrieve_page("https://www.ietf.org/rfc/rfc793.txt")
13 print(the_text)
```

Opening the remote url returns what we call a **socket**. This is a handle to our end of the connection between our program and the remote web server. We can call read, write, and close methods on the socket

object in much the same way as we can work with a file handle.

13.10. Glossary

delimiter

A sequence of one or more characters used to specify the boundary between separate parts of text.

directory

A named collection of files, also called a folder. Directories can contain files and other directories, which are referred to as *subdirectories* of the directory that contains them.

file

A named entity, usually stored on a hard drive, floppy disk, or CD-ROM, that contains a stream of characters.

file system

A method for naming, accessing, and organizing files and the data they contain.

handle

An object in our program that is connected to an underlying resource (e.g. a file). The file handle lets our program manipulate/read/write/close the actual file that is on our disk.

mode

A distinct method of operation within a computer program. Files in Python can be opened in one of four modes: read ("r"), write ("w"), append ("a"), and read and write ("+").

non-volatile memory

Memory that can maintain its state without power. Hard drives, flash drives, and rewritable compact disks (CD-RW) are each examples of non-volatile memory.

path

A sequence of directory names that specifies the exact location of a file.

text file

A file that contains printable characters organized into lines separated by newline characters.

socket

One end of a connection allowing one to read and write information to or from another computer.

volatile memory

Memory which requires an electrical current to maintain state. The *main memory* or RAM of a computer is volatile. Information stored in RAM is lost when the computer is turned off.

13.11. Exercises

1. Write a program that reads a file and writes out a new file with the lines in reversed order (i.e. the first line in the old file becomes the last one in the new file.)
2. Write a program that reads a file and prints only those lines that contain the substring `snake`.
3. Write a program that reads a text file and produces an output file which is a copy of the file, except the first five columns of each line contain a four digit line number, followed by a space. Start numbering the first line in the output file at 1. Ensure that every line number is formatted to the same width in the output file. Use one of your Python programs as test data for this exercise: your output should be a printed and numbered listing of the Python program.
4. Write a program that undoes the numbering of the previous exercise: it should read a file with numbered lines and produce another file without line numbers.

Chapter 14: List Algorithms

This chapter is a bit different from what we've done so far: rather than introduce more new Python syntax and features, we're going to focus on the program development process, and some algorithms that work with lists.

As in all parts of this book, our expectation is that you, the reader, will copy our code into your Python environment, play and experiment, and work along with us.

Part of this chapter works with the book *Alice in Wonderland* and a *vocabulary file*. Download these two files to your local machine at the following links. https://learnpythontherightway.com/_downloads/alice_in_wonderland.txt¹³ and https://learnpythontherightway.com/_downloads/vocab.txt¹⁴.

14.1. Test-driven development

Early in our Fruitful functions chapter we introduced the idea of *incremental development*, where we added

small fragments of code to slowly build up the whole, so that we could easily find problems early. Later in that same chapter we introduced unit testing and gave code for our testing framework so that we could capture, in code, appropriate tests for the functions we were writing.

Test-driven development (TDD) is a software development practice which takes these practices one step further. The key idea is that automated tests should be written *first*. This technique is called

test-driven because — if we are to believe the extremists — non-testing code should only be written when there is a failing test to make pass.

We can still retain our mode of working in small incremental steps, but now we'll define and express those steps in terms of a sequence of increasingly sophisticated unit tests that demand more from our code at each stage.

We'll turn our attention to some standard algorithms that process lists now, but as we proceed through this chapter we'll attempt to do so in the spirit envisaged by TDD.

14.2. The linear search algorithm

We'd like to know the index where a specific item occurs within in a list of items. Specifically, we'll return the index of the item if it is found, or we'll return -1 if the item doesn't occur in the list. Let

¹³https://learnpythontherightway.com/_downloads/alice_in_wonderland.txt

¹⁴https://learnpythontherightway.com/_downloads/vocab.txt

us

start with some tests:

```
1 friends = ["Joe", "Zoe", "Brad", "Angelina", "Zuki", "Thandi", "Paris"]
2 test(search_linear(friends, "Zoe") == 1)
3 test(search_linear(friends, "Joe") == 0)
4 test(search_linear(friends, "Paris") == 6)
5 test(search_linear(friends, "Bill") == -1)
```

Motivated by the fact that our tests don't even run, let alone pass, we now write the function:

```
1 def search_linear(xs, target):
2     """ Find and return the index of target in sequence xs """
3     for (i, v) in enumerate(xs):
4         if v == target:
5             return i
6     return -1
```

There are a some points to learn here: We've seen a similar algorithm in section 8.10 when we searched for a character in a string. There we used a `while` loop, here we've used a `for` loop, coupled with `enumerate` to extract the `(i, v)` pair on each iteration. There are other variants — for example, we could have used `range` and made the loop run only over the indexes, or we could have used the idiom of returning `None` when the item was not found in the list. But the essential similarity in all these variations is that we test every item in the list in turn, from first to last, using the pattern of the short-circuit *eureka*

traversal that we introduced earlier —that we return from the function as soon as we find the target that we're looking for.

Searching all items of a sequence from first to last is called a **linear search**. Each time we check whether `v == target` we'll call it a **probe**. We like to count probes as a measure of how efficient our algorithm is, and this will be a good enough indication of how long our algorithm will take to execute.

Linear searching is characterized by the fact that the number of probes needed to find some target depends directly on the length of the list. So if the list becomes ten times bigger, we can expect to wait ten times longer when searching for things. Notice too, that if we're searching for a target that is not present in the list, we'll have to go all the way to the end before we can return the negative value. So this case needs N probes, where N is the length of the list. However, if we're searching for a target that does exist in the list, we could be lucky and find it immediately in position 0, or we might have to look further, perhaps even all the way to the last item. On average, when the target is present, we're going to need to go about halfway through the list, or $N/2$ probes.

We say that this search has **linear performance** (linear meaning straight line) because, if we were to measure the average search times for different sizes of lists (N), and then plot a graph of time-to-search against N , we'd get a more-or-less straight line graph.

Analysis like this is pretty meaningless for small lists — the computer is quick enough not to bother if the list only has a handful of items. So generally, we’re interested in the **scalability** of our algorithms — how do they perform if we throw bigger problems at them. Would this search be a sensible one to use if we had a million or ten million items (perhaps the catalog of books in your local library) in our list? What happens for really large datasets, e.g. how does Google search so brilliantly well?

14.3. A more realistic problem

As children learn to read, there are expectations that their vocabulary will grow. So a child of age 14 is expected to know more words than a child of age 8. When prescribing reading books for a grade, an important question might be *“which words in this book are not in the expected vocabulary at this level?”*

Let us assume we can read a vocabulary of words into our program, and read the text of a book, and split it into words. Let us write some tests for what we need to do next. Test data can usually be very small, even if we intend to finally use our program for larger cases:

```

1 vocab = ["apple", "boy", "dog", "down",
2         "fell", "girl", "grass", "the", "tree"]
3 book_words = "the apple fell from the tree to the grass".split()
4 test(find_unknown_words(vocab, book_words) == ["from", "to"])
5 test(find_unknown_words([], book_words) == book_words)
6 test(find_unknown_words(vocab, ["the", "boy", "fell"]) == [])

```

Notice we were a bit lazy, and used `split` to create our list of words —it is easier than typing out the list, and very convenient if you want to input a sentence into the program and turn it into a list of words.

We now need to implement the function for which we’ve written tests, and we’ll make use of our linear search. The basic strategy is to run through each of the words in the book, look it up in the vocabulary, and if it is not in the vocabulary, save it into a new resulting list which we return from the function:


```

1 def find_unknown_words(vocab, wds):
2     """ Return a list of words in wds that do not occur in vocab """
3     result = []
4     for w in wds:
5         if (search_linear(vocab, w) < 0):
6             result.append(w)
7     return result

```

We can happily report now that the tests all pass.

Now let us look at the scalability. We have more realistic vocabulary in the text file that could be downloaded at the beginning of this chapter. Upload the `vocab.txt` file to a new repl so that you can access it from your code.



Now let us read in the file (as a single string) and split it into a list of words. For convenience, we'll create a function to do this for us, and test it on the vocab file.

```

1 def load_words_from_file(filename):
2     """ Read words from filename, return list of words. """
3     f = open(filename, "r")
4     file_content = f.read()
5     f.close()
6     wds = file_content.split()
7     return wds
8
9 bigger_vocab = load_words_from_file("vocab.txt")
10 print("There are {0} words in the vocab, starting with\n {1} "
11       .format(len(bigger_vocab), bigger_vocab[:6]))

```

Python responds with:

```

1 There are 19469 words in the vocab, starting with
2 ['a', 'aback', 'abacus', 'abandon', 'abandoned', 'abandonment']

```

So we've got a more sensible size vocabulary. Now let us load up a book, once again we'll use the one we downloaded at the beginning of this chapter. Loading a book is much like loading words from a file, but

we're going to do a little extra black magic. Books are full of punctuation, and have mixtures of lowercase and uppercase letters. We need to clean up the contents of the book. This will involve removing punctuation, and converting everything to the same case (lowercase, because our vocabulary is all in lowercase). So we'll want a more sophisticated way of converting text to words.

```

1 test(text_to_words("My name is Earl!") == ["my", "name", "is", "earl"])
2 test(text_to_words('"Well, I never!", said Alice.') ==
3      ["well", "i", "never", "said", "alice"])

```

There is a powerful `translate` method available for strings. The idea is that one sets up desired substitutions — for every character, we can give a corresponding replacement character. The `translate` method will apply these replacements throughout the whole string. So here we go:

```

1 def text_to_words(the_text):
2     """ return a list of words with all punctuation removed,
3     and all in lowercase.
4     """
5
6     my_substitutions = the_text.maketrans(
7         # If you find any of these
8         "ABCDEFGHIJKLMNOPQRSTUVWXYZ0123456789!\"#$%&()*+,-./:;<=>?@[^_`{|}~'\\" ,
9         # Replace them by these
10        "abcdefghijklmnopqrstuvwxyz")
11
12    # Translate the text now.
13    cleaned_text = the_text.translate(my_substitutions)
14    wds = cleaned_text.split()
15    return wds

```

The translation turns all uppercase characters into lowercase, and all punctuation characters and digits into spaces. Then, of course, `split` will get rid of the spaces as it breaks the text into a list of words.

The tests pass.

Now we're ready to read in our book:

```

1 def get_words_in_book(filename):
2     """ Read a book from filename, and return a list of its words. """
3     f = open(filename, "r")
4     content = f.read()
5     f.close()
6     wds = text_to_words(content)
7     return wds
8
9 book_words = get_words_in_book("alice_in_wonderland.txt")
10 print("There are {0} words in the book, the first 100 are\n{1}".
11       format(len(book_words), book_words[:100]))

```

Python prints the following (all on one line, we've cheated a bit for the textbook):

```

1  There are 27336 words in the book, the first 100 are
2  ['alice', 's', 'adventures', 'in', 'wonderland', 'lewis', 'carroll',
3   'chapter', 'i', 'down', 'the', 'rabbit', 'hole', 'alice', 'was',
4   'beginning', 'to', 'get', 'very', 'tired', 'of', 'sitting', 'by',
5   'her', 'sister', 'on', 'the', 'bank', 'and', 'of', 'having',
6   'nothing', 'to', 'do', 'once', 'or', 'twice', 'she', 'had',
7   'peeped', 'into', 'the', 'book', 'her', 'sister', 'was', 'reading',
8   'but', 'it', 'had', 'no', 'pictures', 'or', 'conversations', 'in',
9   'it', 'and', 'what', 'is', 'the', 'use', 'of', 'a', 'book',
10  'thought', 'alice', 'without', 'pictures', 'or', 'conversation',
11  'so', 'she', 'was', 'considering', 'in', 'her', 'own', 'mind',
12  'as', 'well', 'as', 'she', 'could', 'for', 'the', 'hot', 'day',
13  'made', 'her', 'feel', 'very', 'sleepy', 'and', 'stupid',
14  'whether', 'the', 'pleasure', 'of', 'making', 'a']

```

Well now we have all the pieces ready. Let us see what words in this book are not in the vocabulary:

```

1  >>> missing_words = find_unknown_words(bigger_vocab, book_words)

```

We wait a considerable time now, something like a minute, before Python finally works its way through this, and prints a list of 3398 words in the book that are not in the vocabulary. Mmm... This is not particularly

scaleable. For a vocabulary that is twenty times larger (you'll often find school dictionaries with 300 000 words, for example), and longer books, this is going to be slow. So let us make some timing measurements

while we think about how we can improve this in the next section.

```

1  import time
2
3  t0 = time.process_time()
4  missing_words = find_unknown_words(bigger_vocab, book_words)
5  t1 = time.process_time()
6  print("There are {0} unknown words.".format(len(missing_words)))
7  print("That took {0:.4f} seconds.".format(t1-t0))

```

We get the results and some timing that we can refer back to later:

```

1  There are 3398 unknown words.
2  That took 49.8014 seconds.

```

14.4. Binary Search

If you think about what we've just done, it is not how we work in real life. If you were given a vocabulary and asked to tell if some word was present, you'd probably start in the middle. You can do this because the

vocabulary is ordered — so you can probe some word in the middle, and immediately realize that your target was before (or perhaps after) the one you had probed. Applying this principle repeatedly leads us to a

very much better algorithm for searching in a list of items that are already ordered. (Note that if the items are not ordered, you have little choice other than to look through all of them. But, if we know the items are in order, we can improve our searching technique).

Lets start with some tests. Remember, the list needs to be sorted:

```
1 xs = [2,3,5,7,11,13,17,23,29,31,37,43,47,53]
2 test(search_binary(xs, 20) == -1)
3 test(search_binary(xs, 99) == -1)
4 test(search_binary(xs, 1) == -1)
5 for (i, v) in enumerate(xs):
6     test(search_binary(xs, v) == i)
```

Even our test cases are interesting this time: notice that we start with items not in the list and look at boundary conditions — in the middle of the list, less than all items in the list, bigger than the biggest.

Then we use a loop to use every list item as a target, and to confirm that our binary search returns the corresponding index of that item in the list.

It is useful to think about having a *region-of-interest* (ROI) within the list being searched. This ROI will be the portion of the list in which it is still possible that our target might be found. Our algorithm will start with the ROI set to all the items in the list. On the first probe in the middle of the ROI, there are three possible outcomes: either we find the target, or we learn that we can discard the top half

of the ROI, or we learn that we can discard the bottom half of the ROI. And we keep doing this repeatedly, until we find our target, or until we end up with no more items in our region of interest. We can code this as follows:

```

1  def search_binary(xs, target):
2      """ Find and return the index of key in sequence xs """
3      lb = 0
4      ub = len(xs)
5      while True:
6          if lb == ub:    # If region of interest (ROI) becomes empty
7              return -1
8
9          # Next probe should be in the middle of the ROI
10         mid_index = (lb + ub) // 2
11
12         # Fetch the item at that position
13         item_at_mid = xs[mid_index]
14
15         # print("ROI[{0}:{1}](size={2}), probed='{3}', target='{4}')"
16         #         .format(lb, ub, ub-lb, item_at_mid, target))
17
18         # How does the probed item compare to the target?
19         if item_at_mid == target:
20             return mid_index    # Found it!
21         if item_at_mid < target:
22             lb = mid_index + 1    # Use upper half of ROI next time
23         else:
24             ub = mid_index    # Use lower half of ROI next time

```

The region of interest is represented by two variables, a lower bound `lb` and an upper bound `ub`. It is important to be precise about what values these indexes have. We'll make `lb` hold the index of the first

item in the ROI, and make `ub` hold the index just *beyond* the last item of interest. So these semantics are similar to a Python slice semantics: the region of interest is exactly the slice `xs[lb:ub]`. (The algorithm never actually takes any array slices!)

With this code in place, our tests pass. Great. Now if we substitute a call to this search algorithm instead of calling the `search_linear` in `find_unknown_words`, can we improve our performance?

Let's do that, and

again run this test:

```

1  t0 = time.process_time()
2  missing_words = find_unknown_words(bigger_vocab, book_words)
3  t1 = time.process_time()
4  print("There are {0} unknown words.".format(len(missing_words)))
5  print("That took {0:.4f} seconds.".format(t1-t0))

```

What a spectacular difference! More than 200 times faster!

```

1  There are 3398 unknown words.
2  That took 0.2262 seconds.

```

Why is this binary search so much faster than the linear search? If we uncomment the print statement on lines 15 and 16, we'll get a trace of the probes done during a search. Let's go ahead, and try that:

```

1  >>> search_binary(bigger_vocab, "magic")
2  ROI[0:19469](size=19469), probed='known', target='magic'
3  ROI[9735:19469](size=9734), probed='retailer', target='magic'
4  ROI[9735:14602](size=4867), probed='overthrow', target='magic'
5  ROI[9735:12168](size=2433), probed='mission', target='magic'
6  ROI[9735:10951](size=1216), probed='magnificent', target='magic'
7  ROI[9735:10343](size=608), probed='liken', target='magic'
8  ROI[10040:10343](size=303), probed='looks', target='magic'
9  ROI[10192:10343](size=151), probed='lump', target='magic'
10 ROI[10268:10343](size=75), probed='machete', target='magic'
11 ROI[10306:10343](size=37), probed='mafia', target='magic'
12 ROI[10325:10343](size=18), probed='magnanimous', target='magic'
13 ROI[10325:10334](size=9), probed='magical', target='magic'
14 ROI[10325:10329](size=4), probed= maggot', target='magic'
15 ROI[10328:10329](size=1), probed='magic', target='magic'
16 10328

```

Here we see that finding the target word “magic” needed just 14 probes before it was found at index 10328. The important thing is that each probe halves (with some truncation) the remaining region of interest. By

contrast, the linear search would have needed 10329 probes to find the same target word.

The word *binary* means *two*. Binary search gets its name from the fact that each probe splits the list into two pieces and discards the one half from the region of interest.

The beauty of the algorithm is that we could double the size of the vocabulary, and it would only need one more probe! And after another doubling, just another one probe. So as the vocabulary gets bigger, this algorithm's performance becomes even more impressive.

Can we put a formula to this? If our list size is N , what is the biggest number of probes k we could need? The maths is a bit easier if we turn the question around: how big a list N could we deal with, given that we were only allowed to make k probes?

With 1 probe, we can only search a list of size 1. With two probes we could cope with lists up to size 3 - (test the middle item with the first probe, then test either the left or right sublist with the second probe). With one more probe, we could cope with 7 items (the middle item, and two sublists of size 3). With four probes, we can search 15 items, and 5 probes lets us search up to 31 items. So the general relationship is given by the formula

```
1 N = 2 ** k - 1
```

where k is the number of probes we're allowed to make, and N is the maximum size of the list that can be searched in that many probes. This function is *exponential* in k (because k occurs in the exponent part).

If we wanted to turn the formula around and solve for k in terms of N , we need to move the constant 1 to the other side, and take a log (base 2) on each side. (The log is the inverse of an exponent.) So the formula

for k in terms of N is now:

$$k = \lceil \log_2(N + 1) \rceil$$

The square-only-on-top brackets are called *ceiling brackets*: this means that you must round the number up to the next whole integer.

Let us try this on a calculator, or in Python, which is the mother of all calculators: suppose I have 1000 elements to be searched, what is the maximum number of probes I'll need? (There is a pesky +1 in the formula, so let us not forget to add it on...):

```
1 >>> from math import log
2 >>> log(1000 + 1, 2)
3 9.967226258835993
```

Telling us that we'll need 9.96 probes maximum, to search 1000 items is not quite what we want. We forgot to take the ceiling. The `ceil` function in the `math` module does exactly this. So more accurately, now:

```
1 >>> from math import log, ceil
2 >>> ceil(log(1000 + 1, 2))
3 10
4 >>> ceil(log(1000000 + 1, 2))
5 20
6 >>> ceil(log(1000000000 + 1, 2))
7 30
```

This tells us that searching 1000 items needs 10 probes. (Well technically, with 10 probes we can search exactly 1023 items, but the easy and useful stuff to remember here is that “1000 items needs 10 probes, a million needs 20 probes, and a billion items only needs 30 probes”).

You will rarely encounter algorithms that scale to large datasets as beautifully as binary search does!

14.5. Removing adjacent duplicates from a list

We often want to get the unique elements in a list, i.e. produce a new list in which each different element occurs just once. Consider our case of looking for words in Alice in Wonderland that are not in our vocabulary. We had a report that there are 3398 such words, but there are duplicates in that list. In fact, the word “alice” occurs 398 times in the book, and it is not in our vocabulary! How should we remove these duplicates?

A good approach is to sort the list, then remove all adjacent duplicates. Let us start with removing adjacent duplicates

```

1 test(remove_adjacent_dups([1,2,3,3,3,3,5,6,9,9]) == [1,2,3,5,6,9])
2 test(remove_adjacent_dups([]) == [])
3 test(remove_adjacent_dups(["a", "big", "big", "bite", "dog"]) ==
4         ["a", "big", "bite", "dog"])
```

The algorithm is easy and efficient. We simply have to remember the most recent item that was inserted into the result, and avoid inserting it again:

```

1 def remove_adjacent_dups(xs):
2     """ Return a new list in which all adjacent
3     duplicates from xs have been removed.
4     """
5     result = []
6     most_recent_elem = None
7     for e in xs:
8         if e != most_recent_elem:
9             result.append(e)
10            most_recent_elem = e
11
12     return result
```

The amount of work done in this algorithm is linear — each item in `xs` causes the loop to execute exactly once, and there are no nested loops. So doubling the number of elements in `xs` should cause this function to run twice as long: the relationship between the size of the list and the time to run will be graphed as a straight (linear) line.

Let us go back now to our analysis of Alice in Wonderland. Before checking the words in the book against the vocabulary, we’ll sort those words into order, and eliminate duplicates. So our new code looks like this:

```

1 all_words = get_words_in_book("alice_in_wonderland.txt")
2 all_words.sort()
3 book_words = remove_adjacent_dups(all_words)
4 print("There are {0} words in the book. Only {1} are unique.".
5       format(len(all_words), len(book_words)))
6 print("The first 100 words are\n{0}".
7       format(book_words[:100]))

```

Almost magically, we get the following output:

```

1 There are 27336 words in the book. Only 2570 are unique.
2 The first 100 words are
3 ['_i_', 'a', 'abide', 'able', 'about', 'above', 'absence', 'absurd',
4  'acceptance', 'accident', 'accidentally', 'account', 'accounting',
5  'accounts', 'accusation', 'accustomed', 'ache', 'across', 'act',
6  'actually', 'ada', 'added', 'adding', 'addressed', 'addressing',
7  'adjourn', 'adoption', 'advance', 'advantage', 'adventures',
8  'advice', 'advisable', 'advise', 'affair', 'affectionately',
9  'afford', 'afore', 'afraid', 'after', 'afterwards', 'again',
10 'against', 'age', 'ago', 'agony', 'agree', 'ah', 'ahem', 'air',
11 'airs', 'alarm', 'alarmed', 'alas', 'alice', 'alive', 'all',
12 'allow', 'almost', 'alone', 'along', 'aloud', 'already', 'also',
13 'altered', 'alternately', 'altogether', 'always', 'am', 'ambition',
14 'among', 'an', 'ancient', 'and', 'anger', 'angrily', 'angry',
15 'animal', 'animals', 'ann', 'annoy', 'annoyed', 'another',
16 'answer', 'answered', 'answers', 'antipathies', 'anxious',
17 'anxiously', 'any', 'anything', 'anywhere', 'appealed', 'appear',
18 'appearance', 'appeared', 'appearing', 'applause', 'apple',
19 'apples', 'arch']

```

Lewis Carroll was able to write a classic piece of literature using only 2570 different words!

14.6. Merging sorted lists

Suppose we have two sorted lists. Devise an algorithm to merge them together into a single sorted list.

A simple but inefficient algorithm could be to simply append the two lists together, and sort the result:

```

1 newlist = (xs + ys)
2 newlist.sort()

```

But this doesn't take advantage of the fact that the two lists are already sorted, and is going to have poor scalability and performance for very large lists.

Lets get some tests together first:

```

1 xs = [1,3,5,7,9,11,13,15,17,19]
2 ys = [4,8,12,16,20,24]
3 zs = xs+ys
4 zs.sort()
5 test(merge(xs, []) == xs)
6 test(merge([], ys) == ys)
7 test(merge([], []) == [])
8 test(merge(xs, ys) == zs)
9 test(merge([1,2,3], [3,4,5]) == [1,2,3,3,4,5])
10 test(merge(["a", "big", "cat"], ["big", "bite", "dog"]) ==
11         ["a", "big", "big", "bite", "cat", "dog"])

```

Here is our merge algorithm:

```

1 def merge(xs, ys):
2     """ merge sorted lists xs and ys. Return a sorted result """
3     result = []
4     xi = 0
5     yi = 0
6
7     while True:
8         if xi >= len(xs):           # If xs list is finished,
9             result.extend(ys[yi:]) # Add remaining items from ys
10            return result           # And we're done.
11
12        if yi >= len(ys):           # Same again, but swap roles
13            result.extend(xs[xi:])
14            return result
15
16        # Both lists still have items, copy smaller item to result.
17        if xs[xi] <= ys[yi]:
18            result.append(xs[xi])
19            xi += 1
20        else:
21            result.append(ys[yi])
22            yi += 1

```

The algorithm works as follows: we create a result list, and keep two indexes, one into each list (lines 3-5). On each iteration of the loop, whichever list item is smaller is copied to the result list, and that list's index is advanced. As soon as either index reaches the end of its list, we copy all the remaining items from the other list into the result, which we return.

14.7. Alice in Wonderland, again!

Underlying the algorithm for merging sorted lists is a deep pattern of computation that is widely reusable. The pattern essence is *“Run through the lists always processing the smallest remaining items from each, with these cases to consider:”*

- What should we do when either list has no more items?
- What should we do if the smallest items from each list are equal to each other?
- What should we do if the smallest item in the first list is smaller than the smallest one the second list?
- What should we do in the remaining case?

Lets assume we have two sorted lists. Exercise your algorithmic skills by adapting the merging algorithm pattern for each of these cases:

- Return only those items that are present in both lists.
- Return only those items that are present in the first list, but not in the second.
- Return only those items that are present in the second list, but not in the first.
- Return items that are present in either the first or the second list.
- Return items from the first list that are not eliminated by a matching element in the second list. In

this case, an item in the second list “knocks out” just one matching item in the first list. This operation is sometimes called *bagdiff*. For example `bagdiff([5,7,11,11,11,12,13], [7,8,11])` would return `[5,11,11,12,13]`

In the previous section we sorted the words from the book, and eliminated duplicates. Our vocabulary is also sorted. So third case above — find all items in the second list that are not in the first list, would be another way to implement `find_unknown_words`. Instead of searching for every word in the dictionary (either by linear or binary search), why not use a variant of the merge to return the words that occur in the book, but not in the vocabulary.

```

1  def find_unknowns_merge_pattern(vocab, wds):
2      """ Both the vocab and wds must be sorted. Return a new
3          list of words from wds that do not occur in vocab.
4          """
5
6      result = []
7      xi = 0
8      yi = 0
9
10     while True:
11         if xi >= len(vocab):
12             result.extend(wds[yi:])
13             return result
14
15         if yi >= len(wds):
16             return result
17
18         if vocab[xi] == wds[yi]: # Good, word exists in vocab
19             yi += 1
20
21         elif vocab[xi] < wds[yi]: # Move past this vocab word,
22             xi += 1
23
24         else: # Got word that is not in vocab
25             result.append(wds[yi])
26             yi += 1

```

Now we put it all together:

Even more stunning performance here:

```

1  There are 828 unknown words.
2  That took 0.0410 seconds.

```


Let's review what we've done. We started with a word-by-word linear lookup in the vocabulary that ran in about 50 seconds. We implemented a clever binary search, and got that down to 0.22 seconds, more than 200

times faster. But then we did something even better: we sorted the words from the book, eliminated duplicates, and used a merging pattern to find words from the book that were not in the dictionary. This was about five times faster than even the binary lookup algorithm. At the end of the chapter our algorithm is more than a 1000 times faster than our first attempt!

That is what we can call a good day at the office!

14.8. Eight Queens puzzle, part 1

As told by Wikipedia, “*The eight queens puzzle is the problem of placing eight chess queens on an 8x8 chessboard so that no two queens attack each other. Thus, a solution requires that no two queens share the same row, column, or diagonal.*”



Please try this yourself, and find a few more solutions by hand.

We’d like to write a program to find solutions to this puzzle. In fact, the puzzle generalizes to placing N queens on an $N \times N$ board, so we’re going to think about the general case, not just the 8x8 case. Perhaps we can find solutions for 12 queens on a 12x12 board, or 20 queens on a 20x20 board.

How do we approach a complex problem like this? A good starting point is to think about our *data structures* — how exactly do we plan to represent the state of the chessboard and its queens in our program? Once we have some handle on what our puzzle is going to look like in memory, we can begin to think about the functions and logic we’ll need to solve the puzzle, i.e. how do we put another queen onto the board

somewhere, and to check whether it clashes with any of the queens already on the board.

The steps of finding a good representation, and then finding a good algorithm to operate on the data cannot always be done independently of each other. As you think about the operations you require, you may want

to change or reorganize the data somewhat to make it easier to do the operations you need.

This relationship between algorithms and data was elegantly expressed in the title of a book *Algorithms + Data Structures = Programs*, written by one of the pioneers in Computer Science,

Niklaus Wirth, the inventor of Pascal.

Let's brainstorm some ideas about how a chessboard and queens could be represented in memory.

- A two dimensional matrix (a list of 8 lists, each containing 8 squares) is one possibility. At each square of the board would like to know whether it contains a queen or not — just two possible states for each square — so perhaps each element in the lists could be True or False, or, more simply, 0 or 1.

Our state for the solution above could then have this data representation:

```

1      bd1 = [[0,0,0,1,0,0,0,0],
2             [0,0,0,0,0,0,1,0],
3             [0,0,1,0,0,0,0,0],
4             [0,0,0,0,0,0,0,1],
5             [0,1,0,0,0,0,0,0],
6             [0,0,0,0,1,0,0,0],
7             [1,0,0,0,0,0,0,0],
8             [0,0,0,0,0,1,0,0]]

```

You should also be able to see how the empty board would be represented, and you should start to imagine what operations or changes you'd need to make to the data to place another queen somewhere on the board.

- Another idea might be to keep a list of coordinates of where the queens are. Using the notation in the illustration, for example, we could represent the state of that solution as:

```

1      bd2 = [ "a6", "b4", "c2", "d0", "e5", "f7", "g1", "h3" ]

```

- We could make other tweaks to this — perhaps each element in this list should rather be a tuple, with integer coordinates for both axes. And being good computer scientists, we'd probably start numbering each axis from 0 instead of at 1. Now our representation could be:

```
1      bd3 = [(0,6), (1,4), (2,2), (3,0), (4,5), (5,7), (6,1), (7,3)]
```

- Looking at this representation, we can't help but notice that the first coordinates are 0,1,2,3,4,5,6,7 and they correspond exactly to the index position of the pairs in the list. So we could discard them, and come up with this really compact alternative representation of the solution:

```
1      bd4 = [6, 4, 2, 0, 5, 7, 1, 3]
```

This will be what we'll use, let's see where that takes us.

Let us now take some grand insight into the problem. Do you think it is a coincidence that there are no repeated numbers in the solution? The solution [6,4,2,0,5,7,1,3] contains the numbers 0,1,2,3,4,5,6,7, but none are duplicated! Could other solutions contain duplicate numbers, or not?

A little thinking should convince you that there can never be duplicate numbers in a solution: the numbers represent the row on which the queen is placed, and because we are never permitted to put two queens in the same row, no solution will ever have duplicate row numbers in it.

Our key insight

In our representation, any solution to the N queens problem must therefore be a permutation of the numbers [0 .. N-1].

Note that not all permutations are solutions. For example, [0,1,2,3,4,5,6,7] has all queens on the same diagonal.

Wow, we seem to be making progress on this problem merely by thinking, rather than coding!

Our algorithm should start taking shape now. We can start with the list [0..N-1], generate various permutations of that list, and check each permutation to see if it has any clashes (queens that are on the same diagonal). If it has no clashes, it is a solution, and we can print it.

Let us be precise and clear on this issue: if we only use permutations of the rows, and we're using our compact representation, no queens can clash on either rows or columns, and we don't even have to concern

ourselves with those cases. So the only clashes we need to test for are clashes on the diagonals.

It sounds like a useful function will be one that can test if two queens share a diagonal. Each queen is on some (x,y) position. So does the queen at (5,2) share a diagonal with the one at (2,0)? Does (5,2) clash with (3,0)?


```

1 test(not share_diagonal(5,2,2,0))
2 test(share_diagonal(5,2,3,0))
3 test(share_diagonal(5,2,4,3))
4 test(share_diagonal(5,2,4,1))

```

A little geometry will help us here. A diagonal has a slope of either 1 or -1. The question we really want to ask is *is their distance between them the same in the x and the y direction?* If it is, they share a diagonal. Because diagonals can be to the left or right, it will make sense for this program to use the absolute distance in each direction:

```

1 def share_diagonal(x0, y0, x1, y1):
2     """ Is (x0, y0) on a shared diagonal with (x1, y1)? """
3     dy = abs(y1 - y0)      # Calc the absolute y distance
4     dx = abs(x1 - x0)      # Calc the absolute x distance
5     return dx == dy        # They clash if dx == dy

```

If you copy the code and run it, you'll be happy to learn that the tests pass!

Now let's consider how we construct a solution by hand. We'll put a queen somewhere in the first column, then place one in the second column, only if it does not clash with the one already on the board. And

then we'll put a third one on, checking it against the two queens already to its left. When we consider the queen on column 6, we'll need to check for clashes against those in all the columns to its left, i.e. in columns 0,1,2,3,4,5.

So the next building block is a function that, given a partially completed puzzle, can check whether the queen at column *c* clashes with any of the queens to its left, at columns 0,1,2,...*c*-1:

```

1 # Solutions cases that should not have any clashes
2 test(not col_clashes([6,4,2,0,5], 4))
3 test(not col_clashes([6,4,2,0,5,7,1,3], 7))
4
5 # More test cases that should mostly clash
6 test(col_clashes([0,1], 1))
7 test(col_clashes([5,6], 1))
8 test(col_clashes([6,5], 1))
9 test(col_clashes([0,6,4,3], 3))
10 test(col_clashes([5,0,7], 2))
11 test(not col_clashes([2,0,1,3], 1))
12 test(col_clashes([2,0,1,3], 2))

```

Here is our function that makes them all pass:

```

1 def col_clashes(bs, c):
2     """ Return True if the queen at column c clashes
3     with any queen to its left.
4     """
5     for i in range(c):      # Look at all columns to the left of c
6         if share_diagonal(i, bs[i], c, bs[c]):
7             return True
8
9     return False           # No clashes - col c has a safe placement.

```

Finally, we’re going to give our program one of our permutations — i.e. all queens placed somewhere, one on each row, one on each column. But does the permutation have any diagonal clashes?

```

1 test(not has_clashes([6,4,2,0,5,7,1,3])) # Solution from above
2 test(has_clashes([4,6,2,0,5,7,1,3]))    # Swap rows of first two
3 test(has_clashes([0,1,2,3]))           # Try small 4x4 board
4 test(not has_clashes([2,0,3,1]))       # Solution to 4x4 case

```

And the code to make the tests pass:

```

1 def has_clashes(the_board):
2     """ Determine whether we have any queens clashing on the diagonals.
3     We're assuming here that the_board is a permutation of column
4     numbers, so we're not explicitly checking row or column clashes.
5     """
6     for col in range(1, len(the_board)):
7         if col_clashes(the_board, col):
8             return True
9     return False

```

Summary of what we’ve done so far: we now have a powerful function called `has_clashes` that can tell if a configuration is a solution to the queens puzzle. Let’s get on now with generating lots of permutations and finding solutions!

14.9. Eight Queens puzzle, part 2

This is the fun, easy part. We could try to find all permutations of `[0, 1, 2, 3, 4, 5, 6, 7]` — that might be algorithmically challenging, and would be a *brute force* way of tackling the problem. We just try everything, and find all possible solutions.

Of course we know there are $N!$ permutations of N things, so we can get an early idea of how long it would take to search all of them for all solutions. Not too long at all, actually — $8!$ is only 40320 different

cases to check out. This is vastly better than starting with 64 places to put eight queens. If you do the sums for how many ways can you choose 8 of the 64 squares for your queens, the formula (called *N choose k*

where you're choosing $k=8$ squares of the available $N=64$) yields a whopping 4426165368, obtained from $(64! / (8! \times 56!))$.

So our earlier key insight — that we only need to consider permutations — has reduced what we call the *problem space* from about 4.4 billion cases to just 40320!

We're not even going to explore all those, however. When we introduced the random number module, we learned that it had a `shuffle` method that randomly permuted a list of items. So we're going to write a "random"

algorithm to find solutions to the N queens problem. We'll begin with the permutation `[0,1,2,3,4,5,6,7]` and we'll repeatedly shuffle the list, and test each to see if it works! Along the way we'll count how many attempts we need before we find each solution, and we'll find 10 solutions (we could hit the same solution more than once, because shuffle is random!):

```

1  def main():
2      import random
3      rng = random.Random()    # Instantiate a generator
4
5      bd = list(range(8))      # Generate the initial permutation
6      num_found = 0
7      tries = 0
8      while num_found < 10:
9          rng.shuffle(bd)
10         tries += 1
11         if not has_clashes(bd):
12             print("Found solution {0} in {1} tries.".format(bd, tries))
13             tries = 0
14             num_found += 1
15
16  main()
```

Almost magically, and at great speed, we get this:

```
1 Found solution [3, 6, 2, 7, 1, 4, 0, 5] in 693 tries.
2 Found solution [5, 7, 1, 3, 0, 6, 4, 2] in 82 tries.
3 Found solution [3, 0, 4, 7, 1, 6, 2, 5] in 747 tries.
4 Found solution [1, 6, 4, 7, 0, 3, 5, 2] in 428 tries.
5 Found solution [6, 1, 3, 0, 7, 4, 2, 5] in 376 tries.
6 Found solution [3, 0, 4, 7, 5, 2, 6, 1] in 204 tries.
7 Found solution [4, 1, 7, 0, 3, 6, 2, 5] in 98 tries.
8 Found solution [3, 5, 0, 4, 1, 7, 2, 6] in 64 tries.
9 Found solution [5, 1, 6, 0, 3, 7, 4, 2] in 177 tries.
10 Found solution [1, 6, 2, 5, 7, 4, 0, 3] in 478 tries.
```

Here is an interesting fact. On an 8x8 board, there are known to be 92 different solutions to this puzzle. We are randomly picking one of 40320 possible permutations of our representation. So our chances of picking a solution on each try are $92/40320$. Put another way, on average we'll need $40320/92$ tries — about 438.26 — before we stumble across a solution. The number of tries we printed looks like our experimental data agrees quite nicely with our theory!

Save this code for later.

In the chapter on PyGame we plan to write a module to draw the board with its queens, and integrate that module with this code.

14.10. Glossary

binary search

A famous algorithm that searches for a target in a sorted list. Each probe in the list allows us to discard half the remaining items, so the algorithm is very efficient.

linear

Relating to a straight line. Here, we talk about graphing how the time taken by an algorithm depends on the size of the data it is processing. Linear algorithms have straight-line graphs that can describe this relationship.

linear search

A search that probes each item in a list or sequence, from first, until it finds what it is looking for. It is used for searching for a target in unordered lists of items.

Merge algorithm

An efficient algorithm that merges two already sorted lists, to produce a sorted list result. The merge algorithm is really a pattern of

computation that can be adapted and reused for various other scenarios, such as finding words that are in a book, but not in a vocabulary.

probe

Each time we take a look when searching for an item is called a probe. In our chapter on [Iteration](#) we also played a guessing game where the computer tried to guess the user's secret number. Each of those tries would also be called a probe.

test-driven development (TDD)

A software development practice which arrives at a desired feature through a series of small, iterative steps motivated by automated tests which are *written first* that express increasing refinements of the desired feature. (see the Wikipedia article on [Test-driven development](#)¹⁵ for more information.)

14.11. Exercises

1. The section in this chapter called Alice in Wonderland, again started with the observation that the merge

algorithm uses a pattern that can be reused in other situations. Adapt the merge algorithm to write each of these functions, as was suggested there:

1. Return only those items that are present in both lists.
2. Return only those items that are present in the first list, but not in the second.
3. Return only those items that are present in the second list, but not in the first.
4. Return items that are present in either the first or the second list.
5. Return items from the first list that are not eliminated by a matching element in the second list. In this case, an item in the second list “knocks out” just one matching item in the first list. This operation is sometimes called *bagdiff*. For example `bagdiff([5,7,11,11,11,12,13], [7,8,11])` would return `[5,11,11,12,13]`

2. Modify the queens program to solve some boards of size 4, 12, and 16. What is the maximum size puzzle you

¹⁵http://en.wikipedia.org/wiki/Test_driven_development

can usually solve in under a minute?

3. Adapt the queens program so that we keep a list of solutions that have already printed, so that we don't

print the same solution more than once.

4. Chess boards are symmetric: if we have a solution to the queens problem, its mirror solution — either

flipping the board on the X or in the Y axis, is also a solution. And giving the board a 90 degree, 180 degree, or 270 degree rotation is also a solution. In some sense, solutions that are just mirror images or rotations of other solutions — in the same family — are less interesting than the unique “core cases”. Of the 92 solutions for the 8 queens problem, there are only 12 unique families if you take rotations and mirror images into account. Wikipedia has some fascinating stuff about this.

1. Write a function to mirror a solution in the Y axis,

2. Write a function to mirror a solution in the X axis,

3. Write a function to rotate a solution by 90 degrees anti-clockwise, and use this to provide 180 and 270 degree rotations too.

4. Write a function which is given a solution, and it generates the family of symmetries for that solution. For example, the symmetries of $[0, 4, 7, 5, 2, 6, 1, 3]$ are :

```
[[0,4,7,5,2,6,1,3],[7,1,3,0,6,4,2,5],
[4,6,1,5,2,0,3,7],[2,5,3,1,7,4,6,0],
[3,1,6,2,5,7,4,0],[0,6,4,7,1,3,5,2],
[7,3,0,2,5,1,6,4],[5,2,4,6,0,3,1,7]]
```

5. Now adapt the queens program so it won't list solutions that are in the same family. It only prints solutions from unique families.

5. Every week a computer scientist buys four lotto tickets. She always chooses the same prime numbers, with

the hope that if she ever hits the jackpot, she will be able to go onto TV and Facebook and tell everyone her secret. This will suddenly create widespread public interest in prime numbers, and will be the trigger event that ushers in a new age of enlightenment. She represents her weekly tickets in

Python as a list of lists:

```
my_tickets = [ [ 7, 17, 37, 19, 23, 43],  
               [ 7, 2, 13, 41, 31, 43],  
               [ 2, 5, 7, 11, 13, 17],  
               [13, 17, 37, 19, 23, 43] ]
```

Complete these exercises.

1. Each lotto draw takes six random balls, numbered from 1 to 49. Write a function to return a lotto draw.

2. Write a function that compares a single ticket and a draw, and returns the number of correct picks on that ticket:

```
test(lotto_match([42,4,7,11,1,13], [2,5,7,11,13,17]) == 3)
```

3. Write a function that takes a list of tickets and a draw, and returns a list telling how many picks were correct on each ticket:

```
test(lotto_matches([42,4,7,11,1,13], my_tickets) == [1,2,3,1])
```

4. Write a function that takes a list of integers, and returns the number of primes in the list:

```
test(primes_in([42, 4, 7, 11, 1, 13]) == 3)
```

5. Write a function to discover whether the computer scientist has missed any prime numbers in her selection of the four tickets. Return a list of all primes that she has missed:

```
test(prime_misses(my_tickets) == [3, 29, 47])
```

6. Write a function that repeatedly makes a new draw, and compares the draw to the four tickets.

1. Count how many draws are needed until one of the computer scientist's tickets has at least 3 correct picks. Try the experiment twenty times, and average out the number of draws needed.

2. How many draws are needed, on average, before she gets at least 4 picks correct?

3. How many draws are needed, on average, before she gets at least 5 correct? (Hint: this might take a while. It would be nice if you could print some dots, like a progress bar, to show when each of the 20 experiments has completed.)

Notice that we have difficulty constructing test cases here, because our random numbers are not deterministic. Automated testing only really works if you already know what the answer should be!

6. Read *Alice in Wonderland*. You can read the plain text version we have with this textbook, or if you

have e-book reader software on your PC, or a Kindle, iPhone, Android, etc. you'll be able to find a suitable version for your device at <http://www.gutenberg.org>. They also have html and pdf versions, with pictures, and thousands of other classic books!

Chapter 15: Classes and Objects — the Basics

15.1. Object-oriented programming

Python is an **object-oriented programming language**, which means that it provides features that support **object-oriented programming**¹⁶ (OOP).

Object-oriented programming has its roots in the 1960s, but it wasn't until the mid 1980s that it became the main **programming paradigm**¹⁷ used in the creation of new software. It was developed as a way to handle the rapidly increasing size and complexity of software systems, and to make it easier to modify these large and complex systems over time.

Up to now, most of the programs we have been writing use a **procedural programming**¹⁸ paradigm. In procedural programming the focus is on writing functions or *procedures* which operate on data. In object-oriented programming the focus is on the creation of **objects** which contain both data and functionality together. (We have seen turtle objects, string objects, and random number generators, to name a few places where we've already worked with objects.)

Usually, each object definition corresponds to some object or concept in the real world, and the functions that operate on that object correspond to the ways real-world objects interact.

15.2. User-defined compound data types

We've already seen classes like `str`, `int`, `float` and `Turtle`. We are now ready to create our own user-defined class: the `Point`.

Consider the concept of a mathematical point. In two dimensions, a point is two numbers (coordinates) that are treated collectively as a single object. Points are often written in parentheses with a comma separating the coordinates. For example, $(0, 0)$ represents the origin, and (x, y) represents the point x units to the right and y units up from the origin.

Some of the typical operations that one associates with points might be calculating the distance of a point from the origin, or from another point, or finding a midpoint of two points, or asking if a

¹⁶http://en.wikipedia.org/wiki/Object-oriented_programming

¹⁷http://en.wikipedia.org/wiki/Programming_paradigm

¹⁸http://en.wikipedia.org/wiki/Procedural_programming

point falls

within a given rectangle or circle. We'll shortly see how we can organize these together with the data.

A natural way to represent a point in Python is with two numeric values. The question, then, is how to group these two values into a compound object. The quick and dirty solution is to use a tuple, and for some applications that might be a good choice.

An alternative is to define a new **class**. This approach involves a bit more effort, but it has advantages that will be apparent soon. We'll want our points to each have an *x* and a *y* attribute, so our first class definition looks like this:

```

1 class Point:
2     """ Point class represents and manipulates x,y coords. """
3
4     def __init__(self):
5         """ Create a new point at the origin """
6         self.x = 0
7         self.y = 0

```

Class definitions can appear anywhere in a program, but they are usually near the beginning (after the `import` statements). Some programmers and languages prefer to put every class in a module of its own — we won't do that here. The syntax rules for a class definition are the same as for other compound statements. There is a header which begins with the keyword, `class`, followed by the name of the class, and ending with a colon. Indentation levels tell us where the class ends.

If the first line after the class header is a string, it becomes the docstring of the class, and will be recognized by various tools. (This is also the way docstrings work in functions.)

Every class should have a method with the special name `__init__`. This **initializer method** is automatically called whenever a new instance of `Point` is created. It gives the programmer the opportunity to set up the attributes required within the new instance by giving them their initial state/values. The `self` parameter (we could choose any other name, but `self` is the convention) is automatically set to reference the newly created object that needs to be initialized.

So let's use our new `Point` class now:

```

1 p = Point()           # Instantiate an object of type Point
2 q = Point()           # Make a second point
3
4 print(p.x, p.y, q.x, q.y) # Each point object has its own x and y

```

This program prints:

```
1 0 0 0 0
```

because during the initialization of the objects, we created two attributes called `x` and `y` for each, and gave them both the value 0.

This should look familiar — we’ve used classes before to create more than one object:

```
1 from turtle import Turtle
2
3 tess = Turtle()      # Instantiate objects of type Turtle
4 alex = Turtle()
```

The variables `p` and `q` are assigned references to two new `Point` objects. A function like `Turtle` or `Point` that creates a new object instance is called a **constructor**, and every class automatically provides a constructor function which is named the same as the class.

It may be helpful to think of a class as a *factory* for making objects. The class itself isn’t an instance of a point, but it contains the machinery to make point instances. Every time we call the constructor, we’re asking the factory to make us a new object. As the object comes off the production line, its initialization method is executed to get the object properly set up with its factory default settings.

The combined process of “make me a new object” and “get its settings initialized to the factory default settings” is called **instantiation**.

15.3. Attributes


Like real world objects, object instances have both attributes and methods.

We can modify the attributes in an instance using dot notation:

```
1 >>> p.x = 3
2 >>> p.y = 4
```

Both modules and instances create their own namespaces, and the syntax for accessing names contained in each, called **attributes**, is the same. In this case the attribute we are selecting is a data item from an instance.

The following state diagram shows the result of these assignments:



The variable `p` refers to a `Point` object, which contains two attributes. Each attribute refers to a number.

We can access the value of an attribute using the same syntax:

```

1 >>> print(p.y)
2 4
3 >>> x = p.x
4 >>> print(x)
5 3

```

The expression `p.x` means, “Go to the object `p` refers to and get the value of `x`”. In this case, we assign that value to a variable named `x`. There is no conflict between the variable `x` (in the global namespace here) and the attribute `x` (in the namespace belonging to the instance). The purpose of dot notation is to fully qualify which variable we are referring to unambiguously.

We can use dot notation as part of any expression, so the following statements are legal:

```

1 print("(x={0}, y={1})".format(p.x, p.y))
2 distance_squared_from_origin = p.x * p.x + p.y * p.y

```

The first line outputs `(x=3, y=4)`. The second line calculates the value 25.

15.4. Improving our initializer

To create a point at position (7, 6) currently needs three lines of code:

```

1 p = Point()
2 p.x = 7
3 p.y = 6

```

We can make our class constructor more general by placing extra parameters into the `__init__` method, as shown in this example:

```

1 class Point:
2     """ Point class represents and manipulates x,y coords. """
3
4     def __init__(self, x=0, y=0):
5         """ Create a new point at x, y """
6         self.x = x
7         self.y = y
8
9     # Other statements outside the class continue below here.

```

The `x` and `y` parameters here are both optional. If the caller does not supply arguments, they’ll get the default values of 0. Here is our improved class in action:

```

1 >>> p = Point(4, 2)
2 >>> q = Point(6, 3)
3 >>> r = Point()          # r represents the origin (0, 0)
4 >>> print(p.x, q.y, r.x)
5 4 3 0


```

Technically speaking ...

If we are really fussy, we would argue that the `__init__` method's docstring is inaccurate. `__init__` doesn't *create* the object (i.e. set aside memory for it), — it just initializes the object to its factory-default settings after its creation.

But tools like PyScripter understand that instantiation — creation and initialization — happen together, and they choose to display the *initializer's* docstring as the tooltip to guide the programmer that calls the class constructor.

So we're writing the docstring so that it makes the most sense when it pops up to help the programmer who is using our `Point` class:



```

1
2 class Point:
3     """ Point class represents and manipulates x,y coords. """
4
5     def __init__(self, x=0, y=0):
6         """ Create a new point at x, y """
7         self.x = x
8         self.y = y
9
10    # Other statements outside the class continue below here.
11
12    q = Point(

```

Tooltip text: `x=0, y=0`
Create a new point at x, y

15.5. Adding other methods to our class

The key advantage of using a class like `Point` rather than a simple tuple `(6, 7)` now becomes apparent. We can add methods to the `Point` class that are sensible operations for points, but which may not be

appropriate for other tuples like `(25, 12)` which might represent, say, a day and a month, e.g. Christmas day. So being able to calculate the distance from the origin is sensible for points, but not for (day, month) data. For (day, month) data, we'd like different operations, perhaps to find what day of the week it will fall on in 2020.

Creating a class like `Point` brings an exceptional amount of “organizational power” to our programs,

and to our thinking. We can group together the sensible operations, and the kinds of data they apply to, and each instance of the class can have its own state.

A **method** behaves like a function but it is invoked on a specific instance, e.g. `tess.right(90)`. Like a data attribute, methods are accessed using dot notation.

Let's add another method, `distance_from_origin`, to see better how methods work:

```
1 class Point:
2     """ Create a new Point, at coordinates x, y """
3
4     def __init__(self, x=0, y=0):
5         """ Create a new point at x, y """
6         self.x = x
7         self.y = y
8
9     def distance_from_origin(self):
10        """ Compute my distance from the origin """
11        return ((self.x ** 2) + (self.y ** 2)) ** 0.5
```

Let's create a few point instances, look at their attributes, and call our new method on them: (We must run our program first, to make our `Point` class available to the interpreter.)

```
1 >>> p = Point(3, 4)
2 >>> p.x
3 3
4 >>> p.y
5 4
6 >>> p.distance_from_origin()
7 5.0
8 >>> q = Point(5, 12)
9 >>> q.x
10 5
11 >>> q.y
12 12
13 >>> q.distance_from_origin()
14 13.0
15 >>> r = Point()
16 >>> r.x
17 0
18 >>> r.y
19 0
20 >>> r.distance_from_origin()
21 0.0
```

When defining a method, the first parameter refers to the instance being manipulated. As already noted, it is customary to name this parameter `self`.

Notice that the caller of `distance_from_origin` does not explicitly supply an argument to match the `self` parameter — this is done for us, behind our back.

15.6. Instances as arguments and parameters

We can pass an object as an argument in the usual way. We've already seen this in some of the turtle examples, where we passed the turtle to some function like `draw_bar` in the chapter titled Conditionals, so that the function could control and use whatever turtle instance we passed to it.

Be aware that our variable only holds a reference to an object, so passing `tess` into a function creates an alias: both the caller and the called function now have a reference, but there is only one turtle!

Here is a simple function involving our new `Point` objects:

```
1 def print_point(pt):
2     print("{0}, {1}".format(pt.x, pt.y))
```

`print_point` takes a point as an argument and formats the output in whichever way we choose. If we call `print_point(p)` with point `p` as defined previously, the output is `(3, 4)`.

15.7. Converting an instance to a string

Most object-oriented programmers probably would not do what we've just done in `print_point`. When we're working with classes and objects, a preferred alternative is to add a new method to the class. And we don't

like chatterbox methods that call `print`. A better approach is to have a method so that every instance can produce a string representation of itself. Let's initially call it `to_string`:

```
1 class Point:
2     # ...
3
4     def to_string(self):
5         return "{0}, {1}".format(self.x, self.y)
```

Now we can say:

```
1 >>> p = Point(3, 4)
2 >>> print(p.to_string())
3 (3, 4)
```

But don't we already have a `str` type converter that can turn our object into a string? Yes! And doesn't `print` automatically use this when printing things? Yes again! But these automatic mechanisms do not yet do exactly what we want:

```
1 >>> str(p)
2 '<__main__.Point object at 0x01F9AA10>'
3 >>> print(p)
4 '<__main__.Point object at 0x01F9AA10>'
```

Python has a clever trick up its sleeve to fix this. If we call our new method `__str__` instead of `to_string`, the Python interpreter will use our code whenever it needs to convert a `Point` to a string. Let's re-do this again, now:

```
1 class Point:
2     # ...
3
4     def __str__(self):    # All we have done is renamed the method
5         return "{0}, {1}".format(self.x, self.y)
```

and now things are looking great!

```
1 >>> str(p)    # Python now uses the __str__ method that we wrote.
2 (3, 4)
3 >>> print(p)
4 (3, 4)
```

15.8. Instances as return values

Functions and methods can return instances. For example, given two `Point` objects, find their midpoint. First we'll write this as a regular function:


```
1 def midpoint(p1, p2):
2     """ Return the midpoint of points p1 and p2 """
3     mx = (p1.x + p2.x)/2
4     my = (p1.y + p2.y)/2
5     return Point(mx, my)
```

The function creates and returns a new `Point` object:

```
1 >>> p = Point(3, 4)
2 >>> q = Point(5, 12)
3 >>> r = midpoint(p, q)
4 >>> r
5 (4.0, 8.0)
```

Now let us do this as a method instead. Suppose we have a point object, and wish to find the midpoint halfway between it and some other target point:

```
1 class Point:
2     # ...
3
4     def halfway(self, target):
5         """ Return the halfway point between myself and the target """
6         mx = (self.x + target.x)/2
7         my = (self.y + target.y)/2
8         return Point(mx, my)
```

This method is identical to the function, aside from some renaming. It's usage might be like this:

```
1 >>> p = Point(3, 4)
2 >>> q = Point(5, 12)
3 >>> r = p.halfway(q)
4 >>> r
5 (4.0, 8.0)
```

While this example assigns each point to a variable, this need not be done. Just as function calls are composable, method calls and object instantiation are also composable, leading to this alternative that uses no variables:

```

1 >>> print(Point(3, 4).halfway(Point(5, 12)))
2 (4.0, 8.0)

```

15.9. A change of perspective

The original syntax for a function call, `print_time(current_time)`, suggests that the function is the active agent. It says something like, “*Hey, print_time! Here’s an object for you to print.*”

In object-oriented programming, the objects are considered the active agents. An invocation like `current_time.print_time()` says “*Hey current_time! Please print yourself!*”

In our early introduction to turtles, we used an object-oriented style, so that we said `tess.forward(100)`, which asks the turtle to move itself forward by the given number of steps.

This change in perspective might be more polite, but it may not initially be obvious that it is useful. But sometimes shifting responsibility from the functions onto the objects makes it possible to write more versatile functions, and makes it easier to maintain and reuse code.

The most important advantage of the object-oriented style is that it fits our mental chunking and real-life experience more accurately. In real life our `cook` method is part of our microwave oven — we don’t

have a `cook` function sitting in the corner of the kitchen, into which we pass the microwave! Similarly, we use the cellphone’s own methods to send an sms, or to change its state to silent. The functionality of

real-world objects tends to be tightly bound up inside the objects themselves. OOP allows us to accurately mirror this when we organize our programs.

15.10. Objects can have state

Objects are most useful when we also need to keep some state that is updated from time to time. Consider a turtle object. Its state consists of things like its position, its heading, its color, and its shape. A

method like `left(90)` updates the turtle’s heading, `forward` changes its position, and so on.

For a bank account object, a main component of the state would be the current balance, and perhaps a log of all transactions. The methods would allow us to query the current balance, deposit new funds, or make

a payment. Making a payment would include an amount, and a description, so that this could be added to the transaction log. We’d also want a method to show the transaction log.

15.11. Glossary

attribute

One of the named data items that makes up an instance.

class

A user-defined compound type. A class can also be thought of as a template for the objects that are instances of it. (The iPhone is a class. By December 2010, estimates are that 50 million instances had been sold!)

constructor

Every class has a “factory”, called by the same name as the class, for making new instances. If the class has an *initializer method*, this method is used to get the attributes (i.e. the state) of the new object properly set up.

initializer method

A special method in Python (called `__init__`) that is invoked automatically to set a newly created object’s attributes to their initial (factory-default) state.

instance

An object whose type is of some class. Instance and object are used interchangeably.

instantiate

To create an instance of a class, and to run its initializer.

method

A function that is defined inside a class definition and is invoked on instances of that class.

object

A compound data type that is often used to model a thing or concept in the real world. It bundles together the data and the operations that are relevant for that kind of data. Instance and object are used interchangeably.

object-oriented programming

A powerful style of programming in which data and the operations that manipulate it are organized into objects.

object-oriented language

A language that provides features, such as user-defined classes and inheritance, that facilitate object-oriented programming.

15.12. Exercises

1. Rewrite the `distance` function from the chapter titled *Fruitful functions* so that it takes two `Point`s as parameters instead of four numbers.

2. Add a method `reflect_x` to `Point` which returns a new `Point`, one which is the reflection of the point

about the x-axis. For example, `Point(3, 5).reflect_x()` is `(3, -5)`

3. Add a method `slope_from_origin` which returns the slope of the line joining the origin to the point. For

example:

```
1 >>> Point(4, 10).slope_from_origin()
2 2.5
```

What cases will cause this method to fail?

4. The equation of a straight line is “ $y = ax + b$ ”, (or perhaps “ $y = mx + c$ ”). The coefficients a and b completely describe the line. Write a method in the `Point` class so that if a point instance is given another point, it will compute the equation of the straight line joining the two points. It must return the two coefficients as a tuple of two values. For example, :

```
1 >>> print(Point(4, 11).get_line_to(Point(6, 15)))
2 >>> (2, 3)
```

This tells us that the equation of the line joining the two points is “ $y = 2x + 3$ ”. When will this method fail?

5. Given four points that fall on the circumference of a circle, find the midpoint of the circle. When will

this function fail?

Hint: You *must* know how to solve the geometry problem *before* you think of going anywhere near programming. You cannot program a solution to a problem if you don’t understand what you want the computer to do!

6. Create a new class, `SMS_store`. The class will instantiate `SMS_store` objects, similar to an inbox or

outbox on a cellphone:

```
1 my_inbox = SMS_store()
```

This store can hold multiple SMS messages (i.e. its internal state will just be a list of messages). Each message will be represented as a tuple:

```
1 (has_been_viewed, from_number, time_arrived, text_of_SMS)
```

The inbox object should provide these methods:

```
1 my_inbox.add_new_arrival(from_number, time_arrived, text_of_SMS)
2     # Makes new SMS tuple, inserts it after other messages
3     # in the store. When creating this message, its
4     # has_been_viewed status is set False.
5
6 my_inbox.message_count()
7     # Returns the number of sms messages in my_inbox
8
9 my_inbox.get_unread_indexes()
10    # Returns list of indexes of all not-yet-viewed SMS messages
11
12 my_inbox.get_message(i)
13    # Return (from_number, time_arrived, text_of_sms) for message[i]
14    # Also change its state to "has been viewed".
15    # If there is no message at position i, return None
16
17 my_inbox.delete(i)      # Delete the message at index i
18 my_inbox.clear()       # Delete all messages from inbox
```

Write the class, create a message store object, write tests for these methods, and implement the methods.

Chapter 16: Classes and Objects — Digging a little deeper

16.1. Rectangles

Let's say that we want a class to represent a rectangle which is located somewhere in the XY plane. The question is, what information do we have to provide in order to specify such a rectangle? To keep things simple, assume that the rectangle is oriented either vertically or horizontally, never at an angle.

There are a few possibilities: we could specify the center of the rectangle (two coordinates) and its size (width and height); or we could specify one of the corners and the size; or we could specify two opposing corners. A conventional choice is to specify the upper-left corner of the rectangle, and the size.

Again, we'll define a new class, and provide it with an initializer and a string converter method:

```
1 class Rectangle:
2     """ A class to manufacture rectangle objects """
3
4     def __init__(self, posn, w, h):
5         """ Initialize rectangle at posn, with width w, height h """
6         self.corner = posn
7         self.width = w
8         self.height = h
9
10    def __str__(self):
11        return "{0}, {1}, {2}"
12            .format(self.corner, self.width, self.height)
13
14    box = Rectangle(Point(0, 0), 100, 200)
15    bomb = Rectangle(Point(100, 80), 5, 10)    # In my video game
16    print("box: ", box)
17    print("bomb: ", bomb)
```

To specify the upper-left corner, we have embedded a Point object (as we used it in the previous chapter) within our new Rectangle object! We create two new Rectangle objects, and then print them producing:


```

1 box: ((0, 0), 100, 200)
2 bomb: ((100, 80), 5, 10)

```

The dot operator composes. The expression `box.corner.x` means, “Go to the object that `box` refers to and select its attribute named `corner`, then go to that object and select its attribute named `x`”.

The figure shows the state of this object:



16.2. Objects are mutable

We can change the state of an object by making an assignment to one of its attributes. For example, to grow the size of a rectangle without changing its position, we could modify the values of `width` and `height`:

```

1 box.width += 50
2 box.height += 100

```

Of course, we’d probably like to provide a method to encapsulate this inside the class. We will also provide another method to move the position of the rectangle elsewhere:

```

1 class Rectangle:
2     # ...
3
4     def grow(self, delta_width, delta_height):
5         """ Grow (or shrink) this object by the deltas """
6         self.width += delta_width
7         self.height += delta_height
8
9     def move(self, dx, dy):

```

```
10         """ Move this object by the deltas """
11         self.corner.x += dx
12         self.corner.y += dy
```

Let us try this:

```
1 >>> r = Rectangle(Point(10,5), 100, 50)
2 >>> print(r)
3 ((10, 5), 100, 50)
4 >>> r.grow(25, -10)
5 >>> print(r)
6 ((10, 5), 125, 40)
7 >>> r.move(-10, 10)
8 print(r)
9 ((0, 15), 125, 40)
```

16.3. Sameness

The meaning of the word “same” seems perfectly clear until we give it some thought, and then we realize there is more to it than we initially expected.

For example, if we say, “Alice and Bob have the same car”, we mean that her car and his are the same make and model, but that they are two different cars. If we say, “Alice and Bob have the same mother”, we mean that her mother and his are the same person.

When we talk about objects, there is a similar ambiguity. For example, if two `Points` are the same, does that mean they contain the same data (coordinates) or that they are actually the same object?

We’ve already seen the `is` operator in the chapter on lists, where we talked about aliases: it allows us to find out if two references refer to the same object:

```
1 >>> p1 = Point(3, 4)
2 >>> p2 = Point(3, 4)
3 >>> p1 is p2
4 False
```

Even though `p1` and `p2` contain the same coordinates, they are not the same object. If we assign `p1` to `p3`, then the two variables are aliases of the same object:


```

1 >>> p3 = p1
2 >>> p1 is p3
3 True

```

This type of equality is called **shallow equality** because it compares only the references, not the contents of the objects.

To compare the contents of the objects — **deep equality** — we can write a function called `same_coordinates`:

```

1 def same_coordinates(p1, p2):
2     return (p1.x == p2.x) and (p1.y == p2.y)

```

Now if we create two different objects that contain the same data, we can use `same_point` to find out if they represent points with the same coordinates.

```

1 >>> p1 = Point(3, 4)
2 >>> p2 = Point(3, 4)
3 >>> same_coordinates(p1, p2)
4 True

```

Of course, if the two variables refer to the same object, they have both shallow and deep equality.

Beware of ==

“When I use a word,” Humpty Dumpty said, in a rather scornful tone, “it means just what I choose it to mean — neither more nor less.” *Alice in Wonderland*

Python has a powerful feature that allows a designer of a class to decide what an operation like `==` or `<` should mean. (We’ve just shown how we can control how our own objects are converted to strings, so we’ve already made a start!) We’ll cover more detail later. But sometimes the implementors will attach shallow equality semantics, and sometimes deep equality, as shown in this little experiment:

```

1 p = Point(4, 2)
2 s = Point(4, 2)
3 print("== on Points returns", p == s)
4 # By default, == on Point objects does a shallow equality test
5
6 a = [2,3]
7 b = [2,3]
8 print("== on lists returns", a == b)
9 # But by default, == does a deep equality test on lists

```

This outputs:

```
1 == on Points returns False
2 == on lists returns True
```

So we conclude that even though the two lists (or tuples, etc.) are distinct objects with different memory addresses, for lists the `==` operator tests for deep equality, while in the case of points it makes a shallow test.

16.4. Copying

Aliasing can make a program difficult to read because changes made in one place might have unexpected effects in another place. It is hard to keep track of all the variables that might refer to a given object.

Copying an object is often an alternative to aliasing. The `copy` module contains a function called `copy` that can duplicate any object:


```
1 >>> import copy
2 >>> p1 = Point(3, 4)
3 >>> p2 = copy.copy(p1)
4 >>> p1 is p2
5 False
6 >>> same_coordinates(p1, p2)
7 True
```

Once we import the `copy` module, we can use the `copy` function to make a new `Point`. `p1` and `p2` are not the same point, but they contain the same data.

To copy a simple object like a `Point`, which doesn't contain any embedded objects, `copy` is sufficient. This is called **shallow copying**.

For something like a `Rectangle`, which contains a reference to a `Point`, `copy` doesn't do quite the right thing. It copies the reference to the `Point` object, so both the old `Rectangle` and the new one refer to a single `Point`.

If we create a box, `b1`, in the usual way and then make a copy, `b2`, using `copy`, the resulting state diagram looks like this:



This is almost certainly not what we want. In this case, invoking `grow` on one of the `Rectangle` objects would not affect the other, but invoking `move` on either would affect both! This behavior is confusing

and error-prone. The shallow copy has created an alias to the `Point` that represents the corner.

Fortunately, the `copy` module contains a function named `deepcopy` that copies not only the object but also any embedded objects. It won't be surprising to learn that this operation is called a **deep copy**.

```
1 >>> b2 = copy.deepcopy(b1)
```

Now `b1` and `b2` are completely separate objects.

16.5. Glossary

deep copy

To copy the contents of an object as well as any embedded objects, and any objects embedded in them, and so on; implemented by the `deepcopy` function in the `copy` module.

deep equality

Equality of values, or two references that point to objects that have the same value.

shallow copy

To copy the contents of an object, including any references to embedded objects; implemented by the `copy` function in the `copy` module.

shallow equality

Equality of references, or two references that point to the same object.

16.6. Exercises

1. Add a method `area` to the `Rectangle` class that returns the area of any instance:

```
1 r = Rectangle(Point(0, 0), 10, 5)
2 test(r.area() == 50)
```

2. Write a `perimeter` method in the `Rectangle` class so that we can find the perimeter of any rectangle instance:

```
1 r = Rectangle(Point(0, 0), 10, 5)
2 test(r.perimeter() == 30)
```

3. Write a `flip` method in the `Rectangle` class that swaps the width and the height of any rectangle instance:

```
1 r = Rectangle(Point(100, 50), 10, 5)
2 test(r.width == 10 and r.height == 5)
3 r.flip()
4 test(r.width == 5 and r.height == 10)
```

4. Write a new method in the `Rectangle` class to test if a `Point` falls within the rectangle. For this exercise, assume that a rectangle at (0,0) with width 10 and height 5 has *open* upper bounds on the width and height, i.e. it stretches in the x direction from [0 to 10), where 0 is included but 10 is excluded, and from [0 to 5) in the y direction. So it does not contain the point (10,2). These tests should pass:

```
1 r = Rectangle(Point(0, 0), 10, 5)
2 test(r.contains(Point(0, 0)))
3 test(r.contains(Point(3, 3)))
4 test(not r.contains(Point(3, 7)))
5 test(not r.contains(Point(3, 5)))
6 test(r.contains(Point(3, 4.99999)))
7 test(not r.contains(Point(-3, -3)))
```

5. In games, we often put a rectangular “bounding box” around our sprites. (A sprite is an object that can

move about in the game, as we will see shortly.) We can then do *collision detection* between, say, bombs and spaceships, by comparing whether their rectangles overlap anywhere.

Write a function to determine whether two rectangles collide. *Hint: this might be quite a tough exercise! Think carefully about all the cases before you code.*

Chapter 17: PyGame


PyGame is a package that is not part of the standard Python distribution, so if you do not already have it installed (i.e. `import pygame` fails), download and install a suitable version from <http://pygame.org/download.shtml>. These notes are based on PyGame 1.9.1, the most recent version at the time of writing.

PyGame comes with a substantial set of tutorials, examples, and help, so there is ample opportunity to stretch yourself on the code. You may need to look around a bit to find these resources, though: if you've

installed PyGame on a Windows machine, for example, they'll end up in a folder like `C:\Python31\Lib\site-packages\pygame\` where you will find directories for *docs* and *examples*.

17.1. The game loop

The structure of the games we'll consider always follows this fixed pattern:




In every game, in the *setup* section we'll create a window, load and prepare some content, and then enter the **game loop**. The game loop continuously does four main things:

- it **polls** for events — i.e. asks the system whether events have occurred — and responds appropriately,
- it updates whatever internal data structures or objects need changing,
- it draws the current state of the game into a (non-visible) surface,
- it puts the just-drawn surface on display.

```
1  import pygame
2
3  def main():
4      """ Set up the game and run the main game loop """
5      pygame.init()      # Prepare the pygame module for use
6      surface_sz = 480    # Desired physical surface size, in pixels.
7
8      # Create surface of (width, height), and its window.
9      main_surface = pygame.display.set_mode((surface_sz, surface_sz))
10
11     # Set up some data to describe a small rectangle and its color
12     small_rect = (300, 200, 150, 90)
13     some_color = (255, 0, 0)      # A color is a mix of (Red, Green, Blue)
14
15     while True:
16         ev = pygame.event.poll()    # Look for any event
17         if ev.type == pygame.QUIT: # Window close button clicked?
18             break                    # ... leave game loop
19
20         # Update your game objects and data structures here...
21
22         # We draw everything from scratch on each frame.
23         # So first fill everything with the background color
24         main_surface.fill((0, 200, 255))
25
26         # Overpaint a smaller rectangle on the main surface
27         main_surface.fill(some_color, small_rect)
28
29         # Now the surface is ready, tell pygame to display it!
30         pygame.display.flip()
31
32     pygame.quit()      # Once we leave the loop, close the window.
33
34 main()
```

This program pops up a window which stays there until we close it:



PyGame does all its drawing onto rectangular *surfaces*. After initializing PyGame at line 5, we create a window holding our main surface. The main loop of the game extends from line 15 to 30, with the following key bits of logic:

- First (line 16) we poll to fetch the next event that might be ready for us. This step will always be followed by some conditional statements that will determine whether any event that we're interested in has happened. Polling for the event consumes it, as far as PyGame is concerned, so we only get one chance to fetch and use each event. On line 17 we test whether the type of the event is the predefined constant called `pygame.QUIT`. This is the event that we'll see when the user clicks the close button on the PyGame window. In response to this event, we leave the loop.
- Once we've left the loop, the code at line 32 closes window, and we'll return from function `main`. Your program could go on to do other things, or reinitialize pygame and create another window, but it will usually just end too.
- There are different kinds of events — key presses, mouse motion,

mouse clicks, joystick movement, and so on. It is usual that we test and handle all these cases with new code squeezed in before line 19. The general idea is “handle events first, then worry about the other stuff”.

- At line 20 we’d update objects or data — for example, if we wanted to vary the color, position, or size of the rectangle we’re about to draw, we’d re-assign `some_color`, and `small_rect` here.
- A modern way to write games (now that we have fast computers and fast graphics cards) is to redraw everything from scratch on every iteration of the game loop. So the first thing we do at line 24 is fill the entire surface with a background color. The `fill` method of a surface takes two arguments — the color to use for filling, and the rectangle to be filled. But the second argument is optional, and if it is left out the entire surface is filled.
- In line 27 we fill a second rectangle, this time using `some_color`.

The placement and size of the rectangle are given by the tuple `small_rect`, a 4-element tuple (`x`, `y`, `width`, `height`).

- It is important to understand that the origin of the PyGame’s surface is at the top left corner (unlike the turtle module that puts its origin in the middle of the screen). So, if you wanted the rectangle closer to the top of the window, you need to make its `y` coordinate smaller.
- If your graphics display hardware tries to read from memory at the same time as the program is writing to that memory, they will interfere with each other, causing video noise and flicker. To get around this, PyGame keeps two buffers in the main surface — the *back buffer* that the program draws to, while the *front buffer* is being shown to the user. Each time the program has fully prepared its back buffer, it flips the back/front role of the two buffers. So the drawing on lines 24 and 27 does not change what is seen on the screen until we `flip` the buffers, on line 30.

17.2. Displaying images and text

To draw an image on the main surface, we load the image, say a beach ball, into its own new surface. The main surface has a `blit` method that copies pixels from the beach ball surface into its own surface. When we call `blit`, we can specify where the beach ball should be placed on the main surface. The term **blit** is widely used in computer graphics, and means *to make a fast copy of pixels from one area of memory to another*.

So in the setup section, before we enter the game loop, we'd load the image, like this:

```
1 ball = pygame.image.load("ball.png")
```

and after line 28 in the program above, we'd add this code to display our image at position (100,120):

```
1 main_surface.blit(ball, (50, 70))
```

To display text, we need do do three things. Before we enter the game loop, we instantiate a font object:

```
1 # Instantiate 16 point Courier font to draw text.
2 my_font = pygame.font.SysFont("Courier", 16)
```

and after line 28, again, we use the font's render method to create a new surface containing the pixels of the drawn text, and then, as in the case for images, we blit our new surface onto the main surface. Notice

that render takes two extra parameters — the second tells it whether to carefully smooth edges of the text while drawing (this process is called *anti-aliasing*), and the second is the color that we want the text to be. Here we've used (0,0,0) which is black:

```
1 the_text = my_font.render("Hello, world!", True, (0,0,0))
2 main_surface.blit(the_text, (10, 10))
```

We'll demonstrate these two new features by counting the frames — the iterations of the game loop — and keeping some timing information. On each frame, we'll display the frame count, and the frame rate. We will

only update the frame rate after every 500 frames, when we'll look at the timing interval and can do the calculations.

First download an image of a beach ball. You can find one at https://learnpythontherightway.com/_downloads/ball.png. Upload it to your repl by using the "Upload file" menu. Now you can run the following code.


```
1  import pygame
2  import time
3
4  def main():
5
6      pygame.init()      # Prepare the PyGame module for use
7      main_surface = pygame.display.set_mode((480, 240))
8
9      # Load an image to draw. Substitute your own.
10     # PyGame handles gif, jpg, png, etc. image types.
11     ball = pygame.image.load("ball.png")
12
13     # Create a font for rendering text
14     my_font = pygame.font.SysFont("Courier", 16)
15
16     frame_count = 0
17     frame_rate = 0
18     t0 = time.process_time()
19
20     while True:
21
22         # Look for an event from keyboard, mouse, joystick, etc.
23         ev = pygame.event.poll()
24         if ev.type == pygame.QUIT:      # Window close button clicked?
25             break                        # Leave game loop
26
27         # Do other bits of logic for the game here
28         frame_count += 1
29         if frame_count % 500 == 0:
30             t1 = time.process_time()
31             frame_rate = 500 / (t1-t0)
32             t0 = t1
33
34         # Completely redraw the surface, starting with background
35         main_surface.fill((0, 200, 255))
36
37         # Put a red rectangle somewhere on the surface
38         main_surface.fill((255,0,0), (300, 100, 150, 90))
39
40         # Copy our image to the surface, at this (x,y) posn
41         main_surface.blit(ball, (50, 70))
42
43         # Make a new surface with an image of the text
```

```

44     the_text = my_font.render("Frame = {0}, rate = {1:.2f} fps"
45                               .format(frame_count, frame_rate), True, (0,0,0))
46     # Copy the text surface to the main surface
47     main_surface.blit(the_text, (10, 10))
48
49     # Now that everything is drawn, put it on display!
50     pygame.display.flip()
51
52     pygame.quit()
53
54
55 main()

```

The frame rate is close to ridiculous — a lot faster than one’s eye can process frames. (Commercial video games usually plan their action for 60 frames per second (fps).) Of course, our rate will drop once we start doing something a little more strenuous inside our game loop.



17.3. Drawing a board for the N queens puzzle

We previously solved our N queens puzzle. For the 8x8 board, one of the solutions was the list `[6,4,2,0,5,7,1,3]`. Let’s use that solution as testdata, and now use PyGame to draw that chessboard with its queens.

We'll create a new module for the drawing code, called `draw_queens.py`. When we have our test case(s) working, we can go back to our solver, import this new module, and add a call to our new function to draw a board each time a solution is discovered.

We begin with a background of black and red squares for the board. Perhaps we could create an image that we could load and draw, but that approach would need different background images for different size boards. Just drawing our own red and black rectangles of the appropriate size sounds like much more fun!

```

1  def draw_board(the_board):
2      """ Draw a chess board with queens, from the_board. """
3
4      pygame.init()
5      colors = [(255,0,0), (0,0,0)]    # Set up colors [red, black]
6
7      n = len(the_board)               # This is an NxN chess board.
8      surface_sz = 480                 # Proposed physical surface size. \
9
10     sq_sz = surface_sz // n          # sq_sz is length of a square.
11     surface_sz = n * sq_sz           # Adjust to exactly fit n squares.
12
13     # Create the surface of (width, height), and its window.
14     surface = pygame.display.set_mode((surface_sz, surface_sz))

```

Here we precompute `sq_sz`, the integer size that each square will be, so that we can fit the squares nicely into the available window. So if we'd like the board to be 480x480, and we're drawing an 8x8 chessboard,

then each square will need to have a size of 60 units. But we notice that a 7x7 board cannot fit nicely into 480 — we're going to get some ugly border that our squares don't fill exactly. So we recompute the

surface size to exactly fit our squares before we create the window.

Now let's draw the squares, in the game loop. We'll need a nested loop: the outer loop will run over the rows of the chessboard, the inner loop over the columns:


```

1  # Draw a fresh background (a blank chess board)
2  for row in range(n):          # Draw each row of the board.
3      c_indx = row % 2          # Change starting color on each row
4      for col in range(n):      # Run through cols drawing squares
5          the_square = (col*sq_sz, row*sq_sz, sq_sz, sq_sz)
6          surface.fill(colors[c_indx], the_square)
7          # now flip the color index for the next square
8          c_indx = (c_indx + 1) % 2

```

There are two important ideas in this code: firstly, we compute the rectangle to be filled from the row and col loop variables, multiplying them by the size of the square to get their position. And, of course, each square is a fixed width and height. So `the_square` represents the rectangle to be filled on the current iteration of the loop. The second idea is that we have to alternate colors on every square. In the earlier setup code we created a list containing two colors, here we manipulate `c_indx` (which will always either have the value 0 or 1) to start each row on a color that is different from the previous row's starting color, and to switch colors each time a square is filled.

This (together with the other fragments not shown to flip the surface onto the display) leads to the pleasing backgrounds like this, for different size boards:



Now, on to drawing the queens! Recall that our solution `[6,4,2,0,5,7,1,3]` means that in column 0 of the board we want a queen at row 6, at column 1 we want a queen at row 4, and so on. So we need a loop running over each queen:


```

1  for (col, row) in enumerate(the_board):
2      # draw a queen at col, row...

```

In this chapter we already have a beach ball image, so we'll use that for our queens. In the setup code before our game loop, we load the ball image (as we did before), and in the body of the loop, we add the line:

```
1 surface.blit(ball, (col * sq_sz, row * sq_sz))
```



We're getting there, but those queens need to be centred in their squares! Our problem arises from the fact that both the ball and the rectangle have their upper left corner as their reference points. If we're going to centre this ball in the square, we need to give it an extra offset in both the x and y direction. (Since the ball is round and the square is square, the offset in the two directions will be the same, so we'll just compute a single offset value, and use it in both directions.)

The offset we need is half the (size of the square less the size of the ball). So we'll precompute this

in the game's setup section, after we've loaded the ball and determined the square size:

```
1 ball_offset = (sq_sz - ball.get_width()) // 2
```

Now we touch up the drawing code for the ball and we're done:

```
1 surface.blit(ball, (col * sq_sz + ball_offset, row * q_sz + ball_offset))
```

We might just want to think about what would happen if the ball was bigger than the square. In that case, `ball_offset` would become negative. So it would still be centered in the square - it would just spill over the boundaries, or perhaps obscure the square entirely!

Here is the complete program:

```
1 import pygame
2
3 def draw_board(the_board):
4     """ Draw a chess board with queens, as determined by the the_board. """
5
6     pygame.init()
7     colors = [(255,0,0), (0,0,0)]    # Set up colors [red, black]
8
9     n = len(the_board)               # This is an NxN chess board.
10    surface_sz = 480                  # Proposed physical surface size. \
11
12    sq_sz = surface_sz // n           # sq_sz is length of a square.
13    surface_sz = n * sq_sz            # Adjust to exactly fit n squares.
14
15    # Create the surface of (width, height), and its window.
16    surface = pygame.display.set_mode((surface_sz, surface_sz))
17
18    ball = pygame.image.load("ball.png")
19
20    # Use an extra offset to centre the ball in its square.
21    # If the square is too small, offset becomes negative,
22    # but it will still be centered :-)
23    ball_offset = (sq_sz-ball.get_width()) // 2
24
25    while True:
26
27        # Look for an event from keyboard, mouse, etc.
28        ev = pygame.event.poll()
29        if ev.type == pygame.QUIT:
```

```

30         break;
31
32     # Draw a fresh background (a blank chess board)
33     for row in range(n):          # Draw each row of the board.
34         c_indx = row % 2          # Alternate starting color
35         for col in range(n):      # Run through cols drawing squares
36             the_square = (col*sq_sz, row*sq_sz, sq_sz, sq_sz)
37             surface.fill(colors[c_indx], the_square)
38             # Now flip the color index for the next square
39             c_indx = (c_indx + 1) % 2
40
41     # Now that squares are drawn, draw the queens.
42     for (col, row) in enumerate(the_board):
43         surface.blit(ball,
44             (col*sq_sz+ball_offset, row*sq_sz+ball_offset))
45
46     pygame.display.flip()
47
48
49     pygame.quit()
50
51 if __name__ == "__main__":
52     draw_board([0, 5, 3, 1, 6, 4, 2])    # 7 x 7 to test window size
53     draw_board([6, 4, 2, 0, 5, 7, 1, 3])
54     draw_board([9, 6, 0, 3, 10, 7, 2, 4, 12, 8, 11, 5, 1]) # 13 x 13
55     draw_board([11, 4, 8, 12, 2, 7, 3, 15, 0, 14, 10, 6, 13, 1, 5, 9])

```

There is one more thing worth reviewing here. The conditional statement on line 50 tests whether the name of the currently executing program is `__main__`. This allows us to distinguish whether this module is being

run as a main program, or whether it has been imported elsewhere, and used as a module. If we run this module in Python, the test cases in lines 51-54 will be executed. However, if we import this module into another program (i.e. our N queens solver from earlier) the condition at line 50 will be false, and the statements on lines 51-54 won't run.

In Chapter 14, (14.9. Eight Queens puzzle, part 2) our main program looked like this:

```

1  def main():
2
3      bd = list(range(8))      # Generate the initial permutation
4      num_found = 0
5      tries = 0
6      while num_found < 10:
7          random.shuffle(bd)
8          tries += 1
9          if not has_clashes(bd):
10             print("Found solution {0} in {1} tries.".format(bd, tries))
11             tries = 0
12             num_found += 1
13
14  main()

```

Now we just need two changes. At the top of that program, we import the module that we've been working on here (assume we called it `draw_queens`). (You'll have to ensure that the two modules are saved in the same folder.) Then after line 10 here we add a call to draw the solution that we've just discovered:

```

1  draw_queens.draw_board(bd)

```

And that gives a very satisfying combination of program that can search for solutions to the N queens problem, and when it finds each, it pops up the board showing the solution.

17.4. Sprites

A sprite is an object that can move about in a game, and has internal behaviour and state of its own. For example, a spaceship would be a sprite, the player would be a sprite, and bullets and bombs would all be sprites.

Object oriented programming (OOP) is ideally suited to a situation like this: each object can have its own attributes and internal state, and a couple of methods. Let's have some fun with our N queens board. Instead

of placing the queen in her final position, we'd like to drop her in from the top of the board, and let her fall into position, perhaps bouncing along the way.

The first encapsulation we need is to turn each of our queens into an object. We'll keep a list of all the active sprites (i.e. a list of queen objects), and arrange two new things in our game loop:

- After handling events, but before drawing, call an update method

on every sprite. This will give each sprite a chance to modify its internal state in some way — perhaps change its image, or change its position, or rotate itself, or make itself grow a bit bigger or a bit smaller.

- Once all the sprites have updated themselves, the game loop can begin drawing - first the background, and then call a `draw` method on each sprite in turn, and delegate (hand off) the task of drawing to the object itself. This is in line with the OOP idea that we don't say "Hey, *draw*, show this queen!", but we prefer to say "Hey, *queen*, draw yourself!".

We start with a simple object, no movement or animation yet, just scaffolding, to see how to fit all the pieces together:

```

1  class QueenSprite:
2
3      def __init__(self, img, target_posn):
4          """ Create and initialize a queen for this
5              target position on the board
6          """
7          self.image = img
8          self.target_posn = target_posn
9          self.posn = target_posn
10
11     def update(self):
12         return                # Do nothing for the moment.
13
14     def draw(self, target_surface):
15         target_surface.blit(self.image, self.posn)

```

We've given the sprite three attributes: an image to be drawn, a target position, and a current position. If we're going to move the spite about, the current position may need to be different from the target, which is where we want the queen finally to end up. In this code at this time we've done nothing in the update method, and our draw method (which can probably remain this simple in future) simply draws itself at

its current position on the surface that is provided by the caller.

With its class definition in place, we now instantiate our N queens, put them into a list of sprites, and arrange for the game loop to call the `update` and `draw` methods on each frame. The new bits of code, and the revised game loop look like this: